

62701

GOVERNMENT OF INDIA

DEPARTMENT OF ARCHAEOLOGY

CENTRAL ARCHÆOLOGICAL
LIBRARY

CALL No. 913-3924 G / Bea

ACC. No. 62701

D.G.A. 79

GIPN-S4-2D. G. Arch. N. D./56.-25-9-58-1,00,000.



TURKEY BEYOND THE
MAEANDER

AN ARCHAEOLOGICAL GUIDE

TURKEY BEYOND THE MAEANDER

AN ARCHAEOLOGICAL
GUIDE

GEORGE E. BEAN

62701

913.39246

Bean



LONDON/ERNEST BENN LIMITED
TOTOWA/NEW JERSEY/ROWMAN
AND LITTLEFIELD

*First published 1971 by Ernest Benn Limited
Bouverie House · Fleet Street · London · EC4*

*Published in the USA 1971 by
Rowman and Littlefield*

*Distributed in Canada by
The General Publishing Company Limited · Toronto*

© George E. Bean 1971

Printed in Great Britain

ISBN 0 510-03211-7

ISBN 0-87471-038-3 (USA)

Central Archaeological Library,
New Delhi.

Acc. No 62701
Date 29.9.71
Call No 913.3924.6
bea

Foreword

THE REGION dealt with in the present work lies immediately to the south of that covered in my earlier book *Aegean Turkey*, corresponding almost exactly with the ancient Caria and largely with the present *vilâyet* of Muğla. Tralles and Nysa are actually north of the Maeander, but are included for the traveller's convenience.

It is a fascinating country, with a character of its own. Apart from the large cities, more or less purely Greek, it is full of smaller places that never entirely lost their Carian nature. I have not attempted to include all of these, and my selection is to some extent arbitrary; even of those included many, I fear, will not often be visited. But those excluded will be visited even less.

On many, even most, of the larger sites excavations are at present in progress, so that this book must inevitably be in some degree out of date even before it appears. This is obviously unavoidable; were I to wait till these excavations were finished, others would no doubt have begun. With hardly an exception I have myself visited all of the places discussed, many of them repeatedly, most of them recently, but some not for many years; if changes are found to have occurred I ask the reader's indulgence.

I have followed the same method of presentation as in *Aegean Turkey* and *Turkey's Southern Shore*, and have observed the same lower limit of time, in general about A.D. 300; some critics have complained that readers would welcome a continuation into Byzantine and Turkish times, but in this matter I must stand firm. Such merit as these books possess must derive largely from their dealing with places and periods with which I am familiar.

Turkey is becoming steadily more popular with tourists. Roads and hotels are constantly improving, as also are facilities for camping; but in the area treated in the present volume (with one or two exceptions, such as Aphrodisias and Hierapolis) busloads of visitors are still a rarity. A word of

warning to campers may not be amiss. The organised camping sites are for the most part adequate and often good; but it is most unwise to set up camp by the wayside or in remote parts. Every year unpleasant cases of molestation occur when this rule is disregarded, and fatalities are by no means unknown.

As before, I have written primarily for the traveller, actual or potential; for a comprehensive treatment of the country scholars must await the publication of Professor L. Robert's vast work *La Carie*. One volume of this was produced in 1954, with the expectation of others to follow in quick succession, but so far nothing more has appeared.

I may, I hope, be forgiven for not repeating here, in connexion with the use of ancient buildings, what I have already said elsewhere; similarly in the historical summary matters previously dealt with are here briefly dismissed. It may, however, be worth while to repeat again the rules for pronouncing Turkish names. These are: in general, consonants are pronounced as in English, vowels as in German, with these exceptions: c = English j; ç = English [t]ch; ş = English sh; ğ after soft vowels = English y, after hard vowels it merely lengthens them. The dotless ı resembles the indeterminate vowel-sound in the English *borough* or *again*. In speaking Turkish names the stress should be spread more evenly over the syllables than is done in English; in particular, the penultimate syllable is rarely stressed.

The photographs were taken by me; the text-figures are by my wife.

Contents

FOREWORD	page 5
GLOSSARY	15
1 <i>Historical</i>	17
2 <i>Mylasa</i>	31
3 <i>Around Mylasa</i>	45
<i>Euromus</i>	45
<i>Olymus</i>	48
<i>Chalcetor</i>	48
<i>Hydae</i>	49
<i>Pecin Kale</i>	50
<i>Ceramus</i>	53
4 <i>Labraynda</i>	58
5 <i>Iasus</i>	69
6 <i>Cindya and Bargylia</i>	82
7 <i>Stratoniceia</i>	88
8 <i>Lagina and Panamara</i>	94
<i>Panamara</i>	98
9 <i>Halicarnassus</i>	101
10 <i>The Myndus Peninsula</i>	115
<i>Myndus</i>	116
<i>The Six Lelegian Towns</i>	119
<i>Caryanda</i>	126
11 <i>Syangela-Theangela</i>	128
12 <i>Cnidus</i>	135
13 <i>The Rhodian Peraea</i>	153
14 <i>Caunus</i>	166
15 <i>Alabanda</i>	180

Bharatya Saktiya sadan on 29/7/22 1564/385/1077/22

16	<i>Alinda and Amyzon</i>	190
	<i>Amyzon</i>	198
17	<i>Gerga</i>	201
18	<i>Tralles and Nysa</i>	208
	<i>Nysa and Acharaca</i>	211
19	<i>Aphrodisias</i>	221
20	<i>Hierapolis</i>	232
21	<i>Laodiceia and Colossae</i>	247
	<i>Colossae</i>	257
	SHORT BIBLIOGRAPHY	260
	INDEX	263

List of Plates

[In one section between pages 64 and 65]

- 1 Mylasa. Baltalı Kapı
- 2 Mylasa. Temple of Zeus (Carius?)
- 3 Mylasa. Wall of the precinct of Zeus Osogos
- 4 Mylasa. Berber İni
- 5 Mylasa. Gümüşkesen; Roman tomb
- 6 Euromus. The Temple
- 7 Peçin Kale. Early Wall
- 8 Ceramus. City Wall
- 9 Labraynda. Andron of Idrieus
- 10 Labraynda. Fountain-house
- 11 Labraynda. The Sacred Way
- 12 Labraynda. Temple of Zeus Labrayndus
- 13 Iasus. Street and Houses
- 14 Iasus. The Land-Wall
- 15 Iasus. The Theatre
- 16 Iasus. Newly-excavated Mausoleum
- 17 Bargyia. The Theatre
- 18 Stratoniceia. The Sarapeum
- 19 Stratoniceia. City Gate
- 20 Stratoniceia. Tombstone in the Museum
- 21 Bargyia. Altar
- 22 Halicarnassus (Bodrum). 'Ox-hide' ingot
- 23 Bodrum. Block of frieze from the Mausoleum
- 24 Bodrum. Castle and Harbour
- 25 Bodrum. The Castle of the Knights
- 26 Bodrum. The Castle Ramp

[In one section between pages 144 and 145]

- 27 Lagina. Gate of the Temple Precinct
- 28 Syangela (Alâzeytin). Lelegian houses
- 29 Syangela. Chamber-tumulus
- 30 Theangela. Door of cistern
- 31 Myndus. 'Lelegian' Wall
- 32 Theangela. Tomb (of the dynast Pigres?)
- 33 Loryma. The Fortress
- 34 Cedraeae. Wall and Tower
- 35 Cedraeae. The Theatre
- 36 Cnidus. Round Temple, probably of Aphrodite, in 1969
- 37 Amos. View from Acropolis
- 38 Caunus. Rock-tombs
- 39 Idyma. Rock-tomb
- 40 Caunus. View over the Harbour; western acropolis on left
- 41 Caunus. The Long Wall
- 42 Caunus. Newly excavated building
- 43 Alabanda. The Theatre
- 44 Alabanda. Council-House
- 45 Alabanda. Aqueduct
- 46 Alabanda. Temple of Apollo Isotimus in 1939
- 47 Alinda. Market-hall and Agora
- 48 Alinda. The Theatre
- 49 Alinda. Half-buried Stage of the Theatre
- 50 Alinda. Interior of the Market-hall
- 51 Alinda. Aqueduct
- 52 Alinda. Tomb in use as a house
- 53 Alinda. Tower in the City Wall

[In one section between pages 224 and 225]

- 54 Bridge at İncekemer
- 55 Gerga. Inscribed rock
- 56 Gerga. Speaker's Platform (?)

- 57 Gerga. Pyramidal Stele
- 58 Gerga. Colossal statue on western hill
- 59 Gerga. Temple
- 60 Gerga. Fountain-house (or tomb?)
- 61 Nysa. The Theatre
- 62 Nysa. The Library
- 63 Acharaca. The Charonium (?)
- 64 Aphrodisias. The Stadium
- 65 Aphrodisias. Sarcophagus
- 66 Aphrodisias. Temple of Aphrodite
- 67 Aphrodisias. Columns of the Agora
- 68 Aphrodisias. Baths of Hadrian
- 69 Aphrodisias. Bull's Head
- 70 Aphrodisias. Sarcophagus
- 71 Hierapolis. Petrified Cascades
- 72 Hierapolis. The Sacred Pool
- 73 Hierapolis. Sculpture in the Theatre
- 74 Hierapolis. Triumphal Arch and Main Street
- 75 Hierapolis. The Plutonium
- 76 Laodiceia. Water-tower, showing remains of pipes
- 77 Laodiceia. The Aqueduct
- 78 Amyzon. The City Wall

List of Illustrations in Text

1	Districts of Asia Minor	<i>page</i> 21
2	Plan of Mylasa. <i>After A. and T. Akarca</i>	40
3	Ceramus. Sculptured Base	56
4	Ceramus. Inscription at Kurşunlu Yapı	57
5	Plan of Labraynda. <i>After the Swedish Publication</i>	62
6	Labraynda. Male Sphinx, in the depot	67
7	Plan of Iasus	76
8	Bargylia. Causeway and Acropolis Hill	84
9	Plan of Bargylia	86
10	Plan of Stratoniceia. <i>After P. Trémaux, 1874</i>	91
11	Lagina. Plan of the Temple	97
12	Plan of Halicarnassus	111
13	Bodrum. Stone Anchor in Museum	114
14	Map of the Myndus Peninsula	115
15	Myndus. Harbour and Peninsula from the Acropolis Hill	118
16	Plan of Myndus	119
17	Plan of Pedasa (Gökçeler)	121
18	Lelegian Chamber-Tomb (?)	129
19	Theangela. Plan of the Fort at D (Tetrapyrgon)	130
20	Plan of Theangela	132
21	The Cnidian Aphrodite	141
22	Plan of New Cnidus	149
23	Loryma. Plan of the Castle	160
24	Loryma. Pyramidal Block	162
25	Plan of Caunus	176
26	Plan of Alabanda	185
27	Alabanda. Theatre	186
28	Alabanda. Council-House	187

29	Plan of Alinda	193
30	Alinda. The Second Acropolis	197
31	Gerga. Plan of the Village Centre	202
32	Gerga. Plan of the Temple	204
33	Gerga. Statue	205
34	Gerga. Base	206
35	Plan of Nysa	213
36	Nysa. Plan of First Floor of the Library. <i>After Graefinghoff</i>	216
37	Nysa. Dolphin and Boy at the School at Sultanhisar	217
38	Acharaca. Plan of the Temple (conjectural)	219
39	Plan of Aphrodisias. <i>By courtesy of Professor K. T. Erim</i>	224
40	Aphrodisias. Part of the Inscription over the North Gate	226
41	Aphrodisias. Plan of the Baths (approximate only)	230
42	Map of the Environs of Denizli	233
43	Plan of Hierapolis	239
44	Hierapolis. Relief in the Theatre	243
45	Hierapolis. Plan of the Martyrium of St. Philip	244
46	Plan of Laodiceia	252
47	Laodiceia. Plan of the Nymphaeum	254
	<i>General Map</i>	<i>facing page 262</i>

Glossary

Acroterium. An ornament placed at one of the angles of a pediment.

Analemma. The end wall of the cavea of a theatre.

Anta. A short projecting wall, treated as a pilaster; *in antis*, 'between antae', used of the columns of a temple or other building.

Ashlar. Masonry of squared blocks in horizontal courses.

Basilica. [1] In Roman architecture, an oblong building with central nave flanked by colonnaded aisles and an apse at one end, used for public business. [2] A church of this form.

Cavea. The auditorium of a theatre.

Cella. The main chamber of a temple, in which the cult-statue stood.

Conventus. A provincial court of justice, or the place where this was held.

Deme. A subdivision of a city's territory; a village.

Dentil frieze. A frieze consisting of a row of alternate square projections and square spaces.

Diazoma. A horizontal passage across the cavea of a theatre.

Epistyle. Architectural members laid on top of a row of columns.

Exedra. A semicircular recess or alcove furnished with a bench.

Hellenistic period. The period from the time of Alexander to that of Augustus.

Hypocaust. Under-floor heating. See *Aegean Turkey*, p. 230.

Isodomic. Laid in courses of equal, or almost equal, height; applied to ashlar masonry.

Neocorus. Title given to a city by virtue of the possession of a temple of the Imperial cult.

Odeum. A small theatre-like building used for musical recitals, lectures or rehearsals.

Opisthodomus. The rear chamber of a temple, often used to house the temple-treasure.

Palaestra. An open court for athletic exercise.

Parodoi. The side-entrances to a theatre, between the cavea and the stage-building.

Pediment. A triangular space like a gable, set over a colonnade or other architectural feature.

Peribolus. The enclosure round a temple.

Pilaster. A rectangular column.

Podium. A solid base on which a structure is erected.

Pronaos. The front chamber of a temple, usually on the east.

Propylon, Propylaea. A monumental gateway.

Return Wall. A wall turning at right-angles from the end of another wall.

Stele. A narrow slab of stone set upright and generally bearing decoration or writing or both.

Stylobate. The stone pavement on which a row of columns stands.



Historical

WHO WERE the Carians?

Ancient Greek belief was that they lived originally on the islands of the Aegean and from there migrated to the mainland of Asia. The Cretan account, as reported by Herodotus, was that they were subjects of Minos, king of Crete, not tributary but manning his fleet when required to do so, and were called at that time Lelegians; later, when the Dorians and Ionians spread from Greece to the islands, they expelled the Carians to the coast of Asia. Strabo's account is similar. Thucydides agrees that they were islanders and says they practised piracy, but disagrees in regarding them as having been expelled by Minos himself. For their occupation of the islands he advances a piece of archaeological evidence: when the island of Delos was 'purified' during the Peloponnesian War—that is, all burials were removed from it—more than half the dead were recognised as Carians both from the manner of their burial and from the armour buried with them. This evidence has not in fact been confirmed by modern archaeology; the early culture of the Cyclades (of which Delos is one) shows a character not Carian but Cretan and Mycenaean.

The Carians themselves, however, would have none of this. They maintained that they had always lived on the mainland and had always been called Carians, and they advanced their own evidence: there was at Mylasa an ancient sanctuary of Carian Zeus, to which, besides Carians, only Mysians and Lydians were admitted; these, they claimed, were historically akin to themselves, and had never been other than mainlanders. Scholars today are much inclined to believe that in this matter the Carians were in the right.

However this may be, the Carians in early times appear to

have been a maritime folk; there was in antiquity a strong tradition of a 'Carian thalassocracy', dated by Eusebius (about A.D. 300) to the latter part of the eighth century B.C. Nothing whatever is recorded either of the leaders of this rather nebulous sea-power or of its achievements.

In Homer's *Iliad* the Carians appear as allies of the Trojans; he calls them 'barbarous of speech' and places them around Miletus and Mt. Mycale. Homer, as Thucydides noted, never speaks of 'barbarians' in the usual sense of non-Greeks; presumably then he is not distinguishing them from other Trojan allies who spoke Greek, but merely refers to the exceptional harshness of their language. (As a coincidence it may be remarked that the dialect of Muğla today is the harshest in the west of Turkey.) Strabo rejects this explanation, but only on the inadequate grounds that Carian included many Greek words mixed with it.

Homer's location of the Carians around Miletus and Mycale is confirmed by Herodotus, who places Miletus, Myus and Priene in Caria and, writing in the present tense, says that they speak a common language, which was presumably Carian. Now in Herodotus' time, and no doubt also in Homer's, these were Greek cities and members of the Ionian League, whose official language was certainly Greek; evidently there was still a considerable element of the former Carian population who continued to speak in their own tongue. The Milesians themselves, according to Pausanias, believed that their country was originally occupied by Carians, until some Cretan refugees from Minos arrived under their leader Miletus, after which the two races merged.¹ In any case these cities were normally reckoned Ionian, and the boundaries of Caria were quite clearly defined, on the north by the Maeander and on the south by the present lake of Köyceğiz.

Closely associated with the Carians at all times were the Lelegians. In the ancient literature these people appear in many parts of the Greek world, east and west of the Aegean; but in many cases they were used, like the 'Pelasgians', merely as a stopgap, and were put in when in fact nothing was known. A certain amount, however, seems to be established firmly

¹ Minos was traditionally dated to the middle of the fifteenth century.

enough. Herodotus and Strabo agree that Lelegian is an earlier name for the Carians; elsewhere they are distinguished, and in fact there can be no doubt that they were distinct. For Homer they are clearly so; he places them far from Miletus in the southern part of the Troad, where their king, Altes, holds the city of Pedasus on the Satnioeis. From here, after the Trojan War, they moved southward, leaving traces of their presence on the way,¹ till they settled finally in the Carian country around Halicarnassus. Here they founded eight cities, of which the ruins, with their distinctive masonry, still remain; of these some account is given below in Chapter Ten. One of them bears the name Pedasa, an obvious echo of the city of Altes.

In their relations with the Carians all accounts agree that they held a subordinate position. Pausanias calls them 'a part of the Carian race'; Strabo says they served the Carians as soldiers and became scattered all over Greece, so that the nation disappeared; Philip of Theangela, itself a Lelegian city, calls them servants of the Carians and compares them with the Spartan helots. Culturally too they seem to have been inferior; not a single Lelegian inscription has ever been found, and to judge by the ruins of their cities their interests were confined to the mere business of living and dying; nothing is found but houses, walls and tombs.² Some attempts have been made by modern scholars to explain the name, of which perhaps the most attractive connects it with the Luwian *lulahi*, 'barbarian'; but nothing is certain. In the absence of inscriptions their language is equally unknown.

It is not impossible that the Lycians also were for a time at home in Caria. It was generally agreed in antiquity that the Lycians came from Crete with Sarpedon, brother of Minos, when he was expelled by the latter; and a tradition with the respectable authority of Ephorus recorded that they made their way first to Miletus, of which they were the founders. From here they will have moved, perhaps some centuries later, to the country which they finally occupied. Now the Lycians called themselves in early times Termilae, and some scholars have thought that the syllable mil-, recurring in Miletus, Mylasa and

¹ Miletus, for example, was called Lelegeis.

² Even sanctuaries are very rare.

Milyas (the old name for Lycia), marks their passage southwards. If the statement that they founded the Carian town of Idrias, later Stratoniceia, has any real basis, it will go to support this theory.

One or two Carian customs are mentioned. They are said to have taught the Greeks the use of crests on helmets and of handles on shields, which previously were worn slung over the shoulder; and it was their practice not to take their women with them to dinner. This last, however strange it may have seemed to the Greeks, would raise no eyebrows in Turkey.

The Carian language is still not understood. This is chiefly due to the paucity of material; only two or three dozen inscriptions in the Carian language and script have so far been discovered, many of them very short or fragmentary, and little real progress has been made in their decipherment. The script is almost certainly alphabetic, not syllabic; some of the letter-forms are identical with Greek, but even here there is no guarantee that their phonetic value is the same; others are peculiar to Carian. It is still disputed whether the language is Indo-Germanic or not, nor has the meaning of any single word been convincingly determined.

Of the successive waves of migration, Aeolian, Ionian and Dorian, from Greece to Asia after the Trojan War, the Dorian was the last and southernmost. It occupied the islands of Rhodes and Cos and a few places on the mainland. A league of six cities was formed, known as the Dorian hexapolis; it included Cos and the three cities of Rhodes, and on the mainland Cnidus and Halicarnassus, and it met periodically at the festival of Triopian Apollo on the territory of Cnidus. Other Dorian settlements, such as Iasus, were not included. The degree of fusion between the newcomers and the native population seems to have varied. At Halicarnassus the Carian names known from the inscriptions form half of the total, whereas at Cnidus they are virtually unknown.

But this Greek colonisation touched only the coast. The interior remained Carian, and Caria was a land of villages. When the country begins to feature in our historical records we find a few places that may fairly be called cities—Mylasa, Alabanda, Alinda, Ceramus and no doubt others—and for the rest a great

number of villages grouped in local federations, each containing a principal village together with the smaller places in the neighbourhood. By the sixth century at least there had developed also some kind of national federation; at least, as



FIG. 1 Districts of Asia Minor

Herodotus tells us, when danger threatened from the Persians the Carians met to decide their policy at a spot called White Pillars, which appears to have been a regular meeting-place. The common sanctuary of the federation was the temple of Zeus Carius at Mylasa. In the earlier records we hear simply of 'the Carians'; the word 'federation' occurs only later.

In the course of the seventh and sixth centuries the Lydian kings had subjugated all the Greek cities of the west coast, including the Dorian cities of Caria. In 546, however, Croesus, the

last king of Lydia, was defeated by the Persians and his kingdom came to an end. The Persians at once set about replacing the Lydian rule with their own, and sent to the west coast an army under their general Harpagus. Having dealt with Ionia Harpagus advanced into Caria, where he met with opposition only from the little Lelegian town of Pedasa; the Greek cities gave no trouble.

A generation later the Ionians organised a revolt against the Persian king, and with some hesitation the Carians joined them. The revolt was wretchedly conducted and failed utterly, ending ignominiously with the capture of Miletus in 494. The Persians then sent an army south under Daurises to suppress the rebel Carians. At their meeting at White Pillars the Carians decided on resistance, but were defeated beside the river Mar-syas; reassembling at Labraynda, where some Milesians joined them, they resolved to fight again. A second defeat cost them the loss of Mylasa, but still did not break their spirit; when Daurises advanced southward to attack the Carian towns around Halicarnassus—and no doubt primarily the Pedasans, who had given trouble before—he contrived to become benighted, and his force was ambushed by the Carians and destroyed.

A few years later came Darius' invasion of Greece, which failed at Marathon, and ten years later again, in 480, the second attempt by Xerxes, defeated at Salamis and Plataea. The Athenians thereupon established their maritime league, known as the Delian Confederacy, which later turned into an Athenian empire; in this virtually all the cities and towns of the Aegean coast, Caria included, were enrolled. Each was required to pay a fixed sum in tribute (or in a few cases supply ships), with the avowed object of preventing a revival of the Persian power on the coast. The sums at which the various places were assessed give a fair indication of their relative wealth and importance at that time.

The defeat of Athens by Sparta in the Peloponnesian War (404 B.C.) put an end to the Delian Confederacy. The Spartans attempted for a time to keep the coast of Asia under their own control; but they had not the qualities to manage an overseas empire, and in 387 B.C., by the treaty known as the King's

Peace, all the cities of Asia were recognised as belonging once more to the Persians.

About this time, following an Athenian naval victory over the Spartans in 394 B.C., a group of Aegean cities formed an alliance among themselves, apparently with the object of securing independence from Persians, Spartans and Athenians alike. The members were Rhodes, Samos, Ephesus, Cnidus, Iasus and Byzantium. This league, if it may be so called, is not recorded by any historian, but is known only by the coinage which it issued. It did not survive for long; even before the King's Peace it seems to have been dissolved.

The vast Persian Empire was divided into regions called satrapies, and the first satrap of Caria was a man of Mylasa by the name of Hyssaldomus; he was succeeded by his son Hecatomnos, and in 377 by the latter's son Mausolus. Mausolus was an able, energetic and ambitious man, and he took advantage of the great distance of his satrapy from the Persian capital to make himself virtually an independent ruler, though he never actually took the title of king. He was not unopposed in Caria itself, for we hear of plots against his life, and on one occasion in 367 'the Carians'—that is evidently the Carian federation—sent an envoy to the Great King, possibly to complain of his conduct. The King, however, took Mausolus' part, and in the other cases the plotters were punished with death or exile.

Mausolus' capital was at Mylasa, the principal city of inland Caria and his own home town. Seeing, however, the much finer position of Halicarnassus, he decided to rebuild that city on a much grander scale and make it his headquarters. This was one of the first steps in the great plan to which his life was devoted, nothing less than the Hellenisation of the whole of Caria. The old Lelegian towns of Myndus and Syangela he rebuilt on new sites with a greatly enlarged area; the others he suppressed and transferred their inhabitants to Halicarnassus. At the extremities of his satrapy he fortified Latmus and Caunus with splendid walls, replacing the Carian name of the former with the Greek name Heracleia. He was active also in the Greek cities of the coast; we have decrees passed in his honour at Iasus and even at Ionian Erythrae, though they give no details, but

merely refer to him as a benefactor. Inner Caria, too, would no doubt have been treated in similar fashion, but Mausolus died comparatively young in 353 B.C., and this part of his work remained uncompleted.

Nor was much done in this way by the members of his family who followed him. He had two sisters and two brothers; the elder sister, Artemisia, was also his wife, and it was she who built his tomb, the Mausoleum. They had no children, and Artemisia succeeded to the rule of Caria; within a few years, however, she died of grief, and the elder brother Idrieus came to power. He married the younger sister Ada, but he, too, quickly died, whereupon the younger brother Pixodarus expelled Ada to exile in Alinda and took command himself. It seems that Pixodarus had not the title of satrap, but ruled unofficially; the official Persian appointee was a man of the name of Orontobates, and Pixodarus called him in to share the government. When Pixodarus, too, died before long Orontobates was left in control, and this was the position when Alexander arrived in 334.

Alexander's conquest of the Persian Empire proceeded with remarkable speed and success. Only in a few places was he vigorously resisted, and one of these was Halicarnassus. After its capture¹ he brought back Ada, with whom he had already had friendly dealings², and handed over the whole of Caria to her.

How long Ada's restored rule lasted is not known. By the time that Alexander's successors had begun to fight for the country she had disappeared. Alexander died at Babylon in 323, leaving the vast territory he had conquered without a ruler. His generals proceeded to divide it among themselves, but before long they grew dissatisfied with the region allotted to them, and for a generation they warred constantly against one another. Prominent among them, and among the most ambitious, were Antigonus and Lysimachus, but their successes were not lasting; eventually three permanent kingdoms were established, those of Macedonia with Greece, of Egypt under the Ptolemies, and of Syria under the Seleucids, with kings named either Seleucus or Antiochus. Western Asia

¹ See below, pp. 107-8.

² See below, p. 190.

Minor, not falling clearly within any of these, continued to be a bone of contention among all of them.

To these three powers two others must be added, namely the kingdom of Pergamum, established soon after 280 B.C., with kings named Eumenes or Attalus, and later the Rhodians, who had built up a considerable sea-power. The history of Asia Minor during the third century is exceedingly confused, and consists largely of a struggle between the Ptolemies and Seleucids; their main interest was naturally concentrated on the Greek cities, whose support was useful to them, and many places changed hands more than once. Some account of the fortunes of the individual cities will be found below.

As the power of Egypt and Syria weakened during the course of the century, the others began to take a hand. The Rhodians had acquired a considerable area of territory on the mainland opposite their island, and Attalus I of Pergamum, after breaking the Seleucid authority, had by about 227 B.C. extended his rule as far south as Caria, though without establishing himself firmly. At this point, perhaps in order to check any further progress by Attalus, Antigonus III of Macedon, called Doson, made an expedition into Caria. This was not a conquest; he met with no opposition and was well received by the cities, which acted independently. In effect he found the country without a ruler, apart from the somewhat enigmatic figure of Olympichus. This man had been a general of Seleucus II, and had held the country around Mylasa in his name. About 245 B.C. Seleucus decided to grant Mylasa freedom and ordered Olympichus to evacuate the district. This, however, he failed to do, for whatever reason; instead, he seems to have made himself into an independent dynast. Antigonus left him undisturbed, and when Philip V became king of Macedon in 220 Olympichus maintained good relations with him. His authority was in any case very limited, and the cities did not recognise him as their ruler. How long he lived is not known, but by 201 at least he has disappeared from the scene.

In that year Philip himself came to Caria. By a series of raids in the Aegean and the Black Sea he had incurred the hostility of Rhodes and Pergamum, and these combined to defeat him in a sea-battle off Chios. Philip thereupon took an

army into Caria, where at least he expected to be well received, in view of the previous good relations established by Antigonos. His campaign, however, was badly mismanaged; he found himself beleaguered in Bargylia by the Pergamene fleet for the whole winter, and was glad to escape the following spring.¹

It is during the third century that we first hear of a second Carian federation, known as the Chrysaoric League. This was common to all Carians and was organised on the old village-system, so that each city's voting strength depended on the number of villages on its territory. The League met to discuss its affairs at the sanctuary of Zeus Chrysaoreus near Stratonicēia.² Its relation to the old Carian League is not clear, but since the latter continued at least down to the first century B.C., the two federations must have existed simultaneously. When the Chrysaoric League was first founded is not known; it may well have been older than the foundation of Stratonicēia, but the earliest actual evidence for it is a newly discovered inscription of 267 B.C.

Philip V's restless energy soon brought him into conflict with the growing power of the Romans, who were just beginning to interest themselves in the affairs of Greece. In 197 B.C. a pitched battle ended with the defeat of Philip, after which the Roman commander ostentatiously declared that all Greek cities, both in Europe and in Asia, should be free.

Antiochus III of Syria, however, was not impressed by this proclamation. In the same year, 197, in a rapid campaign he overran the south and much of the west coast of Asia Minor in a determined effort to regain the old Seleucid empire. His activity had the result of bringing the Roman armies for the first time into Asia, and in 190 at the crucial battle of Magnesia-under-Sipylus Antiochus was utterly defeated. By the treaty of Apamea which followed, Caria and Lycia were given to the Rhodians and the rest of western Asia Minor to Eumenes of Pergamum.

Rhodian control continued for twenty years and was bitterly resented from the start. The Lycians especially resisted continuously, and in 167 B.C. the Carians, too, organised a revolt.³

¹ See below, p. 85.

² See below, p. 89.

³ See below, p. 34.

The revolt failed, but in the same year the Roman Senate issued a decree declaring Caria and Lycia free.

Freedom lasted until 133 B.C., when Attalus III bequeathed the kingdom of Pergamum to Rome. This unprecedented gesture, which has been compared with that of a captain scuttling his own ship, was not allowed to pass unchallenged. A certain Aristonicus, claiming kinship with the royal house, at once attempted to secure the kingship for himself. After some successes he was suppressed by the Romans, who thereupon, in 129 B.C., organised the Pergamene territory as the province of Asia. In this province Caria (but not Lycia) was included.

The Roman provincial government was highly unsatisfactory, chiefly owing to the cupidity of the governors and of the Roman merchants and bankers who found abundant opportunities for enriching themselves. Accordingly, when in 88 B.C. the king of Pontus on the Black Sea, Mithridates VI, decided to overrun the province, he was in most places welcomed as a liberator. By his command all the Romans in the province, together with their families, were ruthlessly butchered, to the number, it is said, of 80,000 persons. The Roman defence was at first feeble, but in 85 Mithridates was finally worsted in the field and expelled from Asia. His second attempt twelve years later did not reach as far as Caria.

The civil wars in Rome during the first century B.C. cannot be recounted in detail here. The murder of Julius Caesar in 44 B.C. was followed by a bad time for the provincials. The 'tyrannicides' Brutus and Cassius, finding themselves for the moment in supreme power, and regarding the provinces in the usual way as a convenient source of wealth and manpower, proceeded to the east to raise money and troops. Back in Rome, however, Mark Antony had roused the people's feelings against the murderers, and in 43 he, together with Octavian, the great-nephew of Caesar, and Lepidus, another of Caesar's supporters, were appointed 'Triumvirs for the ordering of the State'. Their first act was to proscribe the enemies of Caesar. Brutus and Cassius, faced with inevitable war, redoubled their exactions from the provincials, requiring from them a levy equal to ten years' normal taxes. The clash came in 42 B.C. at the battle of

Philippi, where Antony and Octavian were victorious, both Brutus and Cassius being killed.

The victors then divided the world between them, the east falling to Antony. This change proved no blessing to the provincials. Antony at once adopted an arrogant, quasi-royal style, taking the title of 'Latter-day Dionysus', and among other things repeating Brutus's demands for the equivalent of ten years' taxation. Before long, however, he fell under the spell of Cleopatra, queen of Egypt, and betook himself to the pleasures of the palace at Alexandria.

Asia was thus left unguarded, and this afforded an opportunity for an event without parallel in Roman history. Brutus and Cassius, when the showdown with the Triumvirs was imminent, in their desire to raise forces had gone so far as to approach the Parthians, Rome's most formidable enemy, for assistance. They sent as their envoy a young man by the name of Labienus. He proved a good negotiator, but before he could bring them aid from this source Brutus and Cassius were dead. Nevertheless, the Parthian king was persuaded to send a force against the Romans, and Labienus was put at its head (40 B.C.). The undefended province of Asia quickly fell a prey to the barbarians under their Roman commander, though resistance was offered in a few places;¹ Caria in particular suffered severely. In face of this inroad Antony found himself obliged to leave Cleopatra's side; in 39 he sent a strong force to Caria to deal with it. Labienus hastily withdrew to Cilicia, whither he was pursued, brought to battle, defeated and put to death.

Free again to return to the charms of Alexandria, Antony proceeded to excesses which finally led to his downfall. Led on by the ambitious Cleopatra, he declared her children by Caesar and himself nominal rulers of the various regions of the east, and himself as virtual monarch of the inhabited world. This was too much for Octavian, who resolved that his old ally must be suppressed. War followed, and at the sea-battle of Actium in 31 B.C., at which Cleopatra was present, she and Antony were decisively defeated.

This was the end of the Roman Republic; in 29 B.C. the Empire was founded, with Octavian, who then received the title

¹ See below, pp. 56, 248.

of Augustus, as the first Emperor. The condition of the eastern provinces at once improved. To Caria, which had suffered more than most, the new Emperor showed himself a good friend; and in general, from now on during the long period of peace which followed, the cities were able to develop their industries and resources and conduct their local affairs in comfort. They were still, as before, under the orders of the governor, except nominally those which were recognised as 'free', 'friends and allies of the Roman People'; but we now hear far less of the exactions and injustices which had disfigured the Republican administration. Most of them grew rich and prosperous, and adorned themselves with the fine buildings whose ruins stand today.

In Caria the smaller, inland cities were at last able to enjoy the benefits of civilisation which Mausolus had not lived to confer on them. Their inhabitants were mainly the old Carian stock; the official language, since Alexander's conquest, was Greek; and as time went on the Roman merchants and others made their way further and further into the interior. Brigandage was still a menace, and continued unruliness in the remoter parts required the establishment of Roman military colonies, though none are known in Caria itself. But the general picture, for the first two centuries of the Empire, is one of contentment and prosperity. Of the provincial Commonalties and their relations with the Emperor, of the worship of the Emperors, and of the multitudinous festivals celebrated annually or quadrennially all over the east, enough has been said elsewhere.¹ In such a long period free from war the cities had naturally little individual history. For the most part an occasional earthquake or a visit from the Emperor is about all there is to record.

Decline set in in the third century. Under a rapid succession of Emperors, some barbarian, many incompetent, most short-lived, the power of the Empire was gradually weakened. The process was accelerated in the middle of the century, first by an appalling plague which raged over the whole Empire for fifteen years, and second by the troublesome inroads of the Goths, who at one time made their way as far south as Miletus. Towards the end of the century the Emperor Diocletian made a

¹ See *Aegean Turkey*, pp. 35-7.

reorganisation of the provinces, by which Caria became for the first time a separate province.

Christianity was on the whole slow to take hold in Caria. The region was not visited by St. Paul, and the only early churches seem to be those of Laodiceia and Colossae on the extreme fringe of the country. It was not, it appears, until Christianity was officially adopted by Constantine that the new religion made any real headway in Caria. The subsequent fortunes of the country belong to Byzantine and Turkish history and are not the business of the present work.



Mylasa

ONLY THREE CITIES of inland Caria are considered 'noteworthy' by Strabo; they are Mylasa, Alabanda and Stratoniceia. The first two of these names, with their old Anatolian endings in -asa and -nda, are sufficient proof of very early foundation; Stratoniceia, on the other hand, Greek in name and foundation, was not yet 300 years old in Strabo's day.

A theory held by certain scholars was mentioned above¹ which connects the name of Mylasa with the passage of the Lycians from Miletus to their final home in the south. This theory is by no means proved, and there is nothing else to suggest a Lycian origin for Mylasa, which is indeed generally thought of as the most Carian of all cities. Stephanus of Byzantium in his *Ethnica*² says that she took her name from a certain Mylasus, son of Chrysaor and a descendant of Sisyphus and Aeolus—an impressive but unsubstantial genealogy. Apart from this obvious fabrication nothing is recorded of the city's origin. Its earliest historical mention is at the beginning of the seventh century, when a Mylasan by name Arselis is said to have helped Gyges in his contest for the throne of Lydia; even at that early date Carians were serving as mercenaries.

Under Persian rule from the middle of the sixth century the individual cities were governed by tyrants appointed with Persian approval, and in 500 B.C. the tyrant of Mylasa was a certain Oliatus, son of Ibanollis. In the Persian fleet led by Aristagoras, tyrant of Miletus, against the island of Naxos³ this Oliatus served as a ship's captain; following the failure of the attack Aristagoras determined upon revolt against the Great King, and began by capturing by means of a trick a

¹ See above, p. 19.

² See below, p. 191, n. 1.

³ See *Aegean Turkey*, p. 225

number of the captains, tyrants of their various cities, including Oliatus. What was done with him does not appear, as he is not mentioned again, but Mylasa, like most of the Carians, joined in the revolt; and a few years later, when the Persian army sent to suppress them was ambushed and destroyed, the Carian leader was a brother of Oliatus named Heraclides. Whether this man had succeeded his brother as tyrant of Mylasa is doubtful; he is heard of once again, when he is said to have fought at Artemisium. Scholars are divided in opinion as to whether this refers to the battle fought by the Greeks against the Persians in 480 B.C. or to another Artemisium in Spain; in any case it seems evident that Heraclides felt it wise to escape from Persian vengeance by withdrawing from Asia.

In the Confederacy of Delos, founded in 478, Mylasa may or may not have been an original member; her situation comparatively far inland, and the flight of Heraclides, suggest the probability that she had fallen back into Persian hands. Later she was included, and from 450 to 440 paid regularly a tribute of one talent or rather less. This assessment, though lower than that of several of the Lelegian towns on the Myndus peninsula, indicates that Mylasa was even at this early date the leading city in her own district; her neighbours Euromus, Hydae and Chalcetor were all assessed at a much lower figure. After 440 the Athenians removed all these places from the list of members, and by the end of the century, if not much earlier, the whole of inland Caria was once more under Persian control.

The days of Mylasa's greatness followed in the early fourth century under the dynasts (officially Persian satraps) Hyssal-domus, Hecatomnos and Mausolus; Mylasa was at once their home town and their capital. The spectacular career of Mausolus has been described above, but his rule was not unopposed at home. An inscription found at Mylasa records three decrees passed by the Mylasans in 367, 361 and 355 B.C.; we read in the first that a certain Arlissis, sent by the Carian League on an embassy to the Great King, abused his trust and plotted against Mausolus, for which he was put to death and his property made over to Mausolus himself; in the second, that the sons of Peldemos had insulted the statue of Hecatomnos and had their goods put up to public sale; in the third that one

Manitas son of Pactyes had attempted the life of Mausolus during the annual festival at Labraynda and had been lynched on the spot, that a further investigation had revealed that another man named Thyssus was involved in the plot, and that the property of both was sold for the benefit of Mausolus.

Among the many changes introduced by the Hecatomnids, and especially Mausolus, it is not improbable that we should count the foundation of the city on its permanent site at Milâs. There are reasons for believing that until the fourth century Mylasa stood on the great rock of Peçin, some three miles south of Milâs. This question will be discussed more fully below, but it may be noticed here that the site at Milâs is a most unusual one for an early Carian city, quite unlike the hilltop positions that were generally chosen. Her situation on the plain at the foot of a considerable mountain was thought surprising in antiquity, and a certain Roman governor is said to have exclaimed, 'If the man who founded this city felt no fear, had he at least no shame?' On the other hand, the proximity of the adjacent mountain had the advantage that it afforded an abundant supply of good-quality marble, so that the city was unusually well equipped with fine public buildings. A professional harpist named Stratonicus, whose *bons mots* were famous, once gave a recital in Mylasa, and noticing the great number of temples, prefaced it not with the usual words 'Oyez ye peoples', but with the change of a single letter, 'Oyez ye temples'—as it might be 'Oyez ye steeples'.

In connexion with Alexander's campaign no special mention is made of Mylasa, except that the Athenian statesman Phocion, whose policy was consistently pro-Macedonian, is said to have been offered by Alexander the revenues of four cities in Asia Minor, one of which was Mylasa. Phocion, however, declined.

Even after the transference by Mausolus of the capital to Halicarnassus, and the great enlargement of that city, Mylasa continued to be the chief centre of her own district. She had from ancient times possessed the sanctuary at Labraynda, and the recent Swedish excavations on that site have thrown considerable light on conditions in the third century. Under Ptolemy II the region was claimed as part of the Egyptian

empire, and its affairs were conducted by the Chrysaoric League with Ptolemaic support; the League may possibly for a time have held its meetings at Mylasa, before being moved to Stratoniceia. But the Egyptian control was very weak, and Antiochus II of Syria (261-246 B.C.) had little difficulty in reconquering the country; and one of the first acts of his successor, Seleucus II, was to declare Mylasa a free city. Not that this meant in practice very much. 'Freedom' implied really little more than freedom from occupation by a garrison and the right to administer its own territory, subject always to interference at the king's pleasure. But Seleucid rule was hardly stronger than the Ptolemaic, and some twenty years later the Macedonian king Antigonus Doson (229-221 B.C.) occupied Caria. He was well received at Mylasa, and friendly relations with Macedonia continued during the early years of his successor, Philip V. A letter from Philip, written in 220, was found at Labraynda confirming the Mylasan possession of the sanctuary. Later, in 201 B.C., after Philip's defeat at sea by the combined fleets of Rhodes and Pergamum, he made his way to Caria; during the following winter, beleaguered in Bargylia and at his wits' end for the means of feeding his army, he was helped by the Mylasans with supplies. Failing, however, to obtain further assistance, he turned upon the city and made an attack on it, though without success. It appears that the Mylasans had reverted to the Seleucid cause under Antiochus III, who a few years afterwards occupied the country almost without resistance.

Some years later, in 189 B.C., after the defeat of Antiochus, when the Roman delegates at Apamea gave Caria to the Rhodians, they expressly declared Mylasa to be free from payment of tribute. Despite this relief the Mylasans were no more pleased than the other Carians with Rhodian rule, and in 167 B.C. they organised a rebellion. Seizing 'the cities in Euromus' (that is, Euromus itself, Olymus, Chalcedon and perhaps some others) they obtained help from Alabanda; but their combined forces were promptly engaged and defeated by the Rhodians at Orthosia. The rebellion was evidently spreading, for Orthosia lies away to the north-east beyond the river Marsyas. But all this was at once rendered meaningless by the Roman decree in

the same year that the Rhodians should withdraw and Caria be left free.

During the comparatively peaceful period which followed, Mylasa, now somewhat overshadowed by her neighbour Stratoniceia, took occasion to improve her standing. Already as early as 209 B.C. she had requested and obtained from Miletus a treaty of 'isopolity', that is a grant of reciprocal citizenship; she now proceeded to bring all the cities in her neighbourhood under her own control by means of treaties of 'sympolity'. The men of Euromus, Chalcedon, Hydae, Olymus and Labraynda now became citizens of Mylasa, and were allotted to one of the three tribes of that city. These tribes were a very ancient institution at Mylasa; back in the fourth century we find decrees ratified by 'Mausolus and the three tribes', and their names are thoroughly Carian: the Otorcondeis, the Conodorcondeis and the Hyarbesytæ. They were subdivided into clans, with equally outlandish names, and these again into families.

Quarrels about territory were always common between Greek cities, and in 143 B.C. when Priene and Magnesia disputed a piece of land, Mylasa was selected by the Roman praetor to act as adjudicator. This was something of a compliment for a Carian city, and shows the extent to which she was by this time accepted into the Hellenic sphere. Mylasa herself had about the same time a similar quarrel with Stratoniceia, which was referred for settlement to Rome.

In the Roman province of Asia, Mylasa, like Alabanda, was chosen as the seat of a *conventus*, that is a centre where the provincial governor held assizes; and in general relations with Rome were good and friendly. Nevertheless, Mylasa could not escape from the effects of the unsatisfactory government under the Roman Republic, and by the middle of the first century B.C. the city was in debt to a Roman banker named Cluvius and unable to meet her commitments.

At this same period Mylasa's affairs were controlled by two distinguished citizens by name Euthydemus and Hybreas. 'Both', says Strabo,

were orators and popular leaders. Euthydemus inherited from his family great wealth and distinction, to which he added personal ability, and so attained to great honour not

only in his own country but all over Asia. Hybreas, on the other hand, was left by his father a pack-mule and its groom; with these for a time he made his living, then after studying under Diotrophes of Antiocheia he returned home and served under the clerk of the market. Having by this means made a little money he entered politics, and rapidly acquired influence, both in Euthydemus' lifetime and more especially after his death, becoming indeed the city's leading statesman. Euthydemus, however, while he lived, was by far the more dominant, and used his power for the city's good; so that even though there was a touch of the tyrannical in his methods, this was fully compensated by the resulting benefit. In this connexion a saying of Hybreas was much applauded: 'Euthydemus', he said, 'you are a necessary evil for our city, for we can live neither with you nor without you'. Hybreas, despite his great reputation and his services to his city, came to grief by his opposition to Labienus;¹ for when the Parthians were already in control of Asia, and Labienus arrived with a Parthian army, most of the cities, being peaceable and unarmed, submitted to him, but Zeno of Laodiceia and Hybreas refused and roused their cities against him. Hybreas furthermore provoked Labienus, a foolish and irascible youth, by a certain answer he made: when Labienus declared himself emperor of Parthia, 'Then', said Hybreas, 'I call myself emperor of Caria'. Labienus thereupon attacked the city. Hybreas himself he failed to capture, as he had withdrawn to Rhodes, but he wrecked his house with all its fine belongings, and ravaged the whole city. When he had gone from Asia Hybreas returned and set about restoring his own fortunes and those of Mylasa.

It was nevertheless some time before Mylasa recovered from this disaster. In 31 B.C., when Augustus (then called Octavian) after his final victory at Actium was sojourning in Samos, the Mylasans sent an embassy to him reminding him of the citizens they had lost as prisoners slaughtered by Labienus, of the holiest of their temples destroyed, of their territory ravaged and their farms burned. Augustus' reply was engraved on stone

¹ See above, p. 28.

by the Mylasans, from which it may be inferred that it was favourable; but the stone is now broken and we do not know what help he may have given. It is, however, likely that it was at this time, or soon after, that the temple of Rome and Augustus was erected which was still standing in the eighteenth century. Some years later the city was still in financial straits and compelled to borrow money from its own citizens.

Under the Empire, here as elsewhere, prosperity returned, and Mylasa, like the other cities, has little or no individual history. Coinage continues down to the third century, and later the city was the seat of a bishopric under the metropolitan of Aphrodisias.

The principal deity of Mylasa was Zeus, who was worshipped under three titles, two of them with an alias. The first is Zeus Carius, whose cult was the most important in early times before the advent of the Hecatomnids. He had, as Herodotus tells us, an ancient sanctuary at Mylasa, to which, besides Carians, their traditional kinsmen the Lydians and Mysians were also admitted, but no others, even if they spoke Carian. He was the god of the 'Commonalty of the Carians', a league which survived, though with reduced importance, at least down to the first century B.C. His temple and sanctuary have been identified by some scholars with the great enclosure on the east slope of the hill of Hisarbaşı in Milâs;¹ but it has recently been proposed to locate it on the rock of Peçin outside Milâs on the south.

The second is the Zeus of Labraynda, called either Zeus Labrayndus or Zeus Stratius. He, too, is mentioned by Herodotus, who notes that Zeus was not worshipped elsewhere under the title Stratius. His cult, though ancient, was a purely local affair until it was adopted wholeheartedly by the Hecatomnids, who greatly increased the splendour of the sanctuary at Labraynda (described by Herodotus as a large and sacred grove of plane-trees), raised the cult to be the most revered in Mylasa, and stamped the figure of the god on their coins. On these he is shown standing, in Greek dress, with a double axe (*labrys*) over his right shoulder and a long spear in his left hand. These weapons mark his character as Stratius, or 'military'.

¹ See below, p. 41.

Later coins, however, show the actual cult-statue of wood which stood in the temple. This is of very archaic appearance, reminiscent in some ways of the Ephesian Artemis; the bearded deity stands stiffly with his feet together, swathed from the waist downwards in a criss-cross of bands like a mummy; in his hands are the double axe and spear; on his head is a cylindrical headdress (*polos*); he wears a necklace and a kind of breastplate with numerous breast-like protuberances. The last three of these features are essentially feminine, and consort oddly with the beard and the weapons; and it has been suggested that the Zeus of Labraynda must at a very early date have been in a manner fused with a female deity who preceded him. The crossed bands have been compared with the network pattern on the omphalos-stone at Delphi, which would mean that Zeus at Labraynda had oracular functions; this question will be mentioned again below,¹ but others prefer to see a connexion with the Egyptian Osiris. From the fourth century onwards Zeus Labrayndus, or Stratius, was an outstanding deity of the Carians.

The third is Zeus Osogos,² the only one of the three who is strictly Mylasan. He was more particularly the god of the tribe Otorcondeis, but his cult was in effect the most important in Mylasa itself, and his renown extended over all Caria and even beyond. He stands on a par with Zeus Labrayndus; on the coins of Mylasa the two gods' attributes are often combined, and the same man might on occasion be priest of both. His sanctuary stood just outside the city³ and was remarkable for a strange phenomenon; it possessed a spring of salt water, though the sea is ten miles away. It appears that the water had originally been fresh but had changed its nature; Theophrastus rather naïvely attributes this change to the frequency of thunderbolts in the region. Whether because of this phenomenon, or perhaps more likely because the Carians had once been a maritime people, Zeus Osogos had to a great extent the character of a marine deity; his special attributes are the trident and the crab, and some scholars have sought to explain

¹ See below, pp. 65-6.

² Or *Osogoa*; the form varies in the sources.

³ See below, pp. 41-2.

the Carian name Osogos by a connexion with the sea¹. The trident was the emblem of the sea-god Poseidon (inherited by Britannia), and the Greeks, always ready to identify barbarian deities with their own, combined his name with that of Zeus and called the Carian god Zenoposeidon. This composite name excited remark in ancient times as a curiosity; it was naturally never used by the Otorcondeis themselves. Athenaeus tells a pleasing story in this connexion. A certain musician by name Dorion paid a visit to Mylasa but had difficulty in finding lodging; he sat down to rest in a sanctuary outside the gates, and seeing the sacristan about his duties asked the name of the god. 'Zenoposeidon,' was the reply. 'No wonder then,' said Dorion, 'that a mere mortal cannot find a bed, when even the gods have to double up.'

Zeus Osogos possessed, besides his temple and sanctuary, a considerable landed estate. A series of inscriptions dating to the first century B.C. record the sale of land to the temple by private owners; in most cases the ex-owner then rents the land from the temple for his own use. This practice, which was common around Mylasa and elsewhere, reflects the general shortage of money among the citizens in the early years of the province of Asia. The temples, however, seem to have managed well enough.

Mylasa has suffered the usual fate of a city continuously inhabited since antiquity, and very little now remains of the many temples and other buildings mentioned by Strabo. Of the city walls nothing at all survives, though they are known to have existed, and for their position we have three clues only: the handsome gate now called Baltalı Kapı; the fact that the temple of Zeus Osogos stood 'in front of' (outside) the city; and the situation of the numerous tombs, which may be supposed to have lain, as usual, outside the walls. The position of the gate suggests that the wall may have run up to the Topbaşı Hill (and perhaps also to the Yeldeğirmeni Hill), then southwards and round between the Augusteum and the present Orta Okul, then bending northwards past the foot of the Hıdırlık Hill.

¹ The element *-og-* has been compared with Okeanos, the ocean, and with the island Ogygia. This cannot be considered established.




Fig. 2 Plan of Mylasa

The unusually weak situation of the city has been noticed above; but it was to some extent compensated by a subsidiary fortification on the Hıdırlık Hill just to the west. The upper part of this hill was enclosed by a ring-wall whose line may still be followed, except in the south-eastern part, where it has disappeared. It is 8 feet thick and stands up to 8 feet high in places; the masonry is a very irregular ashlar. There are no surviving traces of buildings in the interior. This fortified enclosure must have served as a refuge for the people in time of danger.

Baltalı Kapı, dating probably from shortly before the Christian era, still stands virtually intact (Pl. 1). It takes its name from the double axe which is represented on the key-stone of the arch on the outer (northern) side. The decoration of the piers consists of a row of flutes surmounting a row of palmettes. An aqueduct was carried over the gate, but this dates from a later period.

Of the many temples originally possessed by Mylasa, scanty remains of one only may now be seen. This has one column still erect and stands on the east slope of the Hisarbaşı Hill in the middle of the town. The column (Pl. 2), a handsome specimen of the Corinthian order, stands on a podium some 11 feet high of which only the east face is now visible. A flight of steps on the north side could be seen until recently. There is a panel on the column as if for an inscription, but nothing can be read. The temple was surrounded as usual by an extensive precinct. The eastern wall of this, overlooking the canal, still stands for the whole of its length, about 100 yards, to a height of eleven courses in places; the masonry is a regular ashlar. This temple, like the Baltalı Kapı, probably dates to the reconstruction of the city after the sack by Labienus in 40 B.C. It is not known with certainty to what deity it belonged. All probability points to Zeus, and a fragmentary dedication was found close by inscribed 'to Zeus . . .', but the distinguishing epithet was broken away. Not, surely, Zeus Osogós, whose precinct stood outside the city; presumably then Zeus Cariús or Zeus Stratiús. Most scholars are inclined to prefer the former.

The temple of Zeus Osogós has quite disappeared, but its

position is known; it stood outside the city wall on the south-west. Not a single stone of the temple itself has ever been seen in modern times, but a part of the wall of the surrounding precinct still exists. It stands to the west of the Güveç Dede Türbesi in the quarter of Hacı İlyas; all this part of the town is now built over, and the wall is mostly hidden among the houses and gardens. It is a fine polygonal wall, still some 10 feet high in places, constructed of large blocks; one of its stones measures 9 feet by 3 feet 8 inches (Pl. 3). Masonry of this kind dates normally to the fifth century B.C. Nothing more can be seen today, but formerly, when this was open ground, there stood a row of columns extending at right-angles from near the south end of the wall; in 1881 there were fourteen, in 1933 only two. These belonged to a stoa which once surrounded the precinct. Four of them were inscribed with the names of priests of 'Zeus Osogos Zeus Zenoposeidon'; another recorded that a certain ex-priest of Zeus presented eight columns to Zeus Osogos. The style of the script, and the Roman names of the priest, show that this colonnade must date to the Imperial period. At the house of Ismail Hakkı Bey, close beside the wall, the writer in 1970 saw two column-stumps, much battered and nearly buried, but said to be each about 6 feet long; whether these may be remnants of the stoa in question he could not determine. Of the famous spring of salt water nothing has ever been seen.

A third temple, that of Augustus and the deified Rome, was seen and described by early travellers. Wheeler's companions in 1675 saw 'a fair temple of marble', with the dedication on the architrave. His drawing shows six Ionic columns on the front, with leaf decoration at the top and bottom of the shafts. The position of this temple, a little north of the present Orta Okul, has recently been determined by means of an inscription, but nothing of it now remains.

A theatre was, of course, an essential feature of all Greek cities of any size. That of Mylasa was situated on the east slope of the Topbaşı Hill, outside the city; but all that survives is the hollow in the hillside. Excavations on the west side of this hill brought to light theatrical masks, and showed furthermore that a shrine of Nemesis must have stood close by.

Otherwise the visible ruins of Mylasa are restricted to tombs. Two of these at least are well worth a visit. The best known is that called Gümüşkesen, on the western fringe of the town (Pl. 5); it is now approached by a broad road. It is a handsome two-storeyed building dating probably from the same period as the Baltalı Kapı, in the late first century B.C. The upper storey is surrounded by an open colonnade, with a square pilaster at each corner and two partially fluted oval columns on each of the four sides; the decoration is similar to that of the Baltalı Kapı. The roof is formed of five layers of blocks, with each layer placed diagonally across the angles of the one below, and decreasing upwards in size to form a shallow pyramid. The underside is adorned with plants and geometric shapes, and is thought to have been originally painted. The lower storey, the actual grave-chamber, has a wall of broad-and-narrow masonry and contains four pillars supporting the floor of the upper storey. The door is on the west side towards the north end, and is now closed with a grille, which is usually kept locked. An interesting feature is a small funnel-shaped hole in the floor of the upper chamber, evidently intended for the pouring of libations to the dead man in the tomb below. To see this it is necessary either to clamber up to the upper storey or to find the guardian who holds the key.

Some two miles to the south of the town at a spot called Süleyman Kavağı, on the left of the road from Milâs to Güllük, is an interesting rock-tomb, well deserving of a visit. It is cut in the east face of a fair-sized hill, just below the summit, looking directly across to Peçin Kale, some fifteen minutes' climb from the gate of the modern cemetery by the roadside. It is known locally as Berber İni or Berber Yatağı (Pl. 4).

The tomb is in two parts, a rock-cut façade in temple form, with two engaged unfluted Doric half-columns flanking a false door, with architrave and pediment above, and below this the tomb itself, with its own plain door. The doorstone is lying outside. Inside are two long benches on right and left; they measure 12 feet by three. At the back is a much smaller chamber, again with its own door; the floor is sunk 16 inches

below that of the outer chamber, and on either side is a ledge some 5 inches wide and 15 inches above the floor. This sunken pit is 5 feet 8 inches long by internal measurement.

There is no inscription, but it has been suggested that this fine tomb, unique in this region, may be that either of Hyssal-domus or of Hecatomnos. The great man would be laid in the rear chamber, while the roomy-benches in the outer chamber would be reserved for his relatives or dependants. On the spot the writer felt some doubt of this, chiefly owing to the modest dimensions of the inner chamber, which Miss Akarca even calls an 'alcove for votive offerings'; if the dead body was laid in a coffin (let alone a sarcophagus) he must have been of distinctly short stature. On the other hand, it is unlikely that he would be required to mix with the others in the outer room. But in fact it seems probable that in tombs of this kind it was usual simply to lay the embalmed corpse on the floor or benches; in countless similar tombs in various parts of Asia Minor the writer cannot remember ever having seen any sign of a sarcophagus on the benches. There is also presumably the possibility that the actual grave is not in the tomb at all, but hidden somewhere close by. The question therefore remains open.



Around Mylasa

OF THE SMALLER cities in the neighbourhood of Milâs, namely Hydae, Chalceator, Olymus and Euromus, all the sites are known, but with the exception of the last their ruins are unspectacular. All were independent cities in early times, and all were enrolled in the Confederacy of Delos, with much lower assessments for tribute than Mylasa. Most of their names had at that time a somewhat different form. They were all, towards the end of the second century B.C., united with Mylasa in a 'sympolity', that is a mutual community of citizenship.¹ By such an arrangement each city in principle kept its independence, but in practice it was common for one of them to exercise a preponderance which might on occasion amount to subjection or even absorption; and such was undoubtedly the case with Mylasa. Otherwise these smaller cities have little or no individual history; they merely shared in the fortunes of the country as a whole.

EUROMUS

Some seven or eight miles from Milâs towards Bafa, at Ayaklı, close to the road on the east side, the traveller's eye is caught by the columns of a temple, still standing to the number of sixteen. This was at first thought to be the temple of Zeus of Labraynda, but in fact marks the site of Euromus. This was the most considerable city in the region after Mylasa in early times. It controlled the northern part of the plain, and seems at one time to have given its name to a wide area, for the historian Polybius once refers to 'the cities in Euromus'. These presumably included Olymus and Chalceator. In the

¹ See above, p. 35.

fifth century the name appears as Kyromus or Hyromus; the Greek form Euromus, 'strong', is likely to date from the Hellenisation of the country which resulted from Mausolus' policy. At the same time it is remarkable that as early as the fifth century B.C. and as late as the first the city's name appears sometimes in the form Europus.

In the revolt of Mylasa against the Rhodian domination in 167 B.C. Euromus and her neighbours were forcibly involved;¹ the Mylasans seized their cities, presumably in order to suppress any local opposition. The Mylasan success was short-lived, but the sympolity which followed before the end of the century was of more account. It seems to have offended the men of Heracleia, Euromus' neighbours on the north; an inscription tells us that they had raided the territory of Euromus and carried off sacred and private property; a Euroman citizen who had suffered in this way complained to the authorities in Mylasa, who thereupon sent one of their citizens as ambassador to Heracleia and succeeded in obtaining satisfaction. It is noticeable that the Euromans do not act on their own account, but prefer to apply to Mylasa; and the inscription observes that the ambassador 'secured the interests of the city'—that is of Mylasa. The inequality of the sympolity is very evident.

This union of the two cities did not last. Quarrels broke out; another inscription records that on one occasion the Mylasans, alleging apparently that the Euromans had broken some agreement, demanded from them an indemnity of fifty talents, and Euromus felt obliged to turn to the Romans and the Rhodians.

Having recovered her independence, Euromus appears to have flourished, for the extant ruins, battered though they are, attest considerable prosperity. The coinage extends from the second century B.C. to the second A.D.

On the ground today the outstanding feature is the temple, which is among the half-dozen best preserved in Asia Minor (Pl. 6). It is in the Corinthian order, and dates from the second century A.D. It had originally eleven columns on the long sides and six on the short; of these, sixteen are still

¹ See above, p. 54.

standing complete with their architrave, in groups of eight, five and three. The three on the south side, and the south-west corner column, are unfluted, no doubt because the work was never quite finished. Most of the columns, on the west and north sides, have a panel with a dedicatory inscription; five were presented by a certain Menecrates, state physician and magistrate, together with his daughter Tryphaena, and seven by Leo Quintus, also a magistrate. On the south side a piece of the cornice with a lion's-head water-spout is still in place. An excavation, begun in 1969, has revealed the foundations of an altar in the usual position in front of the temple on the east, and has made a start on clearing the jumble of blocks in the interior. Among the most interesting discoveries is an inscription of Hellenistic date recording an honorific decree to be set up in the temple of Zeus Lepsynus. This tells us not only the name of the god who possessed the temple, but also that the present building is not the first to be erected on the site. The epithet Lepsynus is new and, like Osogós, un-Greek. The excavation continues.

The temple is outside the city, which occupied the ground to the north. A hundred yards from the temple, on a slight rise, is a handsome round tower in good ashlar masonry, belonging to the city wall; the wall itself may be followed from here, curving round northwards over the hillside, with other towers at intervals. It is in general 8 to 9 feet thick, having two faces with headers and rubble filling. A wall of this quality can date little, if at all, after 300 B.C. It enclosed a considerable area, nearly a quarter of a square mile; some distance to the north it descends into the plain, crosses a ridge and comes down to the road, then runs southward parallel to the road on its west side for 700 yards before turning east to join the round tower near the temple.

In a recess in the hillside, a little above the plain, is the theatre, quite large but badly ruined; it faces west. Five rows of seats remain visible, best preserved on the north; of the stage-building a corner of the substructure survives, with five or six courses standing. The agora or market-place stood on the flat ground surrounded on all four sides by a stoa, some of whose columns are still erect. Further west is another stoa. On

one of the pillars is a long inscription, very hard to read, recording the financial services to the city of a certain Callisthenes and mentioning an alliance with Iasus. Close to the road is a large, rather shapeless building of late date, probably a baths. Finally, beside the path leading from the road to the temple, are several underground tomb-chambers handsomely constructed and roofed in the Carian manner with huge slabs. Other buildings in more or less ruinous condition will be noticed, but nothing more is identifiable.

OLYMUS

Although nothing now remains visible above ground, the site of Olymus is fixed with certainty by the great number of inscribed and other ancient stones which are found a little below the surface. It lies five miles north-north-west of Miläs and three miles east of Euromus across the hills, at or near the village of Kafaca (Kafci). In the Delian Confederacy the city's name appears as Hylimus.

The principal deities were Apollo and Artemis, who shared a temple; they were worshipped under the title of 'gods of the people of Olymus'. The site of this temple is recognisable as a mound rising a few feet above the ground, but it has never been excavated. The form of the cramps joining the blocks found here suggests a date in the Hellenistic period. The temple possessed a considerable area of land, much or most of which was obtained by purchase from private owners; these frequently continued to work the property as tenants of the temple. Numerous leases of this kind have been discovered.

It is possible that the city itself was situated on the hills above the village, although no ruins have been found; in this case the temple was outside the city, like that at Euromus and that of Zeus Osogós at Mylasa, and many others.

CHALCETOR

About six miles from Miläs on the way to Bafa a road turns off to the left to Karakuyu and the ruins of Chalcetor. This was never a city of any consequence; apart from its membership

of the Delian Confederacy all we know of its history is that it was instructed by one of the Hellenistic kings to enter into sympolity with another city; the name of the second city is lost, but is likely to have been Euromus. This might help to explain Polybius' curious phrase 'the cities in Euromus'. Later, of course, both were united with Mylasa. The name Chalceator is to all appearance Greek, meaning 'with heart of bronze'; but it is likely to be a Graecised form of an earlier Anatolian name.

Shortly before reaching Karakuyu the road passes through the necropolis of Chalceator; the villagers will readily act as guides. The acropolis of the city is on a pine-clad hill of fair height called Yaz Tepesi, from which a ridge runs down to the modern road; it is about half an hour's climb. Nothing is preserved apart from the ring-wall, well built of squared blocks in the Lelegian manner. Two other fortresses defended the city; they are something over a mile away by the hamlet of Köşk, and are called respectively Asar and Kale. Their walls of dry rubble are surprisingly thick, as much as 12 and 15 feet, but are nowhere preserved to a height of more than 5 feet.

At the foot of the ridge, close to the road, are the scanty remains of the temple of Apollo. Lying on the ground are a large block with dentil frieze and a fluted column-drum, Ionic or Corinthian, 5 feet high and 2 feet in diameter, but little more. Here was found the inscription recording the sympolity, and another including the name Chalceator; and in 1968 the writer found there a Carian text in three lines which has not yet been interpreted.

The tombs in the necropolis are of various types. Some are underground chambers like those at Euromus, solidly constructed of stone blocks, with roofing slabs up to 9 feet in length, and in some cases with layers of small stones on top. Others are shallow graves, quite plain, and in one place a sarcophagus with disc-and-festoon relief is standing in the middle of a field.

HYDAE

Recorded in the Delian Confederacy in the form Kydae, and united later in a sympolity with Mylasa, this small city has no

other history. Its site, unknown until 1933, is located in the valley of the Sarıçay west of the Sodra Dağı at the village of Damlıboğaz. The name is certainly Anatolian,¹ and occupation of the site was much earlier than the earliest record, as is proved by a small hand-made jug found at Damlıboğaz and dating to the third millennium B.C. This is now in the museum depot at Milâs. As at Olymus, the city's principal deities were Apollo and Artemis, who here also shared a temple; they were called 'ancestral gods', which may indicate that they are old Carian deities assimilated to the Greek. Here as elsewhere the river was deified, and the coinage shows a river-god representing the Sarıçay; its ancient name was the Cybersus.

Not very much remains to be seen on the spot. The acropolis hill, directly above the village, is of moderate height; the summit carries a ring-wall now largely reduced to a pile of stones, but standing in places up to 8 feet. The entrance is on the south-east, and outside the wall on the south-west are one or two plain rock-tombs. Other tombs, some dating to the Hellenistic period, are frequently found by digging in the village.

On the plain in front of the village is a flat heap of ruins, only a few feet high, which it has been thought may represent the temple of Apollo and Artemis. The plan of the building is not now easy to make out, and the identification must be regarded as quite uncertain.

PEÇİN KALE

The visitor to Milâs who is not unduly pressed for time should not fail to spend half a day on a visit to Peçin Kale. About three miles to the south of Milâs this great flat-topped rock rises abruptly from the plain to a height of some 700 feet; it is easily ascended on the west side by a paved and stepped road of Turkish construction. The place was an important stronghold of the Menteşe dynasty in the fourteenth century, and the extensive summit carries, in addition to the powerful

¹ Even though the next village is called Yaşyer, 'Wet Place', it would be a mistake to connect the name Hydae with the Greek word for water.

fortress, a number of Turkish buildings, among which the *medrese* of Ahmet Gazi is especially worth a visit.

But ancient remains also are not lacking. Below the castle on the east is a short stretch of early wall in handsome bossed ashlar masonry (Pl. 7); whether this is part of a ring-wall or merely a terrace wall cannot now be determined. And just inside the entrance to the castle, on the right, a flight of six solid marble steps is preserved, which is recognised to have belonged to an ancient temple, and one of fair size. It is accordingly clear that there was here at least a sanctuary in ancient times, and it has generally been thought that the importance of Peçin in antiquity amounted to no more than this. Miss Akarca in her book on Milâs remarks that Peçin was not then a place of any consequence. But recently Professor J. M. Cook has shown reason to revise this estimate, and to believe that this was in fact the site, or at least the citadel, of Mylasa until the fourth century B.C. Professor Cook's arguments are briefly as follows.

Sherds found on the site range in date from the seventh to the early fourth centuries, and include a good proportion of Attic black-glazed vessels, indicating a site of some importance by Carian standards. The wall and temple-steps are not accurately datable, but sherds of Hellenistic and Roman date are remarkable by their absence. On the other hand, an obsidian blade-core picked up in the writer's presence in 1968 suggests occupation on the site as far back as the Early Bronze Age around 2000 B.C.¹

Among the ancient historians Herodotus tells us only that there was in Mylasa an ancient sanctuary of Zeus Carius, but Strabo has rather more to say; he speaks of Mylasa and her two sanctuaries of Zeus Osogos and Zeus Labrayndus, then continues:

these then are peculiar to the city, but there is a third sanctuary of Zeus Carius, common to all Carians and shared

¹ Professor Colin Renfrew of Sheffield University, for whose expert advice I am very grateful, reports that it is a worked-out blade-core of a type common in Greece and the Cyclades, but rare in the eastern Aegean. It is likely to have come from the island of Melos, with a possible range of date from 3000 to 1500 B.C.

by the Lydians and Mysians as kinsmen. It is said (*or there is said*) to have been a village in olden times, with the ancestral home and palace of the Hecatomnids.

The editors of Strabo have always assumed that the subject of the last sentence is the city of Mylasa (which in Strabo's day was of course at Milâs); but the historian *seems* to be distinguishing the village from the city of his own time; and it is much more satisfactory to suppose that he is recording a tradition that Mylasa, with the temple of Zeus Carius, once stood on the hill of Peçin. The temple is then the one whose steps are still to be seen, the same which is recorded by Herodotus.

If this is right, it is virtually certain that the move down to the new site at Milâs was made by Mausolus. In accordance with his policy of Hellenising Caria he moved the position of a number of cities, notably Myndus and Syangela. And Peçin is a far more suitable town-site than Milâs for the Carians of early times, who chose invariably to live on hill-tops. One other piece of evidence may be suggestive. An ancient writer passing under the name of Aristotle informs us that Mausolus at one time collected contributions to pay for the erection of a city wall, the city being then unfortified—as it would naturally be if the site was in fact a new one.

Professor Cook is careful to observe that this suggestion is not yet proved beyond a doubt. If it is right, pre-Mausolan remains at Milâs should be lacking in any considerable quantity. A few early pieces have in fact been reported from there, but not enough excavation has been done to determine the presence or absence of a fifth-century city. The temple on Hisarbaşı, as was said above, is likely to have been a temple of Zeus, most probably Zeus Carius; but this is not to say that in Herodotus' time his temple did not stand at Peçin; if it was wrecked (for example) by Labienus in 40 B.C. it might well be rebuilt in the city. It may indeed have been built there when the move was made; so at Cnidus, which changed her site about the same time, new temples were at once erected on the new site.

Until further evidence appears, therefore, we may regard it as probable that when Mausolus embarked on his scheme to change the Carian way of life to something more Hellenic, he began with his home-town Mylasa.

CERAMUS

The north side of the Gulf of Cos towards its east end is formed by the mighty wall of the Kıran Dağ rising sheer from the sea to over 2,000 feet and leaving no room for a road along the shore. Only at one point is this wall broken, where the Koca Çay makes its way down from the plateau above and has formed an alluvial plain or delta at its mouth. Despite its length of over twenty miles this river dries up in summer, and much of the water from the plateau finds its way to the sea by underground channels. In a corner of this plain are the ruins of Ceramus. The delta has spread since antiquity, and the walls still standing on the flat ground are quite deeply buried in their lower parts; it is likely that Ceramus stood originally on or near the sea. Being somewhat difficult of access the site is rarely visited; the alternatives are a jeep trip of some thirty miles from Milâs or a long boat trip from Bodrum. In the latter case the return journey is apt to be rough, when the wind gets up in the afternoon. The ancient name survives in the form Gereme, which is nowadays applied to the country around; the village itself is called Ören, meaning 'ruins', and has the rank of a *nahiye*.

For a city of her size Ceramus is peculiarly devoid of any history. Nothing is known of her foundations, and she was evidently Carian in origin; although her name is identical with the Greek word for 'pottery' or 'tile', this is agreed to be a coincidence only. The city had, however, become in some degree at least Hellenised by the sixth century, as archaic statuary of Greek type has been found there; whether this was due to the city's own initiative or to an unrecorded Dorian settlement is unsure, but in the Hellenistic period (the earliest for which we have evidence) the Doric dialect was not used in the inscriptions. Ceramus was a member of the Delian Confederacy, paying a talent and a half, and later of the Chrysaoric

League, of which indeed she was among the more important members, owing to the large number of villages on her territory. To what extent Mausolus interested himself in Ceramus there is nothing to show, but he can hardly have been indifferent. With the rest of Caria Ceramus was given to Rhodes in 189 B.C. and taken away again in 167; to the period following this belongs the one fragment known of the city's individual history. We learn from an inscription that Ceramus had entered into a sympolity with another city, unnamed but almost certainly Stratoniceia, whose territory must have adjoined hers. Things went badly, however, and Ceramus found herself 'in a difficult situation'; no doubt, as so often happened, the stronger partner began to assert herself unduly; at all events Ceramus found it necessary to apply to Rhodes for an alliance; this was secured by the good offices of the man honoured in the inscription. The choice of Rhodes is interesting, and suggests that the Ceramians at least bore no lasting grudge against their recent masters who had proved so unpopular elsewhere. In the Mithridatic War it appears that Ceramus took the king's side, and was punished by being given in 81 B.C. to Stratoniceia.

The coins range in date from the second century B.C. through the Roman Imperial period. Some of them show a youthful god standing clad in a short tunic and carrying a double axe and a spear; this is evidently a local deity, hard to identify with any Greek god; we shall meet him again below. In some cases he appears together with Zeus Chrysaoreus, the principal deity of Ceramus.

Almost the only Ceramian of any distinction was the runner Polites, who won the stadium, diaulus and long-distance races at Olympia on the same day. In later times Ceramus was one of the many bishoprics attached to the metropolitan of Aphrodisias.

The ruins of Ceramus have suffered sadly in recent years from the depredations of the local inhabitants, and much of what was recorded earlier in this century is no longer to be seen. The city-wall could until recently be followed in all its length; at present a long stretch is visible high up on the rocky mountainside on the east of the city, and on the flat ground on the south it is still standing in part. The masonry is in general

polygonal (Pl. 8), but in some places the upper part was built of squared stones; the unusual effect was accentuated by the difference in material, the polygonal work being of grey limestone, the squared masonry of a yellowish pudding-stone. But of the upper parts virtually nothing now remains. There were numerous gates, mostly arched but in a few cases rectangular; some of these survive. The polygonal work need not imply an early date, nor the arches a late one; the whole wall was no doubt built at one time in the early Hellenistic period. Outside the gates the roads were flanked with tombs in the usual way; some are sarcophagi, others of 'Carian' type sunk into the ground.

On a low hill, very dry and stony, just outside the village, at a spot called Bakıcak, is a site which has produced a good deal of early material. A platform with supporting wall of respectable ashlar masonry carries the foundations of a temple which has almost totally disappeared; only three large blocks remain, lying at different levels on the hillside, so that the form and order of the temple cannot be determined. There is, however, evidence to suggest that it was a temple of Zeus, in all probability Zeus Chrysaoreus. A block was found nearby with a relief of a double axe, the special symbol of Zeus in Caria. And in 1932 the villagers unearthed on the spot a youthful male head in marble, of archaic date and of the type known as *kouros*. It has been attractively suggested that this is the head of the young god who appears on coins in company with Zeus. The head is now in the museum in Smyrna. Other archaic fragments have been found in the same place, and the antiquity of the temple is beyond doubt.

Below the platform on the west a terrace wall was later constructed, the space between it and the platform being divided into chambers by cross-walls; and below this again, at a much lower level, is a second terrace wall, the intervening space being again divided by two cross-walls now mostly destroyed. In the outer face of this lower wall are six large niches with round top. Along the upper terrace wall runs a water-pipe. The purpose of this unusual complex is not clear.

One other temple is known at Ceramus. It lies outside the city-walls about a quarter of a mile to the east, at the foot of

the mountains, and is known as Kurşunlu Yapı. Here the destruction has been particularly lamentable, and the building is now a sorry sight. The temple stood on a platform with supporting wall, which until recently stood to its full height of 20 feet, with a cornice at the top. This is now completely




FIG. 3 Ceramus. Sculptured Base

destroyed. Of the temple itself, in the Corinthian order, many architectural members are lying around; their excellent quality shows that the building must have been very handsome. On no other site has the writer been more depressed by the vandalism which is still only too rife in Turkey. The temple walls were decorated with reliefs showing a round shield enclosed in a wreath, with their inscriptions still legible. One of them reads: 'With good fortune. I, the pious priest Marcus Aurelius Chrysantas, zealously and openhandedly performed my duties towards the gods and the other priests, together with my wife Aurelia Euphrosyne'. The other is similar. Modesty was a quality not expected in documents of this kind.

Other ruins of Roman and Byzantine date meet the eye in various parts of the site, but their purpose is unknown. On the south side of the city, beside a Turkish cemetery, is a small Byzantine church with some remnants of wall-paintings.



FIG. 4 Ceramus. Inscription at Kurşunlu Yapı

Ceramus was not without water, as springs issue at the foot of the mountains, the water coming apparently underground from the plateau above; but a more satisfactory supply was obtained by means of an aqueduct leading from the north. But of this also hardly anything survives.



Labraynda (Labranda)

SOON AFTER 499 B.C. a Persian army under Daurises marched south to suppress the Carians who had supported the revolt of the Ionian cities. A battle was fought by the river Marsyas; the Carians were defeated with heavy losses and retired to the sanctuary of Zeus Stratius at Labraynda. Here they debated whether to surrender to the Persians or to quit Asia altogether, but on the arrival of reinforcements from Miletus they decided to stand and fight again. Again they were defeated, and Mylasa fell into Persian hands. Herodotus describes the sanctuary as a large and sacred grove of plane-trees, and remarks that the Carians are the only people known to sacrifice to Zeus Stratius.¹

His description is far from doing justice to the site as it appears today, and in fact the splendid buildings recently cleared by the Swedish excavators were not erected till more than a hundred years later. They are due to the Hecatomnid rulers Mausolus and his brother Idrieus, who adopted the cult of Zeus Stratius, or Labrayndus, and raised it to an importance which it never afterwards lost.² Herodotus makes no special mention of a temple, and it may well be that there was none at the time of the battle of Labraynda. After Idrieus practically no changes were made until the first century A.D.

The sanctuary belonged from early times to Mylasa, the nearest city and Mausolus' capital, and was in fact joined to it by a Sacred Way, paved with stone and eight miles long, by which at festival time the procession made its way up. At the same time, the priest of Zeus had a certain measure of independence, and was responsible for the administration of the

¹ Zeus Stratius was in fact worshipped, at least in later times, at a number of places in the northern part of Asia Minor.

² See above, p. 37.

temple lands. According to Strabo he was appointed for life from among the notables of Mylasa, but this rule seems to have been abandoned in the course of time and the priesthood became annual.

Mylasan possession of the sanctuary was not, however, altogether undisputed. In the early part of the third century the country was dominated politically by the Chrysaoric League, centred on Stratoniceia and supported by the Ptolemies. An inscription recently found at Labraynda records a meeting of the League in the nineteenth year of Ptolemy II (267 B.C.), though not apparently held at Labraynda itself. Soon after this, however, Antiochus II of Syria (261–247 B.C.) overran the country and brought it under Seleucid control. His successor, Seleucus II, was friendly to Mylasa and granted the city her 'freedom', at the same time confirming her possession of Labraynda. But the priests of Zeus were jealous of their limited independence, and before long, about 240 B.C., we find a priest by the name of Corris complaining to Seleucus that the Mylasans were usurping his privileges and otherwise misbehaving. The king was sympathetic and sent instructions to his governor Olympichus to restrain them. The Mylasans, however, indignantly denied the priest's accusations, whereupon Seleucus held an investigation; the upshot was that Corris was judged to have lied and Mylasa to be in the right.

Twenty years later this incident was almost exactly repeated. In the meantime the Seleucid control had weakened, and Olympichus, though ordered by Seleucus to evacuate the district and leave it to Mylasa, had neglected to do so and had made himself into a independent dynast. This was the situation when the Macedonian king Antigonus Doson occupied Caria in 227 B.C. He established good relations both with Mylasa and with Olympichus, and the latter, after the king's departure, seems to have acted as representative of Macedonia in the region. While Antigonus was in Caria another priest of Zeus, apparently named Hecatomnos, approached him with similar complaints to those of Corris, and obtained from him a letter conveying a favourable reply. Knowing, however, that his claims were in fact false, he suppressed the letter for six years until the king died. When he finally produced it the

Mylasans immediately protested to Antigonos' successor, Philip V, complaining at the same time that the officials of the Chrysaoric League were attempting to appropriate Labraynda in an effort to recover their old dominance. Philip's response was wholly in favour of Mylasa; he sent orders to Olympichus to exclude the Chrysaorians and to restore the sanctuary to the city. This decision was final and, so far as we know, Mylasan possession of Labraynda was never again seriously questioned; the village and sanctuary continued as before to be a part of the Mylasan state.

Early in the first century A.D. a number of buildings were added to the precinct, including baths at the east end and a stoa at the west, the building E on the plan, and probably also the well-house L. Much later a second baths was built on the south side. In the fourth century most of the western part was ruined by a disastrous fire; but the place was not abandoned, and in early Byzantine times a church was built between the eastern baths and Propylaea, largely with material taken from those structures, which by that time must have already collapsed. This church was in its turn destroyed by fire, perhaps about the eleventh century.

Not very much is known about the cult of Zeus at Labraynda. Of the god himself, with his two titles Stratius and Labrayndus, an account was given above;¹ his name is sometimes coupled with that of Hera. It is possible that his sanctuary contained an oracle; of this more will be said later. There is also some evidence that athletic contests were held, and in fact a stadium has recently been recognised on the slope above the temple.

The site of Labraynda is remarkable for its steepness, necessitating numerous artificial terraces, and for its abundance of water, from which at present the town of Milâs is supplied. The sanctuary is set on a steep hillside, with an acropolis on the summit several hundred feet higher up. The acropolis comprises a fortress about 100 yards in length, containing several buildings, all badly ruined and overgrown. Since Labraynda was never a city, only a village, it is thought that this fortress may have been built by Ada while she was

¹ See above, pp. 37-8.

maintaining herself in semi-royalty at Alinda. The altitude is well over 2,000 feet. A passage in a letter from Olympichus to Mylasa reads: 'I restore to you the place and its territory and revenues; and I hand over to you also Petra by Labraynda'. It has been suggested that Petra, 'the rock', may be identified with this acropolis. Although the acropolis must surely be included, if not in the 'place', at least in the territory, it might nevertheless be separately mentioned because Olympichus had maintained a garrison there. But there are at least two other fortresses within a mile or two, and Petra may equally well be one of these.

The material used generally on the site is the local stone, a kind of gneiss; the marble used for facing and other purposes was brought from the Sodra Dağı above Milâs, but is not of first-rate quality.

Herodotus, as was mentioned above, speaks only of a grove of plane-trees; and there are today some fine trees of this kind close to the sanctuary. The earliest temple of Zeus, built perhaps some time in the fifth century, was a simple affair of the type called *in antis*, consisting merely of a pronaos with two columns between the antae, and a cella behind. In the following century this was converted by Idrieus into the building whose foundations have recently been excavated. The walls of the old temple were allowed to stand, with the addition of two short antae at the west end, with two columns between, forming a very shallow opisthodomus; and the whole was surrounded by an Ionic colonnade having eight columns on the long sides and six at front and back. These unusual proportions are due to the fact that the building was not planned for itself but was merely a conversion of an existing structure (Pl. 12).

Though the temple was completed and dedicated to Zeus by Idrieus (part of his dedicatory inscription has been found), it is likely that he was only carrying out a plan conceived by his brother, for it was Mausolus who initiated the great transformation of the sanctuary. Two dedications by him have come to light, namely those of the North Stoa and the Second Andron (F and D on the plan); in each case the god's name appears as Zeus Lambrayndus. If the name is, as is generally supposed, connected with the word *labrys*, a double axe, the 'm' is




FIG. 5 Plan of Labraynda

intrusive, and in fact this form does not occur after the fourth century. In the Hellenistic inscriptions it is consistently Labraynda, and this is also the form found most usually in the manuscripts of the ancient writers from Herodotus onwards. The later inscriptions have commonly Labraeynda, showing that the word had four syllables, not three. The more familiar form Labranda has only inferior authority.

The most conspicuous building on the site is the First Andron (C, Pl. 9), dedicated by Idrieus. This building, which stands in part to its full height apart from the roof, has always been visible, and before the Swedish excavations was supposed to be the temple of Zeus. It is virtually identical in shape and size with the Second Andron built by Mausolus, which is identified as an andron by its inscription. The word means 'a room for the men', that is a sort of men's clubhouse, though no doubt of a more or less religious character. It would be used for banquets at the festival and doubtless for other social occasions. In form it is strikingly similar to the old fifth-century temple, though larger, and is remarkable for its unusually large door and for the number and size of its windows. There are no fewer than ten of these, two in the antechamber, three in each side of the main room, and rather surprisingly two in the wall between the two rooms. This wall is exceptionally thick, over 6 feet, and the windows are more like passages. The building is thus particularly well lit, an obvious advantage when artificial lighting was so inadequate. The windows are fitted with grooves for fixing shutters against the wind and rain. A further peculiarity, found also in Mausolus' andron, is the rectangular niche at the back of the main room. It forms a projection behind the building, and on the inside begins about 7 feet from the floor. Its purpose is uncertain; possibly it held statues. The Second Andron differs from this only in being less well preserved and in having no windows in its north wall, owing presumably to the buildings, called 'annexes' by the excavators, which flanked it on that side.

Adjoining the First Andron on the north is a group of two rooms with a porch and four Doric columns in front; the inscription on the architrave designates them as 'Houses', that is probably dwelling-quarters for the temple clergy. They are


quite well preserved, with the back wall standing to its original height. Like the andron, they were dedicated to Zeus Lambrayndus by Idrieus. At a much later date the roof of the larger room was replaced by a dome of tiles, supported by piers placed in each corner of the room. The smaller room too was used in Christian times, when a marble altar was set against its back wall.

The early terrace-house K was apparently standing in the fifth century B.C., but was demolished in the course of the great reconstruction by the Hecatomnids. It was replaced by the later terrace-house J, which is still quite well preserved, with four rooms and a corridor in front. These were perhaps store-rooms. They are backed against the temple terrace, to which stairs lead up, so that the roof of the house formed a sort of continuation of the terrace.

The eastern part of the temple terrace is an open space bounded on the north by a stoa and at the far end by the 'East House', H on the plan. This house dates back to the fifth century, but little or nothing is known about it. The stoa, on the other hand, was dedicated by Mausolus. It is not completely excavated owing to the modern road which passes just above. The semicircular exedra standing in front of its east end is a much later addition.


In front of the Second Andron is another open terrace flanked on the north by a handsome terrace wall with a well- or fountain-house in its middle (Pl. 10). Behind this wall is another stoa, built by Idrieus, but the fountain-house with its three columns was not added before the first century A.D. At the east end of this terrace is a vast building which has not been excavated; its nature is accordingly not known, though it is conjectured to have been a royal palace. At the other end, beside the Second Andron, is the Third Andron E. This, though similar in form to the other two, is of much inferior workmanship and is poorly preserved; it too dates to the first century A.D. Of the same period also is the West Stoa P.

The south-east corner of the precinct, on a lower level, must have been in the fourth century B.C. just as impressive as the western part, though it is now much less well preserved. From the terrace above a splendid staircase leads down to a central



1 Mylasa. Baltalı Kapı.





4 Mylasa. Berber İni.

2 Mylasa. Temple of Zeus (Carius?)

3 Mylasa. Wall of the precinct of Zeus Osogos



5 Mylasa, Gümüşkesen; Roman tomb.

6 Euromus. The Temple.

7 Peçin Kale. Early Wall.






8 Ceramus. City Wall.

9 Labraynda. Andron of Idrieus.




10 Labraynda. Fountain-house.


11 Labraynda. The Sacred Way.



12 Labraynda. Temple of Zeus Labrayndus.



13 Iasus, Street and Houses,



14 Iasus, The Land-Wall.




15 Iasus. The Theatre.

16 Iasus. Newly-excavated Mausoleum.

17 Bargylia. The Theatre.






18 Stratoniceia. The Sarapeum.

19 Stratoniceia. City Gate.



20 Stratoniceia, Tombstone in the Museum.


21 Bargylia, Altar.



22 Halicarnassus (Bodrum), 'Ox-hide' ingot.



23 Bodrum. Block of frieze from the Mausoleum.



24 Bodrum. Castle and Harbour.



25 Bodrum. The Castle of the Knights.

26 Bodrum. The Castle Ramp.

courtyard with magnificent entrance gateways (propylaea) on the east and south, to which the Sacred Way led up. The stairway is almost 40 feet broad, with twenty-three steps, most of which are still in place. The two entrance gateways appear to be contemporary, both being due to Idrieus. The reason for thus providing two similar entries of such grandeur so close together is not clear, and it has been suggested that the East Propylaea was built first and almost immediately destroyed by an earthquake or other calamity, being replaced by another on the same plan but in a different place. The respective levels of the two structures and the adjoining buildings give some support to this idea.

Close to the South Propylaea on the east are the ruins of a small building called by the excavators the 'Doric House'. It faced north, with four Doric columns on the front, and may possibly have been a treasury; it dates, like the propylaea, to the time of Idrieus. When in Roman times a baths was built just to the east, the house was incorporated in it in such a way that its western half became the tepidarium of the baths, while its eastern half was demolished and made to form part of the hypocaust. The façade was reduced to two columns, the Doric flutes being chiselled away to produce plain round shafts—a remarkable indication of the taste of the times.

Still further down to the south-east, at a level some 100 feet below that of the temple terrace, is the long wall R which seems to have formed the southern boundary of the precinct, and set against it is the interesting building Q. This was in two storeys, the upper containing three rows of seven monolithic granite columns, more than half of which are still standing; the lower storey is filled with a mass of fallen blocks and architectural members. There seems to have been no wall in the upper storey, but merely an open hall forming a kind of canopy to the lower storey. This building has not (at the time of writing) been cleared out; the Swedish excavators have dubbed it an 'Ablution Hall', but the French scholar A. Laumonier offers a more interesting interpretation. Aelian, in his work on the Nature of Animals, observes that there are in the sanctuary of Zeus at Labraynda, in a fountain of limpid water, tame fish adorned with necklaces and earrings of gold. Pliny confirms

this, and adds that the fish come when called and readily accept food from all hands. Is it not possible that they were housed in this curious building Q? Though it is not explicitly stated, there can be no doubt that these fish were sacred to the god, and it may even be that he issued oracles by means of them. Ancient fish-oracles are well known; there was one, for example, at Sura in Lycia, where the response was favourable or otherwise according to whether the fish accepted or rejected the morsels offered them. There is some slight evidence that Zeus Labrayndus had oracular functions. The crossed bands on the god's statue, which have sometimes been compared with the Delphic omphalos-stone, were mentioned above;¹ and there has been found at Labraynda a dedication by a certain chresmologus, or pronouncer of oracles. He may have been attached in a professional capacity to the sanctuary; but this is by no means certain, since itinerant oracle-mongers were commonly called by this name. The matter must therefore remain undecided, at least until building Q has been excavated.

The recently discovered stadium lies above the temple to the north, running east and west across the slope. It is in poor condition, only the two extremities being preserved about 200 yards apart. At the west end is a solidly built structure spanning a gully, with a tunnel through it to permit the passage of the winter rain-water; at the east end still less is preserved.

Many tombs are to be seen around the sanctuary, placed mostly in the ancient fashion along the roads leading to the site. They are more than mere villagers' tombs, and reflect the universal desire, not only in ancient times, to be buried as near as possible to some holy spot. As would be expected, they are numerous along the Sacred Way. In general they are of two types, either chamber-tombs in a rock-face or large boulder, or sunk into the rock and covered with a massive lid. The finest of all, however, is a built tomb on the slope above the temple; a short but steep path leads up in a few minutes from the terrace. The tomb is in three parts, a forecourt and two funerary chambers one behind the other. The walls, outside and in, are superbly constructed of beautifully finished ashlar. The door to

¹ See above, p. 38.

the forecourt is at the east end of the south wall; it was closed with a slab on its inner side, as will be explained. The floor of the forecourt was paved only in the part in front of the tomb. The doorway into the tomb itself was closed by a huge stone slab which is now standing in the forecourt; it is estimated to



FIG. 6 Labraynda. Male Sphinx, in the depot

weigh about six tons. The outer chamber contained two sarcophagi, one on each side, of which only broken fragments remain. From here another door leads through to the larger inner chamber, in which are three sarcophagi, one on each side and a very large one at the back, all well preserved. Both chambers are roofed with a 'corbelled' vault, the blocks being cut away in a curve on their under sides to produce the effect of a true vault. The inner corner stones are so cut as to form part both of the back and of the side walls. Over both chambers is an upper storey, equally solidly built but less carefully finished

and only about 4 feet high; it is entered by a window-like opening overlooking the forecourt. It is roofed with ten slabs of stone 14 feet in length, and even longer blocks, over 17 feet, are to be seen above the entrance to the outer chamber.

Nearly everything about this tomb is remarkable, and not least the arrangements for burial. Originally, it appears, the largest sarcophagus stood alone in the inner chamber, no doubt in a more or less central position; at the same time the two sarcophagi were installed in the outer chamber. These would be the tombs of the owner himself and two of his dependants. The chamber doors were then closed and a slab set in position on the inner side of the door to the forecourt, after which the whole forecourt was filled with earth and sand. At some later time the tomb was opened and the other two sarcophagi introduced to the inner chamber, the large sarcophagus being pushed back to the corner where it now stands; the forecourt was then filled up again. Despite the impressive precautions the tomb has at some time been broken into by treasure-seekers. A further remarkable feature is that the original sarcophagus is too large to be taken through the doors, so that the tomb must have been built around it. Little evidence has been found to determine the date of construction, but certain sherds unearthed in the forecourt suggest a period not later than the fourth century B.C. As to the identity of the owner, nothing whatever is known.

Stretches of the Sacred Way are preserved here and there. It is paved with long blocks of stone placed transversely, a method quite unlike the Roman. It resembles the Roman roads, however, in running very straight, in spite of the steep gradient; there are cuttings and embankments in places. The width is in general about 25 feet. The piece shown on Pl. 11 is close beside the modern road, about a quarter of a mile west of the sanctuary.



Iasus

UNTIL RECENTLY the most convenient way of reaching Iasus was by chartering a boat from the port of Küllük, and this can of course still be done. But in recent years a road has been opened from the Milâs-Bafa highway, turning off through the village of Karakuyu; buses use this road, and it is perfectly passable for a car. The site of the ancient city is now partially occupied by the village of Kuren.

A professional musician once visited Iasus and gave a recital in the theatre. In the middle of his performance a bell rang, indicating that the fish-market was now open. The audience at once rose in a body and departed, except for one old man who remained seated with his hand cupped to his ear. The musician approached him and said, 'I must thank you, sir, for the compliment you have paid to me and my art; for when the bell rang everyone else rushed away.' 'What?' said the other, 'did you say the bell had rung?' 'Why yes.' 'Then, sir, by your leave—' and he too hurried away.

Strabo tells this story to illustrate the character of the city; for, he says, the soil being poor, the inhabitants live mainly by the produce of the sea. Fish were abundant, as they still are, witness the big fishery (*dalyan*) at the head of the gulf. The great marsh, now largely reclaimed, at the mouth of the Sarıçay to the north-east of Küllük was in antiquity sea; an inscription tells us that two citizens of Iasus persuaded Alexander the Great to restore to the city possession of the 'Little Sea', that is without doubt the area of the marsh. For a city dependent on its fisheries the matter was of importance, and the two citizens were suitably rewarded with immunity from taxation and a front seat in the theatre. A gastronomer of the fourth century B.C. observes that the visitor to Iasus will find

there prawns of great size but scarce in the market; and the present-day visitor to Küllük will inevitably be offered fish for his dinner.

Since 1960 Italian archaeologists have been digging at Iasus. The excavations are still in progress at the time of writing, but have already revolutionised our knowledge of the city's early history.

According to the Greek foundation-legend Iasus was colonised by Peloponnesians from Argos. Their coming was not unopposed, and the local Carian inhabitants inflicted such losses on them that they were obliged to call in help from the son of Neleus, the founder of Miletus. As a result of this Milesian influx the city became Ionian instead of Dorian. The settlement by Argives is very likely to be historical; Homer gives to Argos the epithet Iason, and there was a small town of Iasus in the Peloponnese. The leader of the colonists was later supposed to be a man of the name of Iasus, and he is represented, with the title Founder, on Iasian coins; in this particular case there is perhaps slightly less reason than usual to regard him as mythical.

Strabo says that Iasus stood on an island lying close to the mainland. At present this island is joined to the mainland by a shallow isthmus, and it is not unlikely that it was so also in antiquity; the term 'island' is sometimes used to denote a peninsula.¹ To the ancients Iasus is to all appearance an island-city, and nothing would lead one to expect, on the mainland, the splendid stretch of fortification-wall, two miles long, which in fact is still standing there. Of this wall and its significance more will be said below.

The Greek settlement was certainly on the island. It was at one time suggested that until the fifth century B.C. the city stood on the mainland, defended by the fine wall just mentioned; but the buildings and sherds discovered on the island by the excavators show continuous occupation there from Mycenaean and even earlier times until the end of antiquity. The meagre remains inside the mainland wall will be described later. The foundation-legend involving the son of Neleus would place the Argive colonisation somewhere about the ninth

¹ A familiar example is the Peloponnese, the 'Island of Pelops'.

century; the excavators' discoveries show that long before this there was civilised occupation on the site, so that the Greeks' arrival might well be strongly resented and resisted.

After it nothing is heard of Iasus until the fifth century, when the city was enrolled in the Delian Confederacy. Tribute was assessed at one talent, the same as that, for example, of Mylasa; when the assessments were revised—that is in most cases raised—in 425 B.C., the Iasian figure was increased to three talents, but whether this was ever actually paid is not known.

In 412 B.C. disaster overtook the city. At that time the Spartans and Persians were acting in concert against the Athenians, whereas Iasus, still an ally of Athens, was in the hands of a certain Amorges, a Persian noble who was in revolt against the Great King. The satrap Tissaphernes then persuaded the Spartan admiral to attack Iasus. The Iasians were taken by surprise, supposing the advancing ships to be Athenian, and their city was captured and sacked; the booty, says Thucydides, was very rich, for the place was wealthy 'from of old'. The tribute of one talent (or even three) does not suggest great riches, but a trade in salted fish was a profitable business in classical Greece, and the recent excavations suggest a reasonable level of prosperity. After the capture the city—though Thucydides calls it rather a 'town' or 'place'—was handed over to Tissaphernes, together with Amorges himself and all the prisoners, slave and free; for these latter he agreed to pay a gold stater per man.

Spartan vindictiveness seems not to have been satisfied with this. It is recorded that the Spartan commander Lysander, shortly before the final defeat of the Athenians in 404 B.C., destroyed the city of 'Thasos in Caria, an ally of Athens', slaughtering 800 adult males and selling the women and children as booty. No city of Thasos in Caria is known or can ever, it seems, have existed; most scholars have accepted that the place in question was really Iasus. Since the population must have been much reduced after the events of 412, the figure 800 is surprisingly high, and gives an impression of considerable importance for the city in its normal state.

All pretence of Spartan control of this region was, however, ended for good by the Athenian naval victory under Conon

near Cnidus in 394 B.C. The interesting attempt, immediately after this, by a group of Aegean states to form an independent league (known only by the coinage it issued) was mentioned above;¹ equally interesting is the inclusion of Iasus. Here again we receive the impression that Iasus was no inconsiderable city, for her partners—Rhodes, Samos, Cnidus, Ephesus and Byzantium—were all places of size and importance. But the league had a short life; the King's Peace in 387 confirmed the Persian possession of all the cities in Asia.

For Mausolus' relations with Iasus we have only one piece of direct evidence, an inscription recording the punishment of certain persons there who had plotted against him. The city was of course within his district as Persian satrap, and in his plan for the Hellenisation of Caria he can hardly have failed to include it; it is not unlikely that it was he who caused the island to be fortified with the handsome wall which was standing till the end of the nineteenth century. At the time of writing, at least, the excavators' discoveries do not appear to contradict this suggestion. The inscription shows that Mausolus' authority was officially recognised but not universally accepted; Iasus had remained as long as possible faithful to Athens, and Mausolus' anti-Athenian policy was no doubt responsible for some disaffection in the city.

When Alexander arrived in 334 B.C. and laid siege to Miletus, the Iasians contributed one ship to the Persian fleet which attempted to relieve her. Iasus had never aimed at naval power, and her one ship was such a slow sailer that it was captured in a minor engagement. Ten years later, when Alexander was in Ecbatana, his armoury-commander was an Iasian named Gorgus; at the festival which Alexander celebrated there, when every kind of toasting and flattery was lavished on the king, this Gorgus is said to have outdone all the rest. This is the same man who, with his brother Minnion, secured for his city the fishery in the Little Sea.

There was another Iasian who also found favour with Alexander. This was a boy who had the curious fortune to be loved by a dolphin. It was the custom at Iasus for the boys, after exercising in the gymnasium, to run down and bathe in

¹ See above, p. 23.

the sea;¹ the dolphin would then come and carry the boy away on his back, then return him safely to land. This story is told in various forms, with different details and different names for the boy; one account says that Alexander, hearing of it, summoned the boy to Babylon and made him priest of the sea god Poseidon. Such tales of dolphins were common in antiquity, from Arion downwards, but this one was evidently firmly believed at Iasus, for the city's third-century coinage shows a boy swimming beside a dolphin, with an arm over its back.

Towards the end of the third century Iasus, still a free city, became involved in the politics of that rather troubled time. Probably about 220 B.C., when Olympichus was established as an independent dynast in the region of Mylasa,² a subordinate of his, by name Podilus, was guilty of misbehaviour on the territory of Iasus; it seems that his troops had been oppressing or molesting the inhabitants. The Iasians complained of this to the Rhodians, who had helped them previously, and the Rhodians made a serious appeal to Olympichus on Iasus' behalf. In doing so they quoted the guarantees that the Macedonian king Philip V had given for the city's security. Philip was much interested in Caria, and when at the end of the century he conducted a campaign in the country, Iasus was one of the towns which he occupied. In 196, however, the Romans required him to withdraw his garrison and leave the city free.

No sooner was this done than Antiochus III of Syria stepped into the breach and by so doing brought the Roman armies to Asia Minor for the first time. At Iasus there was a division of loyalty; the town was held by the king's garrison, but a rival party supported Rome. These latter were compelled to leave the city and joined the Roman forces. In 190 B.C. the Roman commander Aemilius was contemplating an attack on Iasus, but the Iasian exiles serving with him put in a strong plea that the city be spared; they themselves, they declared, were the true representatives of the city's loyalty, the others having

¹ Sea-bathing does not appear to have been so much indulged in by the ancients as it is today; the same was true in Turkey until quite recently.

² See above, p. 25.

been merely coerced by the king's troops. It is doubtful whether this was really true, but the Rhodians joined in pleading for their 'friends and kinsmen', and Iasus escaped.¹

Nothing is heard of Iasus under the Rhodian domination which followed Antiochus' defeat later in the same year, nor during the period of freedom after 168 B.C. until the formation of the province of Asia in 129. In the war with Mithridates (88 B.C.) Iasus evidently took the king's side, and did not escape punishment; the pirates were permitted by Sulla to sack the town before his own eyes.

Under the Empire Iasus was not a city of great account, though she seems to have served as one of the customs stations in the province; we hear of a certain Pulcher who functioned there as agent for the tax-farmers. Coinage continued down to the third century, and later Iasus was the seat of a bishopric, attached, like the other cities of the region, to the metropolitan of Aphrodisias. The castle on the island is now thought to be attributable to the Knights of Rhodes.

The principal deities of the city were Apollo, Artemis Astias and Zeus Most Great. The temple of Artemis has not been located; it is known to have been 'hypaethral', that is, the cella was unroofed and the cult-statue of the goddess stood exposed to the weather. This, however, caused her no inconvenience, for when Zeus sent rain or snow he was careful that none should fall on his daughter. The situation of the temple of Zeus is known approximately from the handsome inscription beside the East Gate which marks the limit of the temple precinct.² At least one other boundary-stone of the precinct is known, but it was not found in its original place. The importance of Apollo is clear from his pre-eminence on the coins, but of his temple nothing is known.


From the Argive colonisation onwards Iasus was always a Greek city. The Carian element was very small; with one or two exceptions, such as Hyssaldomus and Bryaxis, the names of her citizens, and of her tribes, are exclusively Greek. The

¹ The 'kinship' depended on nothing more than the Dorian nationality of the original colonists of Iasus; but the Greek cities were always ready and willing to discover such ties of relationship even on the slenderest grounds.

² See below, p. 80.

constitution from Hellenistic times was that of a normal Greek democracy. The chief magistrate was the *stephanephorus*, whose name was used for dating the year of his office; other magistrates mentioned in inscriptions are the *prytaneis*, who presided at the assemblies, the *strategi*, now only nominally military and charged rather with civil duties, and the *prostatae*, concerned primarily with the register of citizens. Also recorded is the board of *neopoeae*, whose proper duty was to care for the upkeep of the temples; they function, however, in a different capacity in an interesting inscription concerning the method of payment of the fee due to citizens attending the assembly. On the sixth of each month (the regular day for the assembly) at daybreak a water-clock is to be set up in the form of a vessel holding nine gallons placed 7 feet from the ground, with a hole the size of a bean, and the water set running as soon as the sun is up. The *neopoeae*, six in number, one for each tribe, are to take their seats, each with a box in front of him having a slot of two fingers' length; the boxes shall be previously sealed by the *prostatae*. Each citizen as he enters is to give to the *neopoea* of his own tribe a ticket inscribed with his and his father's names, which the *neopoea* shall put into the box. The inscription breaks off at this point, so we do not know how or when the fee was actually paid; but it is evident that no citizen arriving after the water had run out was entitled to any pay. Inscriptions such as this, which give a sudden glimpse of life as it was lived in an ancient city, are unfortunately all too rare.

Certainly the most striking feature in the ruins of Iasus is the great land-wall which runs west and north from near the village for a mile and a half, then turns south-westward for another half mile and suddenly stops. Beyond this point no trace of it has been clearly observed. The wall is well and elaborately built, with frequent jogs and round towers; its average thickness is about 6 feet. The masonry is a very irregular ashlar, with many small blocks and others up to two tons in weight. Each tower is entered by a door through the wall, and contains two sally-ports close against the outer face of the wall on right and left; in the wall of the tower are five v-slit windows. Each jog also contains a sally-port, so that the



A, A - Land Wall

B, B - Island Wall, now destroyed

C - Theatre

D - Gymnasium

E - Council House (or Odeum?)

F - Graves recently excavated

G - Agora

H - Building with mosaic floor

J - Byzantine Gate

K - Mausoleum

L - Round Building

M, M - Similar buildings

N - Castle

P - Street and Houses

Q - Main Gate

FIG. 7 Plan of Iasus

number of gates leading outside the wall is exceptionally high. The main entrance-gate (Q on the plan) is set in a recess near an angle of the wall, from which it is enfiladed; it is further protected by windows. Close beside each tower a stairway led up to the parapet (Pl. 14).

By whom, when and for what purpose was this wall built? The question has been much discussed, but two things at least appear certain: the wall was never finished, and it never enclosed a city. As it stands it forms rather less than half a complete circuit; if the missing part had been dismantled to afford material for building either the city on the island or some more modern construction, it is hard to see why the more remote portion should have been chosen for the purpose. Much of the interior is thickly overgrown and has not been thoroughly explored; but the lack of building-remains is very striking, and it seems impossible that a city on this site can have disappeared so completely. Nor is the wall itself a normal city wall; its purpose seems to be purely military.

Not that there is nothing whatever in the interior. Buildings have been noted both inside and out, but they are not city buildings; they are indeed curious and interesting. A good example, and comparatively well preserved, has been recently excavated by the Italians; it lies near the point where the land-wall breaks off (L on the plan). A wall about 3 feet thick encloses a rough circle some 30 yards in diameter and ending on the north at two small buildings, one oval, one rectangular, which are standing up to 8 feet in height. Each has a door on the inner side. In the oval building is a staircase which led probably to a flat roof rather than to an upper storey. The two buildings are joined by a short wall between them, and also by a curved wall enclosing a semicircular space which was once paved; on this stood an olive-mill with a circular groove in its surface. Near the rectangular building, but outside the ring, is a stone deeply hollowed out, apparently a drinking-trough.¹ Black-glazed pottery and a coin found by the excavators suggest that this building was constructed about 400 B.C. and collapsed about a century later. Similar structures have been

¹ So say the excavators; but in fact the hollow is only 5 inches deep and 17 inches in diameter.

noted in the northern bulge of the land-wall, also outside it and further to the south. J. M. Cook and the present writer have proposed to explain them as shepherds' shielings; the Italian excavators suggest rather small oil-factories. In any case they are clearly of a pastoral, not an urban, character.

It seems therefore certain that the long wall was built to defend not a city but a camp. It has not yet proved possible to date it by sherds or other material evidence, but on general grounds a date around the late fifth or early fourth century B.C. is probable. It is no makeshift affair, and the camp was evidently intended to be permanent. It is not likely that the Hecatomnid dynasts would want a permanent camp at Iasus, or that they would leave it unfinished if they did; by far the most probable builder is surely Amorges. This man was maintaining a large army in revolt against the Great King, and needed a secure base; if he had had a little more time he could have been safe from attack by land, but the Spartan assault in 412 took him by surprise, and the great wall remained for ever unfinished and unused. No similar situation arose again; within a few years the peasants were building around it their huts and circles, and there it has stood ever since, a white elephant even less meaningful than the Maginot Line.

The city of Iasus stood, then and always, on the island; only the necropolis lay on the mainland. The earliest occupation was on the summit and dates back, as the Italian excavators have shown, to the Early Bronze Age at the end of the third millennium. Among their discoveries is that of an early ring-wall, of which they have uncovered a stretch below the mediaeval castle on the east side; it is about 2 feet 8 inches thick, built of irregular blocks with small stones inserted between. Whether this is to be attributed to the Argive colonists or is even older has not been determined. Later, when the sea-wall was built, this early circuit became unnecessary and was used as a terrace wall; other terraces and houses occupied the slopes below. In particular, an area just to the south of the theatre has been cleared (Pl. 13), revealing a narrow main street flanked by a handsome wall and numerous houses. The wall is dated to the fifth century, but Mycenaean and archaic sherds have been found.

The theatre is of good size, over 200 feet across, but in poor preservation; it faces approximately north-east. Texier saw twenty-one rows of seats still in place, but these are now entirely gone, only the rock-cut substructures remaining, and these covered with earth. The retaining wall of the cavea is of handsome bossed masonry, best preserved on the south side, where a broad staircase, recently excavated, leads up to the cavea. The stage-building is preserved in part, but belongs in its present state to a late reconstruction in Roman times. Four or five courses are preserved, but only the lowest is original; the rest was remade to form the back wall of the Roman stage. This contains three doors leading to rooms behind which are mostly destroyed. The front wall of the Roman stage stands 18 feet further forward into the orchestra; this has a door in the middle which led under the stage, and on either side a group of three niches, one curved between two rectangular, with columns between. In the middle, between these two walls, is a row of columns which supported the stage.¹ This middle row is continued on the south side by a row of blocks which is perhaps the remnant of a ramp leading up to the stage; the first of these blocks is the base of a statue of Justice dedicated by a citizen to the People.

The walls of the theatre once carried an interesting series of inscriptions, dating to the second century B.C., recording special performances by flute-players and comedians paid for by the generosity of private citizens. These have long since been removed, but there remains on the north wall part of a long inscription in a single line recording the dedication of a section of the cavea and the stage to Dionysus and the People, also of the same century; the repair of this part of the cavea is in fact evident from the inferior workmanship.

On the flat ground to the north of the theatre was the city centre. Here again much has been revealed by the Italian excavators. To the west, a high wall with two arched doorways has always been visible; it is thought to be a gymnasium or palaestra. Let into the wall is an inscription in one line dedicating it to Artemis Astias. The agora has been (at the

¹ These appear in the photograph (Pl. 15) encased with small stones put there by the excavators to protect them from damage.

time of writing) partially cleared, and near it a handsome theatre-like building has come to light, well preserved in its lower parts. The rows of seats are divided into three sections, with four stairways, and the 'orchestra' forms nearly a complete circle. On either side is an arched entrance approached down a flight of steps, and a vaulted corridor runs all round behind the seats. This building appears to be a council-house.

Of the elegant isodomic ashlar wall which surrounded the island very little survives. It was standing complete until late in the nineteenth century, when nearly all of it was removed to build quays and other structures in Istanbul. A small fragment remains at the southern tip, and more has been uncovered by the excavators near the gate at the north-east corner (J on the plan). This gate has been rebuilt more than once, and before the excavation only its latest form, a Byzantine arch, was visible. On a bastion of classical date close by is the inscription mentioned above marking the limit of the precinct of Zeus; this appears to date to the fifth century B.C. A short distance to the south a tower in the wall is well preserved.

The site of the temple of Zeus is located with much probability at a point some 70 yards inside the gate, where a basilica was later erected. Under the basilica were found stylobates bearing the marks of columns; these are not all parallel and must belong to different buildings. The architectural fragments found are datable to the second century B.C., but an excavation beside the basilica on the north-east revealed walls and pottery dating from Mycenaean to Hellenistic times. This excavation is continuing.

Space on the island being restricted, burials were mostly confined to the mainland. There a multitude of tombs may be seen, ranging from prehistoric graves to the built tombs and mausolea of Roman times. The earliest date to the third millennium; over eighty of these have recently been excavated. In general they consist simply of four thin slabs, unworked, set up on edge. Similar graves on the island are also found. They are nearly all of less than a man's length. Mixed with and overlying these are later tombs; and the presence of walls and olive-presses indicates that the area was at one time inhabited. Here and there are tombs of 'Carian' type, that is a rectangular

hollow sunk in the rock and covered by a separate lid. In the village are many built tombs of rather mean aspect, with more or less illegible inscriptions on the door-lintel; some of these have been converted into modern houses. Before the excavators got to work the most conspicuous tomb was a mausoleum of Roman date in two storeys, reminiscent of the Gümüşkesen monument at Mylasa but of different construction. This, however, is now eclipsed by the splendid mausoleum revealed by the excavations. This stands close beside the Roman aqueduct in the middle of a large square courtyard with walls containing blind arches. This enclosure was visible before the excavation, and had been variously supposed to be either a gymnasium or possibly the fish-market to which, in Strabo's story, the musician's audience hurried away. The mausoleum itself consisted of a tall temple-like chamber standing on a podium and approached by a flight of ten steps, of which six remain. The order is Corinthian. Under the chamber, inside the podium, are numerous sunken graves in which bones were found; they were originally covered with slabs to form a lid. The monument has been partially restored to stand over 30 feet high (Pl. 16). It is of Roman date, but no inscription has come to light to tell the owner's name. Such a fine tomb in a spacious enclosure is a distinct rarity, and finds its closest parallel in the handsome mausoleum by the shore at Side in Pamphylia.¹

¹ See *Turkey's Southern Shore*, p. 99 and Pl. 41.



Cindya and Bargylia

ARTEMIS ASTIAS at Iasus was not alone in enjoying miraculous immunity from rain and snow. Exactly the same claim was made for her sister goddess Artemis Cindyas. Cindya was a purely Carian city of whose origins nothing is known, nor indeed do we hear much about it at any time, apart from Artemis herself. Early in the fifth century a certain Pixodarus, son of Mausolus, was living at Cindya and was probably a dynast there; his name and his father's leave little doubt that he was an ancestor of Hecatomnos and Mausolus, and he was distinguished enough to marry a Cilician princess. Later in the same century Cindya was assessed in the Delian Confederacy at the respectable figure of one talent, six times more than was paid by her neighbour Bargylia. In 425 B.C. the city was still under a dynast, and the assessment was raised to four talents.

The scanty ruins of Cindya crown the summit of a steep hill, some 600 or 700 feet high, directly above the village of Sığirtmaç, close beside the main road from Milâs to Bodrum. They comprise an outer wall, poorly preserved, enclosing a citadel whose walls stand in places up to 16 feet in height; the gate is on the north-west. The masonry is of dry rubble roughly coursed. Many fallen blocks are strewn over the interior, but nothing is standing.

By the third century B.C. Cindya had ceased to exist as a city and had become absorbed in Bargylia; Artemis was thenceforth the principal deity of Bargylia. The site of her temple has been located on a slight eminence close to the point where the road to the village of Kemikler leaves the main highway. Here were found many architectural fragments and two inscriptions, which leave no doubt of the identity, but nothing now remains

beyond a few stones belonging to a Byzantine church which replaced the temple. The spot has not been excavated.

This complete reversal in the status of Bargylia relative to Cindya may no doubt be explained by the importance of sea-borne commerce in the Hellenistic period; at the same time it is likely to have been instigated by some ruling power, and we may not improbably see in it the hand of Mausolus or one of his successors. Only now did Bargylia become a Greek city. No claim was made for any early colonisation from Greece. A legend grew up that the hero Bellerophon founded the city in honour of his friend Bargylus, who was killed by a blow from his winged horse Pegasus; and in memory of this, Pegasus was commonly shown on Bargylian coins. On the other hand, we hear from Stephanus of Byzantium that Bargylia was at one time called Andanus. Both names are equally un-Greek.

As was mentioned above, Philip V in 201 B.C. made Bargylia his base for a time, and passed the winter there with his fleet. He was far from happy, being both short of provisions and uneasy for his safety; the peculiar situation of the city made it only too easy for his ships to be trapped. In 196 he was ordered by the Roman general Lentulus to withdraw his garrison, and Bargylia was declared 'free'. This freedom was interrupted for twenty years when Caria was given to Rhodes after the battle of Magnesia, but was resumed after 167.

In 133 B.C. when the pretender Aristonicus was fighting the Romans for the kingdom bequeathed to them by Attalus III of Pergamum, he sailed to Myndus and took her by force. The Bargylians, who had contributed forces to the Roman side, viewed the situation with alarm, fearing that they might be next; and it seems that the city was for a time in real danger, from which it was saved by a miraculous epiphany of Artemis Cindyas. What form the divine intervention took the inscription, as usual, does not tell us. About the middle of the first century Bargylia was one of the five Carian cities who were in arrears with their debts to the Roman banker Cluvius.

On the coins the commonest types are Pegasus and Artemis Cindyas. The goddess is clearly an old Carian deity identified with the Greek Artemis; she is shown on the coins standing stiffly to the front, with her arms folded on her breast, wearing

a long robe and a veil; sometimes a deer stands beside her. This portrait evidently represents the cult-statue in her temple. The coins begin in the early second century and continue into Imperial times. Under the early Empire the cult of Artemis was associated with that of Augustus, a compliment normally paid in the east only to the old Anatolian deities.




FIG. 8 Bargylia. Causeway and Acropolis Hill

The site of Bargylia is very much denuded—remarkably so, since there is no habitation within miles. It is likely that here, as at Iasus and elsewhere, stones have been removed by sea for city-building in other parts. The ruins lie on a low hill at the angle of a boot-shaped inlet from the gulf of Mandalya, called on the Admiralty chart 'Bargylia Creek'. Its present name is Varvil Bay, preserving the ancient name in its mediaeval form, Barbylia. The early maps mark salt-pans at the southern tip of the peninsula, and until the present century salt was exported from here in quantities up to 2,000 tons a year; but this industry is now defunct. The inner part of the inlet, beyond the city, has become silted up by a small stream and is now marshy, but the outer part remains navigable for small boats;


there is a landing-stage about a mile north of the ruins. At L on the plan a solid causeway leads across the inlet, but there is no proper road across the flat land to the east. Bargylia is a desolate spot.

The hill has two summits, both quite low; the earlier remains, Hellenistic and Roman, are mostly on and around the northern, the rest being mainly Byzantine. Of the city wall nothing remains but an angle on the west slope of the southern hill and a few short pieces near the shore on the east (A, A on the plan). At the top of the northern hill are the foundations of a temple about 100 feet in length; it is orientated north-west to south-east, and is in the Corinthian order. Numerous architectural blocks have rolled from it down the slope to the south, including a pediment-block and columns partly concave-, partly convex-fluted. This temple is of Roman date, but to what deity it belonged is not known. Lower down the south slope is a small odeum facing south-east; Newton counted ten rows of seats, and the vaulted passage under them is still preserved.

Lying on the hillside between the temple and the odeum is a rectangular altar now broken into two parts. All four sides carry reliefs, showing respectively Artemis Cindyas in a long robe, with a bow in her left hand and with her right drawing an arrow from the quiver; Apollo, apparently lyre in hand; a male figure in a cloak, possibly the hero Bargylus; and a female figure carrying a cornucopia. These figures are now a good deal damaged, but still recognisable (Pl. 21).

On the east slope is the theatre, facing east over Varvil Bay. It is in poor condition, but an angle on the south side is well preserved (Pl. 17), and much of the stage-building no doubt exists under a mound of earth; the vaulted rooms of its ground floor are still visible. But of the rows of seats little or nothing survives, though the position of the diazoma is discernible.

South-east of the odeum the remains of a stoa are, or were, to be seen, running north-west to south-east for a distance of some 50 feet. The columns are no longer standing, but their positions are shown by circular marks on the stylobate. Close by on the south-west is a short stretch of an aqueduct with neatly-formed arches of Roman date.



A, A _ City Wall

B _ Temple

C _ Altar

D _ Theatre

E _ Odeum

F _ Stoa

G _ Aqueduct

H _ Byzantine Wall

J _ Byzantine Castle

K _ Church

L _ Causeway

M, M _ Byzantine Buildings

N _ Necropolis

FIG. 9 Plan of Bargylia

The southern hill is largely occupied by a Byzantine castle of no particular interest; and the church below on the west is unremarkable. To the south of the causeway a quay of uncertain antiquity can, or could, be seen above the surface when the water is low.

Tombs are mostly of sarcophagus type with slightly arched lids. Chamber-tombs are scarce.



Stratoniceia

UNDER THE Prohibited Degrees a man may not marry his stepmother; but in the Hellenistic royal families these matters were otherwise regulated. Seleucus I, king of Syria, had a wife Stratonice whom in 294 B.C. he transferred to his son Antiochus; and it was this lady, his stepmother-wife, in whose honour Antiochus founded Stratoniceia. The date is not known, but must have been after 281, when the Seleucids first came into control of this country. Strabo says that they adorned the new city with costly buildings, which is natural enough; yet before very long they gave it away as a present to Rhodes. The date is again uncertain. Long after, in 166 B.C., a Rhodian envoy to the Roman Senate, pleading that Stratoniceia should not be taken away, claimed that the Rhodians had received her 'by the great generosity of Antiochus and Seleucus'. As only too often in the ancient writers, no indication is given as to which of the numerous kings of those names are meant; but the reference appears to be to the same Antiochus I and his son Seleucus, who were co-regents from 279 to 268.

Livy says that in 197 B.C., or a little later, the Rhodians 'recovered' Stratoniceia. They must presumably therefore have lost her at some period, though the event is not recorded; it occurred perhaps during the Carian campaign of Philip V in 201-198 B.C. Rhodian possession of the city was confirmed at Apamea in 188, but in 167 it was taken away for good. At the end of 130 B.C. Aristonicus, on the final failure of his attempt to dispute the Roman inheritance of the Pergamene kingdom, took refuge in Stratoniceia and was reduced by hunger to surrender.

In 88 B.C. the city was captured by Mithridates and punished for its resistance, but was compensated at the end of the war by

Sulla, who treated it handsomely. Labienus, at the head of his Parthian hordes, attacked Stratoniceia in 40 B.C., but was successfully repulsed; he revenged himself by sacking the sanctuary of Hecate at Lagina, but failed in a similar attempt upon Panamara.

According to the ancient writers Stratoniceia was founded on the site of an old Carian town which was called first Chrysaoris then Idrias; and by one account she was the first city founded by the Lycians. If this last tradition has any historical basis, it may go to strengthen the theory mentioned above¹ by which the Lycians passed southwards from Miletus to their ultimate home. Both names, Chrysaoris and Idrias, must in fact have denoted a region rather than a town; Herodotus says that the Marsyas flows 'from the Idrias country' to the Maeander, and Strabo observes that the reason why the Idrians are not mentioned by Homer is that they are included in the Carians. In the tribute lists of the Delian Confederacy the Edrians (evidently a variant form of the same name) are assessed together with Euromus and the unknown Hymessus at the remarkably high figure of six talents. Chrysaoris is quoted by Pausanias as an earlier name for the site and territory of Stratoniceia, and in Hellenistic times Chrysaorian became a synonym for Carian, at least outside Caria itself.

The reason for this was the Chrysaoric League,² to which all Carians belonged. The temple of Zeus Chrysaoreus, where the League met to offer sacrifice and discuss its affairs, is said to have been close to Stratoniceia, and the new city, though not Carian but Macedonian, was admitted to membership by virtue of the many Carian villages on its territory. Herodotus speaks of a place called White Pillars, where he says the Carians met, near the river Marsyas; this has been thought to be the same sanctuary of Zeus Chrysaoreus, though he does not actually call it so, and there is in fact no actual reference to the Chrysaoric League before 267 B.C. The place has not been identified with certainty, though there are ancient remains at a spot some two and a half miles to the east of Eskihisar which would meet the conditions reasonably well.³ The other

¹ See above, pp. 19-20.

² See above, p. 26.

³ They are described as lying beside the main Aydin road around a

Stratoniceian sanctuaries at Lagina and Panamara are discussed separately below.

As a Hellenistic foundation Stratoniceia was not divided like Mylasa into tribes and clans, but on the Greek model into tribes and demes. This was, however, a distinction without a difference, for the demes were in fact the old Carian villages, just like the Mylasan clans. Their names—Loboldeis, Londargeis, Korazeis and others—are equally un-Greek.

Under the Empire Stratoniceia is recorded as a free city and was very rich and prosperous. Stephanus says that she was 'founded'—that is, refounded, or rather embellished with new buildings—by Hadrian, and took in his honour the name Hadrianupolis; but this is agreed to be a confusion with another Stratoniceia in the neighbourhood of Pergamum. In Byzantine times the bishopric of Stratoniceia was subordinate, like the others of the region, to Aphrodisias.


The ruins of Stratoniceia at Eskihsar are somewhat scanty in proportion to the size of the city, but what remains gives an impressive idea of the solidity and magnificence which they once possessed.

The acropolis hill lies to the south of the site, beyond the area shown on the plan FIG. 10; it is fortified with a ring-wall round the summit. But the inhabited city lay on the flat ground to the north, and is now partially occupied by the village of Eskihsar. Of the city wall F,F only insignificant ruins now remain; it was originally rather less than a mile in length. The main entrance was on the north at C; part of the arched gate is standing, in massive broad-and-narrow masonry, and just inside it a single unfluted Corinthian column survives from the row which originally stood there (Pl. 19). At the north-east corner of the site are the ruins of a powerful fort, D, overlooking a dip in the ground; it is solidly constructed of large squared blocks in regular courses, with some mortar, but in places additions or repairs show a very inferior masonry with many reused blocks and even column-drums.

In the present village, and almost in the centre of the ancient

Turkish cemetery, with many broken marbles and two large blocks flush with the ground. The writer has not seen these.

city, is the most impressive building on the site, the Sarapeum or temple of Sarapis, A, dating from the second or third century A.D. The outer walls are standing to a fair height (Pl. 18), in the same broad-and-narrow masonry as the north gate, but the interior is filled with earth and is now used as a



- | | | |
|-----------------------------|---------------------------------|-------------------------------|
| A - Temple of Sarapis | D - Fortress | G - Colonnaded Street |
| B - Gate of temple precinct | E - Building of unknown purpose | H - Agora |
| C - Main City-gate | F, F - City Wall | J - Coffee-house of Eskihisar |

The Acropolis hill and the Theatre lie further to the south.

FIG. 10 Plan of Stratoniceia

garden. The north wall is covered, partly on the inside and wholly on the outside, with inscriptions in Greek and Latin; one of these, at the east end of the inner face, is an ex-voto to Helios Zeus Sarapis for salvation from war and foreign seas. Another records an oracle delivered by Zeus of Panamara; the Stratoniceians had asked, apparently on the advice of Sarapis, whether the barbarians would attack the city in the current

year; the god reassures them. The occasion was evidently the invasion of the Goths in the middle of the third century A.D. A third is a very curious document; it consists of twelve very faulty verses, each of which contains as many letters as one of the months of the year, beginning with October; the number of days is written at the right in Greek numerals. At the same time the initial letters of the lines form an acrostic giving the name of the writer, Menippus. His purpose, as he explains, is to provide a mnemonic which may be useful to his less well educated fellow-citizens.

Just to the west of this building, in a maize-field, stands a solitary gate, B, with uprights and lintel. This was an entrance to the peribolus or precinct surrounding the temple, an enclosure over 100 yards square of which very little else survives. The gate carries no inscription.

To the west again lay the agora or market-place of Stratoniceia. Virtually all that now remains of it is a row of marble blocks, H on the plan, bordering one of the village lanes. To the north of this, beyond the coffee-house, is a building E of unknown purpose, comprising at present a long wall of large well-squared blocks, joined on the south side by part of a curved wall. This arrangement does not conform to the plan of any normal building.

At the north-east corner of the site (G on the plan) Trémaux in 1874 saw a colonnade beside a street leading in the direction of the city-gate at C. Something of this colonnade is said to survive, but the present writer has not seen it.

At the north foot of the acropolis hill, not shown on the plan, is the theatre, large and quite well preserved, but badly overgrown and poorly maintained. The cavea, facing north in the manner approved by Vitruvius, is divided by stairways into nine cunei; the single diazoma is now largely destroyed. The capacity is estimated as not less than 10,000. The stage-building too, or at least its foundations, is probably in quite good preservation; but it has not been excavated and the plan is not at present to be made out.

On the hillside above the theatre is a levelled area on which lie the ruins of a small temple in the Ionic order, identified from an inscription as devoted to the cult of the Emperors.

Across the main road from the school is a small museum which is well worth a visit. It contains mostly small pieces of Roman date, including epitaphs and several bearded heads from the angles of a sarcophagus; among the former is the quaint tombstone of a young man (Pl. 20) erected by his parents and brothers. But the most remarkable object is a Mycenaean stirrup-cup of buff with horizontal red stripes which is dated to the twelfth or eleventh century B.C. All the exhibits were found locally.



Lagina and Panamara

OF ALL THE DEITIES who made up the Greek pantheon one of the strangest is surely Hecate. It is possible, though not proved, that she was of Carian origin; but in Greek mythology she is daughter either of Zeus or of a Titan. She is assimilated to, or even identified with, other goddesses, especially Artemis and Demeter; in one metrical inscription she is addressed as *Ompnia*, a special epithet of Demeter. She is thought of as an underworld deity, mistress of the dead and holder of the key to the door of Hades; she is the sender of bad dreams, ghosts and spectres, but as sender can also defend men against them. Often she is accompanied by dogs, and dogs were sacrificed to her. The dog was indeed called 'the Carian sacrifice', and its association with the underworld is seen for example in the familiar case of Cerberus. At the same time Hecate is a moon-goddess, a roamer by night, haunting especially crossroads and forks in the road, and in these places she was worshipped by night, on the last day of the old moon, with offerings of cakes, fish, eggs and cheese. A proper temple such as that at Lagina is therefore something out of the ordinary. In art she is represented sometimes with a single body (so at Lagina, and this seems to be her earliest form), or more often with three complete bodies or with one body and three heads. Her principal attributes are torch, dagger, whip, snake and key. At Lagina she carries a torch in her left hand and a dish in her right; on her head is the cylindrical headdress called *polos*, with the horns of a crescent moon, and at her feet sometimes a dog. At Lagina also mysteries were celebrated in her sanctuary, and it appears that on occasion she might even deliver oracles.

How old the cult of Hecate at Lagina may be is not known. Our earliest evidence is an inscription recording a priest of

Hecate and of Helios and Rhodes; this must clearly date from the Rhodian domination of 189-167 B.C. The temple itself, of which the ruins remain, is variously dated by scholars from about 125 B.C. to the time of Augustus; the choice lies most probably between the earliest date, after the war with Aristonicus and the foundation of the province of Asia, and one about 80 B.C. after the war with Mithridates. What stood in the sanctuary before this is unknown. In 88 B.C. Mithridates took Stratoniceia by force; after his defeat the decree of the Senate confirming the friendship and alliance of Rome and the inviolability of the sanctuary was engraved on the wall of the temple at Lagina; at the same time a festival was inaugurated with the double title of Hecatesia-Romaea. In 40 B.C. Labienus failed to capture Stratoniceia, but he sacked her temples, including that of Hecate; the inscription on the lintel of the propylon which is still standing refers in general terms to the help given after 27 B.C. by Augustus in restoring the cult after this disaster.

From 81 B.C. onwards the Hecatesia-Romaea were celebrated every fourth year with especial brilliance; in the intervals the Hecatesia alone were held annually. But these were by no means the only ceremonies in honour of Hecate. Very important was the festival of the Bearing of the Key, held once a year and accompanied by games, lasting several days. The key of the temple was carried in procession from Lagina to Stratoniceia and back; this would symbolise the attachment of the sanctuary to the city, but the key must surely have meant more than this in the minds of the worshippers; Hecate held the key to the door of the underworld. Important also was the Birthday Festival, held annually on the goddess's birthday, the thirtieth of the month; it may also have been held, with less splendour, on the same day of every month. At the annual celebration gifts of money were made to the citizens. At the same time Hecate shared with Zeus a shrine in the council-house at Stratoniceia; here, in consequence of certain miracles performed by the goddess, ceremonies were held every day throughout the year. All this is peculiar to Hecate at Lagina, and very different from the popular worship at crossroads in the dead of night.

The temple cult was served by a male priest; not until the third century A.D. do we hear of a priestess, nor even then does she take the place of the priest; she is usually his wife or other close relation and serves under him. Among the other personnel of the clergy the most important was the Key-Bearer, always a young girl, whose duty it was to open and close the temple; she too was generally related to the priest. At a late date we hear of a neocorus, or temple-warden, with duties corresponding to those of a sacristan. Eunuchs also were attached to the cult; in early times, no doubt, as in oriental religions generally, these were important, but when we hear of them, in the third century A.D., they have uncharacteristic functions, as for example the maintenance of the trees in the temple precinct. Another permanent official was the President of the Mysteries; but of his duties, and of the mysteries themselves, we are as usual told nothing. They were, however, celebrated regularly at least from the second century onwards.

The temple precinct consisted of a large, nearly rectangular enclosure about 490 by 440 feet, surrounded by a stoa, plain on three sides, but on the south raised on a flight of steps; at the west end on this side was a monumental gateway (propylon), of which the jambs and lintel are still in place—the only thing actually standing on the site (Pl. 27). As the inscription shows, it dates to the time of Augustus, and it is likely that the whole stoa is of the same period. The steps were probably used as seats for those assisting at the mysteries.

Nearly in the centre of the precinct stood the temple of Hecate. It was excavated, or at least investigated, in 1891–92, but the work was never carried through, and the ruins still lie in a jumbled heap not easy to understand. The chief result of this work was the recovery of numerous blocks of the frieze and their transportation to the museum in Istanbul. Then and at other times many inscriptions have been found, and to these we are indebted for most of what we know about the cult. The temple is in the Corinthian order, unlike the stoa, which is Doric. It is pseudo-dipteral, with eight columns at front and back, but only eleven on the long sides; it includes a deep pronaos, with two columns in antis, and a cella, but no opisthodomus. Little of this, however, can be made out on the spot.

The frieze on the east front showed Hecate assisting at the birth of Zeus, and carrying the stone to offer in his place to his father Cronos; at the west end she watches over a battle between gods and giants. The north side showed a scene of




FIG. 11 Lagina. Plan of the Temple

fraternisation between Amazons and Greek soldiers, while Hecate pours a libation; this is thought to be an allusion to the treaty of alliance ratified in 81 B.C. between Stratoniceia and Rome. On the south side was a series of figures, mostly unrecognisable, apparently representing Carian deities and cities.

There was much else in the sanctuary besides the temple, though little of it can be seen today. In front of the temple on

the east an altar would be expected, and there is in fact a heap of ruins in this position (C on the plan), but it has not been excavated and is differently orientated from the temple; its identity is therefore uncertain. The precinct housed a considerable permanent population, attached in various ways to the cult; an inscription of the second century A.D. tells us that a priest constructed at his own expense three stoas 'in the sacred house' and completed the stoa in front of the sacred house 'close to the provision-market'. This house was probably occupied by the clergy. There was also a sacred grove of trees, for whose upkeep the eunuchs were responsible, and another inscription forbids the pasturing of flocks in the sanctuary. All of this—altar, houses, market, grove and pasture—was apparently contained within the area of the precinct.

A few hundred yards to the east of the temple is an attractive pool, fed from a spring above. An inscription found here, but not yet published, apparently records the installation of this pool.¹ A fragmentary text from the sanctuary refers to the construction of a water-channel 'leading to the fountain from the . . .'; here it breaks off, but it is likely enough that it led from the pool in question to a fountain in the temple precinct.

Lagina was a deme of Stratoniceia, and was joined to her by a Sacred Way six miles long, of which only the scantiest traces remain. The name of Lagina, however, is never used in the inscriptions, and it appears that the deme was known as Hieracome, the sacred village. The nearest town now is the *nahiye* of Turgut, about a mile to the south; this name is new, and until recently the place preserved its ancient name in the form Leyna—which indeed is still heard. It is nine miles from Yatağan by a perfectly tolerable road.

PANAMARA

A second sanctuary belonging to Stratoniceia, and rivalling in importance that of Hecate at Lagina, was that of Zeus Panamaros. The site, discovered in 1886, is about seven miles as the crow flies to the south-east of Eskihisar, but it is reckoned

¹ The stone is said to have been subsequently built into a house with the inscribed face hidden, and the writer was unable to see it.

three and a half or four hours on foot. The ruins are on a hill above the village of Bağyaka, but they have never been excavated and there is not now very much to see. The sanctuary consists of a walled enclosure some 50 yards square containing a jumble of blocks among trees and bushes; this forms part of a larger enclosure nearly 100 yards square, with a massive wall of which the west angle is preserved for some 80 yards. In one corner is a ruined building about 60 feet long. This outer enclosure was joined on the south-west by a paved road from Stratoniceia, of which a long stretch is recognisable on the height opposite. Many inscriptions have been found on the site, and give much information concerning the cult.

The two principal buildings were the temples of Zeus Panamaros and of his consort Hera; these, however, have not been identified on the ground. But other deities also were worshipped, notably Artemis and Sarapis; and as at Lagina the precinct contained many shrines and other buildings. We hear for example of a reception-room, a luncheon-hall and a store-room.

Panamaros is an old Anatolian name, and the cult too may be very ancient, though our information concerning it begins only after the foundation of Stratoniceia. The sanctuary was honoured with a visit by Philip V; it may have suffered from Mithridates in 88 B.C.; but in 40, when Labienus, failing to take Stratoniceia, attacked Panamara, the defenders, aided by the powerful walls and by a miraculous intervention of the god himself, successfully repelled him. The details of the battle were recorded in a long decree engraved in the sanctuary; there were apparently three attacks. The first took place by night, but the god sent a great flame of fire upon the assailants and they recoiled. Next morning the assault was renewed; this time the god's aid took the form of a thick mist followed by a great storm, before which the attackers fled as if pursued by Furies; not a single defender was seriously wounded. A third attack was made with reinforcements, and now the god's mysterious power became very evident; cries were heard as if of a relieving force, though none appeared, and a snarling as of dogs attacking the assailants; the latter were then, from some cause which is not apparent, suddenly hurled down from the

walls. Throughout these events the lamps in the temple were found to have remained burning.

Festivals at Panamara seem to have been less frequent than at Lagina; we hear notably of three. Of these the greatest was the Panamareia, celebrated annually and lasting for ten days; the statue of Zeus was carried down to Stratoniceia for the duration, and the festival and games took place in the city. In honour of Hera the Heraea was held at Panamara every other year and was, at least at first, restricted to women; it lasted one day and included mysteries. Finally, every fourth year, a two-day festival of Zeus, the Comyria, was held in a sanctuary at Panamara called the Comyrium; this was primarily for men and it too included mysteries.

The name Panamaros, as was said above, is Anatolian, but it was later Graecised in the form Panemeros or Panemerios, and understood to mean either 'very gentle' or 'of the full daylight', in contrast to the nocturnal Hecate.

*Halicarnassus*

OF THE Seven Wonders of the ancient world—only one of them in Greece itself—hardly anything survives today, apart from the pyramids of Egypt. The lighthouse at Alexandria, the Colossus of Rhodes, the Hanging (that is terraced) Gardens of Babylon and the statue of Zeus at Olympia are utterly lost. Of the temple of Artemis at Ephesus some fragments of the columns are in the British Museum, and the foundations still remain, sunk in a muddy pool. The Mausoleum at Halicarnassus has fared little if at all better. Its site was determined by Sir Charles Newton in 1856, and a number of the sculptures that he found are also in the British Museum; large quantities of the green stone which formed its base may be seen built into the Castle of the Knights at Bodrum; on the site itself virtually nothing is now visible. This famous building has, however, served to make the name of Halicarnassus more familiar than any other city of Caria.

That Halicarnassus was a Dorian foundation is stated both by Herodotus and by Strabo; the colonists came, according to the tradition, from Troezen on the east coast of the Peloponnese under a certain Anthes or one of his descendants. In A.D. 26, when Halicarnassian envoys came to Rome to compete for the privilege of erecting a temple to the Emperor Tiberius, they urged in their own favour that for 1,200 years their city had never felt the shock of an earthquake. This would put the foundation, at the latest, very soon after the Trojan War;¹ but in fact it is unlikely to have been earlier than the Dorian invasion of Greece about 1100 B.C. Strabo indeed observes that at a date after the death of Codrus, the last king of Athens,

¹ Traditionally 1194–1184 B.C. Modern scholars are inclined to regard this as too late by perhaps half a century.

about the first quarter of the eleventh century, Cnidus and Halicarnassus were not yet in existence. We may therefore probably accept the foundation under Anthes some time after 1000 B.C.

At first the city was a member of the Dorian hexapolis,¹ but was later expelled for the misconduct of one of its citizens. The story as told by Herodotus, himself a Halicarnassian, is that a certain Agasicles, after winning a victory in the games celebrated in honour of Apollo at Triopium near Cnidus, received a bronze tripod as his prize; in disregard of the rule which required him to dedicate this on the spot to Apollo, he took it home with him and hung it up in his house. It is likely enough that this was a mere pretext, and that the real reason for the expulsion was the increasing Ionian tendencies of the Halicarnassians; at all events, when the city becomes familiar in the fifth century it appears as purely Ionian. Herodotus wrote in Ionic, as did his uncle Panyasis the epic poet, and even the earliest inscriptions show no trace of the Doric dialect. It is not clear how this came about. No special reason (as for example at Iasus or Smyrna) is recorded, apart of course from the expulsion from the hexapolis. However this may be, the connexion with the mother-city of Troezen was maintained, and the Halicarnassians built there a temple of Aphrodite.

When the Persians overran the Greek cities of the coast after the capture of Sardis in 546 B.C. Halicarnassus naturally fell with the rest. Sixty years later, at the time of the Persian Wars, the city was ruled in the Persian interest by a Carian dynasty of which the most famous member was the queen Artemisia. Her name is Greek, but her father had the Carian name Lygdamis, while her mother was Cretan. When Xerxes was preparing for his invasion of Greece in 480 B.C., this redoubtable woman not only joined his navy in person—though, as Herodotus remarks, there was no need for her to do so—but was esteemed by him above all his other counsellors. At Salamis, when the King was debating whether to risk a sea-fight with the Greek navy, Artemisia was alone in advising him against it, pointing out among other things the worthlessness of many of the elements in his forces; Xerxes himself was in-

¹ See above, p. 20.

clined to agree, but thought it better to adopt the advice of the greater number. In the battle itself Artemisia was favoured by chance in a curious way: when the Persian fleet was routed and in confusion, she found her own ship closely pursued by an Athenian vessel; thereupon, whether by chance or by design, she bore down on a ship of her own side from Calynda and sank it with all hands. The Athenian, supposing that her ship must be fighting for the Greeks, turned away and Artemisia escaped; on the other hand, the King and his companions, watching the battle from a neighbouring hillside, imagined the Calyndian to be an enemy, and were loud in their praises of the queen's prowess; Xerxes himself was said to have exclaimed, 'My men have shown themselves women and my women men'. As Herodotus drily observes, it was lucky for her that no Calyndian survived to give the game away. From then on she stood higher than ever in the King's favour, and when she advised him to return home after the battle, he accepted her advice and entrusted his bastard children to her care. The Athenians, on the other hand, had put a price of 10,000 drachmae on her head if taken alive—a reward which was never claimed.

When the Delian Confederacy was founded a few years afterwards, Halicarnassus, either then or later, became a member. The comparatively modest standing of the city at that time is shown by the amount of its normal tribute, namely one and two-thirds talents, or less than was paid by the Lelegian towns of Termera and Pedasa. It had, however, an influence disproportionate to its size; at least, Artemisia is said to have ruled also over several of the islands, including the large island of Cos. The same dynasty continued in control until the middle of the fifth century, and it was during this period that Herodotus grew to maturity. Forced to leave his native city by the oppressive government of the tyrant Lygdamis II, the historian later returned and was instrumental in putting an end to the dynasty.

Such is the account current in later antiquity. But an interesting inscription, the earliest found at Halicarnassus, suggests that the power of the tyrant was not altogether unbridled. It takes the form of a decree issued by the 'Council of the Halicarnassians and Salmacitans, together with Lygdamis'.

Persian control was of course removed after Salamis, and it appears that the first steps had been taken towards a kind of democracy, though no doubt the ultimate authority would rest with the tyrant.

The inclusion of the Salmacitans in this decree is interesting. Salmacis is indeed something of a puzzle. In later times we find it described variously as a headland, a fountain and (less convincingly) as a city of Caria. Its position is fixed approximately on the west side of the harbour at Bodrum. Evidently in the fifth century it formed a kind of suburb of Halicarnassus, with enough independence to be separately represented on the Council; its inferior status is shown by the fact that elsewhere in the inscription only Halicarnassus is mentioned. The fountain had some celebrity, or rather notoriety, for it was said that its water, though excellent to drink, had the effect of causing venereal disease in the drinker. The Roman architect Vitruvius, who shows a particular interest in Halicarnassus, vigorously denies this imputation, and attributes the fame of the spring to a much nobler cause. When the Greek colonists arrived, he says, and drove the Carians to the hills, the latter gave them much trouble by raiding and brigandage; but after a while one of the Greeks set up a tavern beside the fountain of Salmacis because of the excellence of the water, and the Carians gradually got into the habit of patronising this. So, by mixing with the Greeks, they learned the ways of society and, thanks to Salmacis, were weaned from barbarity to civilisation.

How much, if any, truth there may be in this story no one can say; but it is certain that there was, from the earliest times of which we can judge, a very considerable Carian element in the city. This is clear from the names of the citizens. Among several hundreds of names of Halicarnassians known to us from inscriptions in the fifth century, Greek and Carian names are almost equally divided. They are, moreover, frequently mixed in the same family; we find sons with Greek names having fathers with Carian names, and vice versa; the father of Herodotus himself had the Carian name Lyxes. It would, however, be quite wrong to suppose that Halicarnassus was anything but a truly Greek city; all the archaeological evidence goes to

show that this strong Carian element was absorbed without any diminution of the city's Hellenic character.

In the fourth century great changes took place at Halicarnassus. Caria was now once again under Persian dominion, ruled by a satrap appointed by the Great King. Early in the century this satrap was, as related above, a certain Hecatomnos, succeeded on his death in 377 by his son Mausolus. Until then Halicarnassus was a comparatively small city, but Mausolus, observing her natural advantages for fortification and commerce, transferred his capital from Mylasa. His ideas were never on a niggardly scale, and he set out to create a worthy capital city. He it was who built the line of walls, some three and a half miles long, of which parts are standing today; and to people this great area he forcibly transplanted the inhabitants of six of the eight Lelegian cities in the neighbourhood. These were of varying size, but some at least, if we may judge by the tribute they paid to Athens in the fifth century, seem to have been comparable to Halicarnassus herself, and the population of the new city must have been four or five times that of the old. For his own residence Mausolus built a palace with walls of dried brick, finished in all parts with marble from the Sea of Marmara. Nothing of this palace survives today, and its position has been the subject of much discussion.¹

Mausolus died in 353 B.C. and was succeeded by his wife and sister, Artemisia the younger. She ruled for only three years, but in that time made herself famous in two notable respects. The first of these was the superb tomb with which she has perpetuated her husband's memory, the Mausoleum. For the form which this monument took we have to rely on the description given by Pliny, eked out by the rather scanty remains unearthed by Sir Charles Newton in 1857. This is not the place to discuss the details,² but the general appearance is clear enough. The building was of oblong shape and comprised four parts: first, a solid base or podium; above this a colonnade of thirty-six columns, disposed apparently with eleven on the flanks and nine on the short sides, surrounding a rectangular chamber;

¹ See below, p. 112.

² The reader will find an excellent discussion in W. B. Dinsmoor, *Architecture of Ancient Greece* (3rd edition, London, 1950), pp. 257-61.

above again, a pyramid of twenty-four steps; and at the top a chariot-and-four bearing (in all probability) figures of Mausolus and Artemisia. The total height, according to Pliny, was 140 Ionic feet—about 41 metres by modern reckoning. All four sides were adorned with sculptured friezes by some of the first-rate sculptors of the day, Leochares, Bryaxis, Scopas and Timotheus, who each took one side. Three of them were apparently brought from Greece, but Bryaxis has a Carian name. It was principally these sculptures, we are told, that caused the Mausoleum to be reckoned among the Seven Wonders. Fragments of them are now in the British Museum, and a single slab is exhibited in the Castle of the Knights (Pl. 23). Even more than these, however, many people (the present writer included) will no doubt admire the superb figure of Mausolus himself which may have occupied the chariot at the top. The Mausoleum stood for 1500 years; Bishop Eustathius in the twelfth century, in his Commentary on Homer, observes that it 'was, and is' a marvel. But when the Knights arrived in 1402 they found it in ruins, destroyed presumably by one of the earthquakes which the envoys to Tiberius claimed to be so rare. Looking for building-stone and material for burning lime, they found here a plentiful supply of both; they removed to the castle almost the whole of the solid base, in the interior of which they discovered and destroyed the handsomely decorated tomb-chamber. Newton found only the lowest courses of the base, made of the same green granite of which the castle is largely constructed; he found also on the west side a rock-cut stairway descending to the level of the lowest foundations, and a few paces from the foot of this stairway a huge door-stone weighting two tons which in all probability closed the entrance to the tomb-chamber. But of the chamber itself nothing remained.

Artemisia's other claim to fame is of a totally different character. That a woman should rule over Caria seemed to the Rhodians an indignity, and also no doubt an opportunity; they therefore equipped a fleet and set out to take the kingdom from her. Artemisia, learning of this, hid her own fleet in a secret harbour joined by a canal to the great harbour. This had been constructed by Mausolus close under his palace, so as to

have his ships under his eye and to make his decisions without interference. The Rhodians sailed in and put their men ashore to occupy the city. Whereupon the queen led her ships quickly out of the secret harbour, seized the unmanned Rhodian vessels and carried them out to sea. The Rhodian soldiers, deprived of their retreat, were surrounded and destroyed in the market-place. Artemisia then put her own men on the enemy ships and sailed to Rhodes. There the Rhodians, supposing their own ships to be returning victorious, admitted the Halicarnassians, and the city was easily captured. To celebrate this victory Artemisia had a trophy erected there in the form of a statue of herself branding the city of Rhodes. Humiliating though this was for the Rhodians, ancient custom forbade that a trophy once set up should be taken down; to hide their shame, therefore, they afterwards erected a building around it and declared it forbidden ground.

On Artemisia's death in 350 B.C. the succession passed in turn to the other children of Hecatomnos, the last of whom, Pixodarus, called in a Persian satrap named Orontobates to share his rule; and this satrap was in control when Alexander arrived in 334, shortly after Pixodarus' death. Of the Macedonian siege of Halicarnassus we have detailed accounts by Diodorus and Arrian, from which the course of events is reasonably clear. Orontobates was assisted in the defence by the Rhodian Memnon fighting in the Persian cause, and the city was well prepared, with command of the sea. Alexander fixed his headquarters on the north-east side, near the Mylasa gate, and after an unsuccessful attack on Myndus settled down to the siege of Halicarnassus.

Sending round a detachment to invest the city on the west side by the Myndus gate and to prevent reinforcement from that quarter, he took command in person on the north-east. Filling in the fosse, he brought up his siege-engines and succeeded in breaking through the wall. The defenders, however, fought back vigorously and built an inner wall to close the breach. The fighting continued with frequent sallies by the Persians to set fire to the engines, all of which were repulsed with much slaughter on either side; the historians emphasise the fierce and determined bravery of both parties. One evening

two of the Macedonian soldiers, having applied themselves too freely to the bottle, got to boasting of their achievements, and to show off their prowess set out by themselves to attack the wall. The defenders came out to punish their presumption, and as others came up on either side a sharp engagement ensued, and the city was almost taken. Alexander, however, was hoping for a voluntary surrender and forbore to press the attack. Meanwhile on the other front by the Myndus gate an unsuccessful sortie by the Persians also brought the city near to capture, but again Alexander called his men back. Eventually Orontobates and Memnon, realising that they could not hold out much longer, while their losses were severe, set fire to the upper part of the city and withdrew with the best of their troops to the two headlands on east and west of the harbour, sending the rest to the island of Cos. Alexander thereupon sacked the city, sparing the inhabitants, but made no attempt on the headlands; leaving a force to blockade them, under the direction of the ex-queen Ada, he passed on into Lycia. The sack was evidently not complete; at least, the Mausoleum and the palace of Mausolus seem to have suffered no harm. The headlands surrendered shortly afterwards, from weariness of the siege rather than from compulsion.

Ada was thereupon appointed as ruler of the whole country. Pliny states further that Alexander attached to Halicarnassus six of the neighbouring Lelegian towns, and gives their names. This, however (in the writer's opinion), is plainly an error; Pliny has wrongly attributed Mausolus' action to Alexander. When Alexander left, the city was not even completely captured, and by the time such a settlement became possible he was in the midst of his eastern campaign.¹

In the free-for-all which followed Alexander's death the Halicarnassians came, early in the third century, under the control of Ptolemy II of Egypt, to whom, together with Apollo, they dedicated a stoa. In 196 B.C. Antiochus III of Syria would have taken the city from the Ptolemies, but was prevented by their allies the Rhodians. After Antiochus' defeat by the

¹ This question cannot be fully argued here. For a discussion of it the reader is referred to the article by J. M. Cook and the present writer quoted in the Bibliography.

Romans in 190 B.C. Halicarnassus was left as a free city, and remained so, as far as we know, for the rest of her history. She was among the places plundered by the notorious Verres in 80 B.C., and by 60 seems to have been in low water; her fortunes were, however, restored, as we are told, by Quintus Cicero, brother of the famous orator, who was governor of Asia at that time. But before long the exactions of the 'tyrannicides' Brutus and Cassius¹ again reduced the eastern cities to distress; and Halicarnassus may well have suffered more than most, for Cassius made his headquarters for a time at Myndus. The better times that followed the establishment of the Empire under Augustus are reflected in an inscription found at Halicarnassus, in which the Emperor is called

Paternal Zeus and Saviour of the entire human race, whose providence has not only fulfilled but exceeded the hopes of all men; for earth and sea are at peace, the cities flourish in good order, concord and prosperity, and every blessing is furnished in fullest measure.

The praise is fulsome, but not unjustified by the facts.

As distinguished Halicarnassians Strabo mentions, apart from Herodotus, Heraclitus, the writer of epigrams, and Dionysius, the historian and literary critic. A less enviable distinction was that of Phormio the boxer, who was victorious at Olympia in 392 B.C., but at the next celebration four years later was found guilty of corruption and was 'fined a Zeus'—that is, he was required to dedicate a bronze statue of Zeus bearing his name at Olympia. His exact offence is not known, but the commonest were being bribed to sell the victory or to enter from a city to which he did not belong.

As is so often the case when a place has been inhabited continuously since antiquity, little is left at Bodrum of the city of Halicarnassus. To reconstruct it as it was we have the help of a passage in Vitruvius, who is led on from speaking of the brick palace of Mausolus to give a description of the site. He compares it to the auditorium of a theatre; at the bottom by the shore, where the orchestra would come, is the agora, and across

¹ See above, p. 27.


the middle, like a diazoma, runs a broad street, and in the middle of this is the Mausoleum. At the top of the citadel, in the middle, is a temple of Ares; on the right wing is the fountain of Salmacis with a temple of Aphrodite and Hermes close by, and on the left wing is the palace of Mausolus, built to his own specification. This palace commands on the right a view of the agora and harbour and the whole circuit of the walls; under it on the left is the secret harbour.

Of all this nothing is actually standing today apart from the city wall. This may be traced for most of its length; on the west the Myndus gate remains in a ruined state, and is evidently to be identified with the Tripylon, or triple gate, mentioned by Arrian. Hereabouts we may imagine the unsuccessful Persian sortie which nearly resulted in the loss of the city. A curious feature is the isolated line of outer wall on the north-east; from Arrian's description of the terrain it seems that this must be the wall that Alexander attacked, and must apparently be an early Mausolan fortification later abandoned. Here was presumably the Mylasa gate, no longer surviving.

The temple of Ares has not been located. Vitruvius' words would suggest the summit of Göktepe, the conical hill which stands at about the middle point of the wall-circuit. There is in fact a level platform here about 40 feet long, but no visible sign of a building. At the east foot of Göktepe there is another large platform on which Newton found some traces of a building similar in style to the Mausoleum, and he and others have preferred to place the temple of Ares here. But the situation so low down does not answer well to Vitruvius' location 'at the top of the citadel in the middle'.

The exact position of the agora is not now determinable, as it has long since been obliterated by the town of Bodrum, nor is there anything much to be seen on the site of the Mausoleum.¹ Salmacis too, with its fountain and temple, has disappeared. Its position was almost certainly on and around the headland which carried the old Turkish arsenal; sherds of classical and archaic pottery are to be found here, but no trace of any ancient building. Something over half a mile down the coast there is a

¹ A small-scale excavation recently carried out has revealed a short stretch of wall and a number of small finds which are now in the museum.



A.A - City Wall

B.B - Outer Fortification

C - Gate

D - Myndus Gate

E - Göktepe

F - Theatre

G - Large Platform

H - Site of Mausoleum

J - Colonnade

K - Castle of the Knights

L - Submerged Wall

M - Arsenal Point (Salmacis)

N.N - Tombs

Contours approximate

FIG. 12 Plan of Halicarnassus

small spring, and a rather shorter distance to the north is the fountain called by the Turks Eski Çesme, but both of these are too far away to come in question. On the other hand, an abundant head of fresh water rises in the harbour just off the Arsenal Point, and it seems highly likely that this represents the fountain of Salmacis; it may quite possibly have risen on land in antiquity, for the west coast in general has sunk some 5 or 6 feet in the last two thousand years.¹

The other, eastern wing was apparently the site of the original settlement. The peninsula on which the Castle of St. Peter stands was in early times an island, and seems to have borne the name of Zephyrium; but the great pile of the castle has obliterated all traces of anything earlier. In this neighbourhood were the palace of Mausolus and the secret harbour and canal. That the palace should be utterly lost is no great wonder, but the disappearance of the secret harbour is surprising. Some remains of walling have been observed under water in the great harbour (L on the plan), and it has been suggested that these may be the remains of it; but the position is not satisfactory. Mausolus' palace had a view on the right over the great harbour and the city walls, and on the left over the small harbour; if it stood on the 'island' with a westward view the city would be on the right, but the secret port would then have to be near the tip of the island, which is obviously out of the question; the peninsula on which the castle stands is solid rock, and a secret harbour once cut into it must ever afterwards be plainly visible. The palace must therefore have been on the landward side of the isthmus; but a situation which would have the harbour and city on the right and the submerged walling on the left could not be anywhere near the eastern 'horn'. Moreover, Artemisia led her ships into the great harbour by a canal, whereas the submerged walling is actually in the great harbour. It seems almost inevitable that the secret port must have been on the east side of the isthmus, with a canal across to the west. This would agree with the words of the geographer who passes under the name of Scylax and wrote about or soon after the time of Mausolus; speaking of Halicarnassus he says that she has 'a closed harbour and another harbour by the island,

¹ See *Aegean Turkey*, pp. 106, 142.

and a stream'. By 'closed' he means closed with a chain in the usual way; this refers to the great harbour. The other harbour by the island would naturally be placed on the east of the present isthmus rather than on the west inside the great harbour, and it may be that Scylax is thinking simply of the open roadstead on that side off the quarter of Kumbahçe; on the other hand, he may equally well be referring to the secret port, which must have existed in his day. The word translated above as 'stream' means generally a river, but is also used occasionally of an artificial stream or canal; since there is nothing near Bodrum which could fairly be called a river, it seems very likely that the word is here used of the canal which joined the two harbours. Cutting across the isthmus this canal would produce the 'island' of which Scylax and other ancient authors speak. This explanation would, in the writer's opinion, be completely satisfactory if only there were some trace existing of the secret port in the required position, but neither there nor anywhere else does there appear to be any. Visitors to Bodrum may be interested in trying their hand at a solution of this puzzle.

Other remnants of the ancient city are scanty. The theatre was on the slope of Göktepe, but is now completely denuded. The curve remains in the hillside, but seats and stage-building are gone. Tombs are to be seen in various places, notably a rock-cut group below the summit of Göktepe. And the modern town is full of ancient stones; at almost every turn the visitor will come on fragments of antiquity.

The splendid Castle of the Knights Hospitallers (Pl. 24-6), which is no doubt the chief attraction of Bodrum today, cannot be described in detail here. It was built in the fifteenth century, at which time the Knights were established in Rhodes, largely, as was said above, with materials taken from the Mausoleum and other ancient buildings. It contains a small museum in three parts, including a selection of objects found during the underwater explorations recently carried out in the neighbourhood. Not the least interesting of these are the copper ingots, roughly in the shape of an oxhide, found in 1960 in a sunken wreck off Cape Gelidonya at the eastern tip of the bay of Finike. Similar ingots were previously known, and it was

supposed that they were a form of currency used in the days before money was invented, and that each represented one talent weight or the value of one ox—hence the 'oxhide' shape. But it seems that this cannot now be accepted. The forty specimens found in 1960 vary in weight from 35 to 59 lb., and hardly any two are of the same weight. The majority, but not




FIG. 13 Bodrum. Stone Anchor in Museum

all, bear marks which also vary greatly; they can scarcely be letters, but are thought to be rather foundry-marks. Probably then the ingots are not currency at all, but simple merchandise, and the 'lugs' at each corner, which give the 'oxhide' shape, are merely for ease of handling. From the pottery found the date of the wreck is estimated to be about 1200 B.C. (Pl. 22).

Other interesting items collected in the castle include: pre-historic and Dorian vases from an excavation at Dirmil near Myndus; Mycenaean vases and other objects, including a necklace of stone, found at Mûsgebi; a headless archaic statue from Caunus, thought to be of Apollo; a bronze figure of a negro boy; the cross-shaft of a huge anchor weighing over half a ton from the sea near Bodrum; a number of stone anchors which had apparently wooden flukes (Fig. 13); and finally a superb Byzantine steelyard.



The Myndus Peninsula

THE PENINSULA between Halicarnassus and Myndus is hilly, largely bare, and in summer almost waterless, but it contains a number of small coastal plains. This region was in early times occupied by the Lelegians, who, as we learn from Strabo, founded there eight cities; at first they were populous, but later the Lelegian race died out, and six of the eight cities were incorporated by Mausolus in his new capital of Halicarnassus. The other two, Syangela and Myndus, continued to exist. The




FIG. 14 Map of the Myndus Peninsula

names of the remaining six we learn from Pliny;¹ they were, with some variations of spelling, Termera, Side, Madnasa, Pedasa, Uranium and Telmissus. Syangela lay some distance to the east of Halicarnassus, the others all to the westward. What in fact happened in the fourth century was that Mausolus forcibly transplanted the inhabitants of the six cities and re-founded the other two, on fresh sites and on a greatly enlarged scale, to play their part as fully Greek cities in his new Hellenised Caria. The depopulated towns were abandoned, but their ruins remain; they are identifiable by their hilltop positions, their general lay-out, and the characteristic Lelegian masonry. They are in general rather remote and can only be reached, with considerable expenditure of effort, on foot.

MYNDUS

The classical city of Myndus is located with complete certainty at Gümüşlük. There is a direct road from Bodrum, or a longer and slightly better road by Karatoprak; both are passable for a car. But Gümüşlük is not the site of the Lelegian town of Myndus. This was a much smaller affair, paying only one-twelfth of a talent in the Delian Confederacy in the fifth century, and was remembered in later times as Old Myndus; it may be confidently identified with the ruins on the hilltop at Bozdağ about two miles to the south-east of Gümüşlük. Nothing survives beyond a ring-wall and the foundations of a large tower on the summit; but the sherds reveal occupation from prehistoric times to the early fourth century.

Mausolus' new foundation at Gümüşlük was on a much more ambitious scale. It had a well-sheltered harbour and a wall-circuit over two miles long. But the problem was to man it. The Lelegian inhabitants of the peninsula had mostly been transplanted to Halicarnassus, and for a long while Myndus was severely underpopulated, and much of the space inside the walls was unoccupied. It is said that the philosopher Diogenes once visited Myndus, and observing that the gates were large

¹ See above, p. 108, and note 1. The account given in this chapter adopts the conclusions reached in that article, where the numerous problems are fully discussed.

but the city small, advised the Myndians to keep their gates closed, or their city would be running away. In later times it was alleged that Myndus was colonised by the descendants of Aëtius, king of Troezen, at the same time as Halicarnassus, but this is clearly a fiction.

Alexander's halfhearted and unsuccessful attempt upon the city was mentioned above; but the Persian hold on it lasted only till the next year, when it was ended by the defeat of Orontobates. In the third century Myndus was mostly in the hands of the Ptolemies, and was still so in 197 B.C. when the Rhodians, as friends of Egypt, undertook to protect her 'allies' against Antiochus III of Syria, and gave their freedom to Myndus and others. It was after this, apparently, that the Myndians first began to issue their own coinage. The city was for a short while held by the rebel Aristonicus about 131 B.C., and after the murder of Caesar in 44 the 'tyrannicide' Cassius kept his fleet there; the city is likely to have suffered from his exactions. After the defeat of Brutus and Cassius at Philippi Mark Antony gave Myndus to the Rhodians, but she was soon taken away again owing to the excessive harshness of their rule. Imperial coinage of Myndus is noticeably scanty, and it may be that the city did not prosper under the Empire as much as most. The silver-mines, traces of whose working have been found in the neighbourhood, and which have given its name to the village of Gümüşlük, are not mentioned in any ancient source. Indeed, the only Myndian product of which we hear is the wine, and this had a poor reputation. It was one of those which were mixed with sea-water, a not uncommon monstrosity in ancient times; it is described as relaxing the stomach, causing flatulence and leaving a hangover. This unattractive beverage led to the Myndians being dubbed 'brine-drinkers'.

The site of Myndus is most attractive; there is hardly a better on the whole coast. The harbour is enclosed and well protected against the prevailing wind, the *meltem*, by the peninsula on the north-west. The fortification-wall on the mainland may be followed for its whole length, and is best preserved on the south-east, the most vulnerable side, where it is strengthened with frequent towers. It is about 9 feet thick, of regular ashlar, constructed in part at least of the green granite which was also

used for the Mausoleum. The quarries from which this stone was cut may be seen close to the shore at Koyunbaba, about two miles to the north.

The fortification also included the peninsula; a hundred years ago the wall could be traced all round, but has now disappeared. There remains, however, another wall running from



FIG. 15 Myndus. Harbour and Peninsula from the Acropolis Hill

north to south up the spine of the hill (Pl. 31; B on the plan). It has the same thickness as the mainland wall, but is built of larger blocks less regularly fitted. It has been called 'the Lelegian wall', but this name stems from the old belief that the Lelegian Myndus stood on this site; in fact the masonry is quite unlike that of the genuine Lelegian towns. This wall has always been something of a puzzle. As it stands, it appears meaningless; with the peninsula walled all round, what could be the point of dividing the interior down the middle with a wall of this solidity? It makes sense only as a continuation of just such a mainland wall as in fact exists, and must (in the writer's opinion) be the beginning of an earlier fortification system which was almost immediately abandoned in favour of a wall encircling the whole peninsula. Its position is comparable with that of the wall on the western extension of the acropolis hill at Caunus. It and the mainland wall will belong respectively to the earlier and later years of Mausolus' reign.

Otherwise hardly anything remains of ancient Myndus. Rock-cut stairways and house-foundations may be seen on the hillside, but virtually all the ruins seen in the early nineteenth century, including theatre and stadium, have totally disappeared; all that survives is a ruined basilica and, at the highest point of the peninsula, what may have been a church.




FIG. 16 Plan of Myndus

There are, however, numerous ancient stones to be seen in and around the village, and at the school about a mile inland there are some column capitals and Roman mosaics.

THE SIX LELEGIAN TOWNS

Pedasa

Of the eight towns this is the easiest to visit. It lies some ninety minutes' walk to the north of Bodrum, at the head of a pass, and is overgrown with pine-trees. The spot is called Gökçeler.

The ancient name survives in the village of Bitez a mile or so to the west.

Pedasa has even a little history of her own, and in the sixth and fifth centuries was apparently of more account than her neighbour Halicarnassus. Herodotus, himself a Halicarnassian, tells us that after the fall of Sardis in 546 B.C., when the Persian general Harpagus was overrunning Caria, the Pedasans held out for a time against him and gave him much trouble by fortifying the mountain of Lide.¹ The historian notes incidentally that whenever any misfortune was due to befall the Pedasans, their priestess of Athena would grow a great beard; this had happened three times.² Later, at the time of the Ionian Revolt, after 499 B.C., another Persian army came south to suppress the Carians who had taken part. After defeating them at Labraynda the Persians were ambushed and destroyed 'on the road to Pedasa' at night. Apparently they had attempted too long a march in this waterless country and had become benighted. The Persians had evidently some respect for the men of Pedasa, and after their capture of Miletus in 494, with the object of weakening these troublesome Lelegians, they transplanted some of them to a site in the hills above Miletus. This new settlement also took the name of Pedasa. In the Delian Confederacy Pedasa paid a tribute of two talents (as compared with Halicarnassus' one and two-thirds), later reduced to one talent.

From the sherds at Gökçeler it is clear that the place was not completely abandoned after its incorporation by Mausolus in Halicarnassus, but was retained as a useful outpost. It is likely that it was occupied by Philip V during his Carian campaign, for we are told that Pedasa was one of the places from which he was required in 196 to withdraw his garrisons. Polybius does not say which Pedasa is in question, but the probabilities seem to favour that at Gökçeler.³

The ruins at Gökçeler are quite considerable and show a characteristic Lelegian town. The main citadel, A on the plan,

¹ Lide is identified with the high mountain to the north-east, called on the Turkish maps *Kaplan Dağı* or *Tırman Dağı*.

² Or twice when Herodotus tells the story a second time.

³ The reader is reminded that many of the matters in this chapter are controversial; see above, p. 116, n. 1.

is some 170 yards long with a high wall of irregular masonry; at its upper (east) end is an inner enclosure or keep approached by a ramp and gateway, with a staircase in one corner. The main entrance, 8 feet wide, is at the west end. In the interior are




FIG. 17 Plan of Pedasa (Gökçeler)

many traces of buildings, especially close up against the inner face of the town wall. Below this citadel on the south and east is a larger outer enclosure with a wall of dry rubble masonry strengthened with towers; the towers, as often, show more regular workmanship.

On the ridges to the south and south-east are a number of

the remarkable 'chamber-tumuli' which are characteristic of the Lelegian country. These consist of a vaulted circular chamber approached by a passage and enclosed by a ring-wall heaped over with loose stones. Some at least of these tombs, from the pottery found in them, must date back to 700 B.C. or even earlier.

Telmissus (Telmessus)

There were two cities of this name in the south-west of Asia Minor; the other is located beyond all doubt at Fethiye in Lycia. Of the Carian Telmissus we are told that she lay sixty stades (rather less than seven miles) from Halicarnassus, in exceptionally fertile country, with a temple of Apollo who delivered oracles and was regarded as the progenitor of a priestly family of diviners. Even after Mausolus had transplanted her inhabitants to Halicarnassus she continued to exist as a religious community centred on the temple. The Telmessian diviners had a considerable reputation; they were consulted, for example, on more than one occasion by the kings of Sardis, and Arrian tells this story of the Phrygian Gordius, a poor farmer: an eagle settled one day on his plough and remained there till evening; to learn the meaning of this portent he went to Telmissus. There in a village he met a girl drawing water and told her of the strange occurrence; she happened to be of the priestly family and advised him (in true oracular fashion) to sacrifice to King Zeus. This he did in accordance with her instructions, and later married her; their son was Midas who afterwards became king of Phrygia.

At the required distance from Bodrum, on a hill above the village of Gürice, is a Lelegian town-site which must (in the writer's opinion) be identified with Telmissus. It has the characteristic form of an inner citadel and outer enclosure, with an entrance on the south-east; the masonry is of dry rubble. On the summit is a large square tower of good ashlar standing some 11 feet high. There are three tombs, a rock-cut chamber inside the circuit, a vaulted chamber-tomb in ruins outside the entrance-gate, and a handsome rock-cut tomb on the north-west. The fertile territory is the arable plain around Mûsgebi to the south. Mûsgebi (Misgibi) is a Turkicised form of

the old name Episkopi, and it is attractive to suppose that the modern bishopric has succeeded, as so often happens, to the ancient religious centre, the temple of Telmessian Apollo. A large Byzantine church was to be seen in the last century about half a mile from Müsgebi, but has now disappeared.

Termera

Before the foundation of the new Myndus by Mausolus, Termera was the leading city in the south-west of the peninsula; her tribute in the Delian Confederacy was at first two and a half talents, or just thirty times more than that of the Lelegian Myndus. Towards the end of the sixth century she was ruled by a dynast called Tymnes, who seems to have controlled all the country from Telmissus to the southern corner of the peninsula. Coins were struck in his name, as they were also by the dynasts of Syangela. Tymnes was succeeded by his son Histiaeus and then by his grandson Tymnes, who about 447 B.C. was expelled from Termera but continued to rule over his other possessions for at least another twenty years. After the removal of her population to Halicarnassus, Termera is said to have been used as a prison by 'the tyrants'. This presumably means the Hecatomnid rulers, and the statement may well be historically true. Forced transplantation of a people is always resented, and the dynasts may very likely have found it necessary to establish police posts, if only to discourage attempts by the evicted citizens to return home.

There was in antiquity a proverbial expression 'Termerian sufferings', of which two quite different explanations were given. One said that it referred to the sufferings inflicted by bandits operating from Termera; the other is more picturesque. A certain Termerus, we read, had the amiable habit of destroying those who came in his path by bashing them on the head; eventually Heracles gave him a dose of his own medicine and killed him in the same fashion. The proverb then applies to those who are paid in their own coin.

Of the site of Termera there is no doubt. Strabo says that it lay in Myndian territory opposite the island of Cos and above the promontory of Scandaria, and in this region there is only one possible site. It stands on a hilltop above the hamlet of

Çeşmebaşı (Aspat). The lay-out is typical—an inner citadel and an outer enclosure, as on the sites described above. The citadel has gates on east and west, and in the interior are foundations of buildings and a large double cistern coated with plaster. The outer circuit is poorly preserved except at the south corner, where a stretch of massive polygonal wall stands up to 17 feet in height. In it is a gate over 6 feet wide; the sides incline inwards to form an arch whose top is now lost.

There are two tombs of Lelegian type on the site itself, and many others on the ridges in the neighbourhood.

Madnasa

Except that she is mentioned by Pliny and by Stephanus of Byzantium (quoting Hecataeus), our knowledge of Madnasa is confined to the fact that she paid a tribute of two talents, later reduced to one, in the Confederacy of Delos. This, however, is enough to show that she was among the more important of the Lelegian cities. Her site is almost certainly to be identified with the considerable ruins on the hill above Türkbükü Bay and lower Göl. The outer enclosure here is over 300 yards long, with a wall of dry rubble 5 feet thick. At the summit on the south-east is a tower of regular masonry, with numerous buildings grouped around it. Within the enclosure are many traces of houses and half a dozen cisterns. The main gate was apparently on the north. At the north-west end is a second tower, and in the rock-face close by is a group of tombs.

Side

This is the most obscure of all the Lelegian towns. Apart from Pliny it is not mentioned at all, unless it be the same as 'Sibda, a city of Caria' recorded by Stephanus. And it is the only one of the eight, except Telmissus, which does not appear in the Athenian tribute lists. Its site, however, can be identified with some probability.

From the village of Göl a pass leads over to Belen on the way to Müsgebi; at its head are the ruins of a church, and a short distance to the south a fortress constructed of squared blocks. Half an hour's steep climb from here to the east, on the Karadağ mountain, is the wildest and most remote of the Lele-

gian settlements. Unlike the others it is in two separate parts. The northern is long and narrow, with a curved wall on the south and a line of cliff on the north, with a wonderful view over the valley and sea. The wall is built of the long, roughly squared blocks which give a characteristic look to the Lelegian masonry. The altitude has been estimated at 1,800 feet. There is as usual an inner enclosure, containing a building about 50 feet long.

The southern settlement is quite fascinating. It has a ring-wall of similar construction to the other, and the interior is packed with houses built close up against one another, not far short of a hundred in all, many of them standing up to 8 or 10 feet in height. Some of the houses contain several rooms, others only a single room; in some cases there appears to have been an upper storey. This part of the site seems to have been residential only. On these bare mountainsides the inhabitants must have lived mainly by pasture, and their forced removal to the urban life of Halicarnassus must have left them bewildered. There is no trace of occupation after the fourth century, and the houses have stood utterly deserted ever since.

Reasons for identifying this site with the Lelegian Side are circumstantial. The only other site on the peninsula, apart from those described above, which can reasonably claim to have been one of the Lelegian towns is close to the west coast at Burgaz;¹ this therefore is the only alternative. But a place so near to the sea is unlikely to have escaped enrolment in the Delian Confederacy, whereas we can easily imagine that the Athenian tribute-collectors would be disinclined to attempt to exact payment from the goatherds of the Karadağ.

For a long time, however, it was believed that this site was probably that of Telmissus. The distance from Halicarnassus, in a straight line, is just about sixty stades, though it is much more by any practicable route; but the chief reason for the identification was the church on the pass below. This is said to be built on the ruins of a Carian or Hellenic building (though the present writer was not able to confirm this); moreover, an inscription found in the village of Belen, but said on local authority to have come from this church, honours a man who

¹ See below, p. 126.

was 'piously disposed towards Apollo Telmisseus, and piously performed the sacrifices on behalf of the Telmissians and the city' (of Halicarnassus). It was accordingly thought that the church probably marks the position of the temple of Apollo; and the nearest site is that on the Karadağ above. This evidence is not altogether free from doubt. The church seemed to the writer to be built mostly of squared blocks taken apparently from the neighbouring fort, which may have given a false impression of antiquity; and, as every traveller in Turkey knows, villagers' information is not always to be relied upon. But the fatal objection is the character of the Karadağ site. Where, on these arid mountainsides, is the exceptionally fertile land which Cicero says that Telmissus possessed? There is no spot on the whole peninsula to which this description is less applicable. The Lelegian town at Gürice was not known until recently; now that the choice is available, it can hardly fail to be preferred.

Uranium

The historian Diodorus tells us that after the Trojan War the island of Syme was occupied by Carians, but that later, owing to persistent droughts, they fled from the island and settled in the place called Uranium. The town also appears in the Delian Confederacy, with a modest tribute. Nothing more is known of it. For its situation, the only remaining Lelegian site on the peninsula is that at Burgaz. This has the familiar form, with citadel and outer enclosure, and two towers; the pottery is of archaic and classical date. There are several 'chamber-tumuli' in the neighbourhood, including a particularly handsome one on the next hill to the north.

CARYANDA

Caryanda was not one of the Lelegian cities, and her site has long been a puzzle. This is not the place to examine all the rather confusing evidence; the conclusion to which the present writer has been led is as follows.

Strabo tells us that there was between Myndus and Bargylia a Lake Caryanda and an island of the same name which the

Caryandans used to inhabit. We must accordingly look for two sites, one on an island, and a later one on the mainland; and there are no inscriptions to assist the search. For the earlier site the most likely candidate is the island of Salihadası in the Bargylian Gulf; here there exists a walled town of fair size and apparently of classical date, though it is buried in such impenetrable forest and scrub that no clear idea of it can at present be obtained. From their island home the Caryandans moved, early in the Hellenistic period, to the mainland, and from this time on the name of Caryanda appears no more except in the works of the geographers. The mainland site, on the other hand, can be identified with reasonable certainty. The lake of Caryanda can hardly be other than the one lake which exists between Myndus and Bargyilia, namely that which gives its name to the present village of Göl (Lake). The lake is still there, though now reduced to little more than a marsh. In the third century this region lay on the territory of Myndus. Here then the Caryandans settled, becoming Myndian citizens, and their old name survived only for the lake. On the shore below the village of Göl are the ruins of a considerable Byzantine town; this has overlaid the Caryandan settlement, of which nothing now remains to be seen.



Syangela-Theangela

THE EIGHTH of the Lelegian cities, and the only one to the east of Halicarnassus, was Syangela. This and Myndus were the two which were not incorporated by Mausolus in his new capital. But this is not to say that he left them untouched; Myndus, as was seen above, was refounded on a new and more Hellenic site, and the same was done with Syangela. By a slight change the city's name was given the more Greek-sounding form Theangela. In this way Mausolus established in the Lelegian country three new cities of Greek type, one in the middle and one at each extremity west and east.

Apart from her preservation by Mausolus, all that we know of Syangela is that in the Delian Confederacy she paid regularly, together with her dependency Amynanda, a tribute of one talent. She was at this time ruled by a dynast, Pigres, who sometimes paid in his own name. A generation or so earlier, in 480 B.C., another Carian Pigres had served as ship-captain in the Persian fleet at the battle of Salamis; he was no doubt of the same Syangelan dynasty. An interesting series of silver coins bearing a griffin's head and dating around 500 B.C. was almost certainly issued by these same dynasts of Syangela; a group of about twenty was found in 1955 on the coast at Alâkilise, some of which were shown to the writer at Theangela in the same year. Like Tymnes at Termera, Pigres evidently controlled a considerable area of country.

Some four hours due east of Halicarnassus, above the village of Alâzeytin, is a thoroughly Lelegian site which may well be that of Syangela. The spot may be reached on foot in about three hours from Etrim, or in rather less from a point on the main Bodrum road north of Kızılağaç. A guide is of course necessary. Of all the Lelegian town-sites this is perhaps the

most attractive. The ring-wall is of dry rubble, with towers of more regular masonry; the interior is closely packed with solidly built houses, often standing to a good part of their height (Pl. 28). On the summit are the foundations of a large tower, and close by is a stepped base. The pottery, as usual, is mainly of archaic and classical date.



FIG. 18 Lelegian Chamber-Tomb (?)

A few hundred yards to the south, on a ridge, is an interesting group of half a dozen buildings. One is rectangular, the others circular. These latter, though they show some variety of form, all belong to a type found elsewhere in the Lelegian country, which has been given the name of 'compound chamber-tumuli'. They are built with two eccentric ring-walls converging on one side into a single wall; on the opposite side, where they diverge, the intervening space is divided by cross-walls into a number of chambers with vaulted roof. The plan of an unusually well preserved specimen is shown in Fig. 18.¹ All the interior walls have an inward curve, and some have supposed from this that the entire building was roofed over. This, however, can hardly have been the case; the average

¹ This is not at Aläzeytin, but on the hillside an hour east of Bodrum.

diameter is some 40 to 50 feet, and in one case as much as 150 feet, and in no case is there a sufficient accumulation of stones in the interior to suggest a collapsed vault. These buildings have generally been taken to be tombs, but it is at least a question whether they should not rather be regarded as sheep- or goat-pens; though perhaps surprisingly solidly constructed for such




FIG. 19 Theangela. Plan of the fort at D (Tetrapyrگون)

a humble use, they would certainly serve the purpose admirably.

The new city of Theangela was a very different affair. Her impressive ruins stand on the high hill directly above the village of Etrim and occupy three summits; the total length of the enclosure is over three-quarters of a mile, and its area comparable with that of Myndus. The city wall, two miles in length, is built mostly in the Lelegian style, with the main gate on the south side near the west end; its thickness is from 7 to 9 feet, and on the more vulnerable south side are frequent towers. As will be seen, this area was not entirely unoccupied when the wall was built.

At the top of the western hill the walls run up to a very fine and powerful fort, with a tower at each corner (plan, Fig. 19), entered from the city by a narrow passage with a right-angled

bend. Just outside, a small postern gate leads through the southern wall. The exceptional strength of this fort is evidently designed to resist artillery. Smaller forts are found on the south and at the east end, where the wall runs out to form salients (C and E on the plan).

At P an interior wall is carried across from north to south, dividing the city into two parts. Almost all the buildings lie to the east of this wall; the middle summit A carries a fortified enclosure, but the main habitation was on and below the eastern peak B. Evidently, here as at Myndus, Mausolus was unable to man his new city, and it was found advisable to reduce its size to less than half by means of this cross-wall.

At the summit of the eastern hill B is a tower in Lelegian style; this same style is seen in other buildings on the site, and shows the conservative tendencies of the builders. Below on the east are two large cisterns finely constructed, and on a terrace on this side was found a black and white mosaic floor. This peak is encircled by a wall to form a citadel, joined to the main city wall by cross-walls on north and south.

The public buildings stood on the lower slope of the middle hill, but they are not identifiable individually. At F is a handsome Lelegian house excellently preserved, with three rooms roofed with a 'corbelled' vault; that is to say, each course of masonry on each side projects beyond the course below so as to meet at the top. In the dip between the two peaks are other cisterns equally well constructed; one of them still furnishes drinking-water to the fire-watcher who lives during the summer in a hut on the western hill D. Theangela possessed no theatre; on the other hand there is, at M on the plan, a building in the form of a stadium, though it is little over 50 yards long, or barely more than a quarter of the usual length. No doubt it was used for athletic exercise.

But the gem of the whole site is perhaps the tomb Q on the slope of the eastern hill. It consists of a long narrow chamber 25 feet in length, with an antechamber at the east end; it runs parallel to the hillside. The roof is corbel-vaulted, and the projecting corners cut away to make a smooth surface. The roof is immensely solid, and on it, when it was cleared by Miss Akarca and the writer in 1955, were found no fewer than forty

stone balls about 6 inches in diameter. These are apparently cannon-balls, and it seems that the roof of the tomb must at some time have been used as an artillery emplacement. Previously there had been found inside this tomb, together with a




FIG. 20 Plan of Theangela

quantity of bones, fragments of vases dating to the latter part of the fifth century B.C. This exceptional tomb must be that of a distinguished man, and it is highly probable that Pigres himself was buried here; he is known to have been alive in 427 B.C. after a reign of several decades.

At that time the city of Theangela was not yet in existence, but there is evidence that the tomb was not entirely isolated on the hill. Archaic Greek statues have been found on the site,

apparently belonging to a sanctuary of Athena; and the writer was shown in 1955 a broken archaic figurine said to come from a spot near the eastern fort at E. It appears therefore that there was in early times a sanctuary on the hill, and it is natural that a dynast should have his tomb close to it. The desire to be buried as near as possible to a sacred spot is familiar in all ages.

Mention may also be made of two short stretches of curved wall at the foot of the mound on which the fort at D stands. These are quite unlike any other masonry on the site and appear meaningless in their present position; they must, it seems, be the remnants of an earlier ring-wall belonging to an isolated fort or outpost of the pre-Mausolan Syangela.

The fine new city of Theangela played a very small part in subsequent history. In Hellenistic times she claimed, like Myndus, to have been colonised from Troezen in the Peloponnese, and the Troezenians recognised the claim; in view of the underpopulation of the city, the settlement (if it really occurred and is not merely a copy of Halicarnassus) can only have been on a small scale. In the late fourth century a dynast by the name of Eupolemus was ruling in this part of Caria; as we learn from an inscription, he laid siege to Theangela, for some reason unstated; he failed to breach the splendid new walls, but succeeded in reducing the city to surrender on terms. Upon condition of no victimisation for the Theangelans and their allies he was permitted to occupy 'the city and the fortified posts'—that is, the forts A, B, C, D and E.

It was formerly believed that at some time during the second century B.C. Theangela lost her independence and became absorbed into Halicarnassus, but this has now been shown to be a mistake; there is even reason to believe that she was a 'free' city under the early Roman Empire. Surprisingly, Theangela seems never to have struck coins. As territory she commanded not only the Çiftlik valley to the south, but also the extensive plain of Karaova on the north. Of her products we know of only one, honey. Theangelan honey had indeed a wide reputation; and the latter-day descendants of the ancient bee-keepers have given its name to the *nahiye* of Mumcular (wax-merchants) some six miles to the north.

Supplementary note. A new publication by W. Radt of

recent investigations on the Halicarnassus peninsula (see the Bibliography) reached me too late to be made use of in this chapter. It records a number of hitherto unknown settlements, and to some extent changes and broadens the picture of Lelegian occupation.



Cnidus

THE SECOND mainland member of the Dorian hexapolis, and the only one after the expulsion of Halicarnassus, was Cnidus. The well-known site at the western tip of the long Reşadiye peninsula was excavated in 1857-58 by Sir Charles Newton, who sent to the British Museum several hundred cases of sculptures and other ancient stones. But this is not the original site of the city. Until about the middle of the fourth century B.C. Cnidus was halfway along the peninsula, near the present *kaza* of Datça, and all references in the classical Greek writers are to this site.¹ The reason for the change was undoubtedly the increasing importance of maritime commerce at that period; the site of the new city at Tekir is rocky, almost waterless, and devoid of arable territory within a distance of six miles, but for commercial purposes it could hardly be better placed. All through the sailing season a strong north-west wind, the *meltem*, blows day and night across the promontory, and sailing vessels coming from the south have great difficulty in rounding it; they are, today as in ancient times, frequently obliged to wait in the harbour of Cnidus till conditions are more favourable. Few merchant ships in antiquity would pass up the coast without calling there.

The Datça site, on the other hand, is of utterly different character. The Reşadiye peninsula is forty miles long from Tekir to the narrow isthmus at Bencik where it joins the mainland; in all this length, apart from small coastal patches, there are only two fertile areas. The whole of the eastern half is bare, mountainous and virtually uninhabited; the western half also is

¹ The proof of this change is given in the article by J. M. Cook and the present writer listed in the Bibliography. The ancient writers do not distinguish old and new Cnidus.

mountainous, rising in places over 3,500 feet, but has towards its western end on the south side a considerable extent of well-watered land reaching to the coast at Palamut Bay and supporting today a group of villages known collectively as Betçe (the five villages). And in the middle of the peninsula, south-west of the isthmus dividing the two halves, is the best and largest area of good land within fifty miles. 'The plain and valley of Datça', says Spratt, 'is very fertile, having fine groves of olive and valonia, and of almonds and other fruit-trees, with abundance of water, if properly utilized'; he speaks of its park-like scenery, and sees for it a promising future. (This last, it must be admitted, has been slow to materialise; in 1950 the writer, during a stay of several weeks, had the greatest difficulty in getting enough to eat.)

In this central area, then, the city of Cnidus was founded by Dorians from the Peloponnese, at a date somewhat later than the settlement of Rhodes and Cos. Herodotus says the colonists came from Sparta; this, if true, is almost the only experiment in colonisation that the Spartans ever made. Other accounts, however, attribute the foundation to the Argive hero Triopas; although his existence may well be doubted, a settlement from Argos appears more likely than the other.

At or about the same time a second settlement was made on the peninsula at Triopium. This was on Cnidian territory, and here was the sanctuary of Triopian Apollo, where the great Dorian festival of the Dorieia was celebrated by the six cities of the hexapolis. The site of Apollo's temple has not been discovered, though its approximate situation is hardly doubtful; more will be said of this below.

From the eighth century onwards Dorian and other colonies had been founded in Sicily by the Greeks, and early in the sixth century the Cnidians made a modest contribution of their own. A band of Cnidian emigrants settled on the north coast of Sicily and founded a city; the local Sicilians and Phoenicians, however, made life so uncomfortable that before long they transferred themselves to the island of Lipara to the north. The other islands of the group, including Strongyle (Stromboli), they tilled but did not inhabit. Here they found new enemies in the Tyrrhenian pirates, but these proved less

unmanageable; the Cnidians were frequently victorious and sent offerings from their victories to Delphi.

Meanwhile the Persians had overthrown the Lydian kingdom (546 B.C.) and were subduing the Greek cities of the Asiatic coast. As their armies moved gradually southwards under their general Harpagus, the Cnidians conceived the idea of defending themselves by cutting the narrow isthmus which joined their territory to the mainland and so making it into an island. As the work proceeded, however, it was found that the splintering of the hard rock was injuring the faces and eyes of the workmen more than appeared natural; they therefore applied for advice to the oracle at Delphi. The god replied, not in his usual hexameters but in iambic verse:

Dig not nor fence your isthmus: Zeus himself
Had made your land an island, had he so wished.

The Cnidians thereupon abandoned their plan, and when Harpagus arrived, submitted without resistance.

Before the geography of the peninsula was properly understood it was thought that the eastern half belonged to Bybassus, and it was accordingly supposed that the isthmus which the Cnidians began to cut was the neck of land near Datça. This, however, is a mile and a half wide, with a ridge of hills nowhere less than 100 feet high; as a rush job, with the Persians approaching, this is out of the question. The true site, as indeed Herodotus makes clear, is the much narrower isthmus at the extreme east end of the peninsula above the little bay of Bencik. This is about half a mile wide (Herodotus says five stades), and is much spoken of locally as a natural curiosity; the Turks call it Balıkaşiran, ('the place where fish may leap across'). In the last century it was often used for the portage of small boats. On the south side a trough about 100 feet wide runs in from the shore almost at sea-level and reduces the width of the neck that would require to be cut to little over 250 yards. The height of the col has been estimated as 50 feet, but seems in fact to be considerably more. Spratt in 1838 believed that he could see actual traces of the ancient cutting; in the hope of confirming this, Professor Cook and the writer in 1950 persuaded the driver of the bus conveying us to Marmaris to

stop while we explored the spot. Although the other passengers displayed no impatience or resentment, our examination was necessarily hasty, and we were not in fact able to find the traces noted by Spratt.

In the course of the seventh century a number of Greek states, mostly maritime cities of the Asiatic coast, had established a trading-station at Naucratis at the mouth of the Nile. Under Amasis, king of Egypt from 569 to 525, this was given the rank of a city. A large precinct containing temples and markets, called the Hellenium, was shared by half a dozen states, including Cnidus and Halicarnassus, and this was the only place in Egypt where Greeks were permitted to trade.

In the Delian Confederacy Cnidus paid to Athens a tribute varying from five to two talents, and was used by the Athenian admiral Cimon as a base for his expedition in 468 B.C. to the south coast of Asia Minor. In 412, however, the city was persuaded by the satrap Tissaphernes, acting in the Spartan interest, to revolt from Athens and quit the confederacy. The Spartans at once planned to use this new ally to advantage. A squadron of twelve ships, arriving at Cnidus, divided into two equal parts, half to guard the city and the rest to wait around Triopium and intercept the merchant vessels bringing corn to Athens from Egypt as they rounded the promontory. Learning of this an Athenian fleet at Samos sailed at once to the spot and seized the six ships at Triopium, whose crews escaped to land; then sailing on to Cnidus they attacked the city and in its unfortified condition almost succeeded in capturing it. Next day they renewed the attack; but during the night the Cnidians had improved their defences, and the sailors from Triopium had reached and entered the city; the Athenians therefore quickly abandoned their assault and returned to Samos after merely ravaging the Cnidian territory.

In reading this account of Thucydides it must of course be remembered that the city of Cnidus was then at Datça, not at Tekir. The captured Spartan ships must have been waiting either at Tekir, if there was at that time a usable harbour, or more likely in Palamut Bay some six miles to the east. From here to the city at Datça is rather more than seven hours on foot; from Tekir it is an hour or so longer; if the Spartan sailors

started some time after midday they would arrive about sunset or soon after.

As Dorians, the Cnidians may well have felt it more natural to be allied with Sparta than with Athens; but they did not remain very long in this condition. In 394 B.C. the Athenian admiral Conon, with the Persians now on his side, put an end to Spartan control of this region by his victory in a sea-battle near Cnidus. It was about this time that a group of maritime Greek states, including Cnidus, entered into an alliance in an attempt to remain independent of Athenian, Spartan or any other domination;¹ but in 387 the King's Peace brought them all once again under the Persian King until the arrival of Alexander in 334.

Some time during the fourth century came the great moment when the city moved from Datça to the new site at Tekir. The exact date is uncertain, but is likely to have been in the 360s. The move involved of course a great deal of activity and much disturbance. A great new wall-circuit was built; streets and houses were laid out on a rectangular plan; temples, theatres and other buildings were erected. It appears that the headland of Deveboynu (Cape Crio) was at the time an island; the Cnidians joined it to the mainland by a causeway, where there is now an isthmus, and constructed an artificial harbour on either side. The city occupied both the mainland and a large part of the peninsula; the public buildings were on the mainland, the peninsula being terraced for private residences. Not all of this could be done in a day, and an inscription gives us a glimpse of conditions shortly after the move. It is a public decree forbidding anyone to take up quarters in the sanctuary of Dionysus. Evidently the housing situation was such that a prohibition upon squatters was considered necessary.

It is likely, though not proved, that the change of site was accompanied by a change of constitution. Back in the early sixth century, according to Diodorus, the Cnidians who emigrated to Sicily and Lipara were 'disgusted with the severity of the kings', implying that the city was governed, like so many others, by a tyrant. Later, the tyranny gave way to an oligarchy, for Aristotle quotes Cnidus as a case where the

¹ See above, p. 25.

oligarchs were overthrown by the democrats because of the harshness of their rule. Democracy was accordingly established at least by about 330, the approximate time when Aristotle wrote. But it may well have been earlier than this. The most distinguished of all the citizens of Cnidus was the scientist Eudoxus, a many-sided scholar almost rivalling Aristotle himself. Mathematician, astronomer, physician, geographer, philosopher, he is recorded also as having drawn up a code of laws for his city. For this there could be no more likely occasion than the establishment of the democracy. Eudoxus died about 355 B.C.

A date for the move in the 360s is suggested by other circumstances also. The new temples in the city at Tekir required new cult-statues, and these were purchased from the outstanding sculptors of the time. In addition to the well-known Demeter, found by Newton (though it had been previously observed) and brought to the British Museum, we hear of a Dionysus by Bryaxis, an Athena and another Dionysus by Scopas, and above all the famous Aphrodite of Praxiteles. All these sculptors were contemporaries. Praxiteles is said to have 'flourished' between 365 and 360; this may mean that he was then about forty years of age, or perhaps that he created his most famous work, the Aphrodite, around that time. In any event, when the Cnidians ordered their new statue of the goddess, it happened that the men of Cos also had just done the same; and it further happened that Praxiteles had two Aphrodites ready in his workshop, one draped and the other nude. The Coans were given the choice and took the former; the nude accordingly remained for the Cnidians, and afterwards gained immensely more fame than the other, so that many people, as Pliny says, sailed to Cnidus simply to see it. Now the Coans too had moved the site of their city in 365 B.C., and it is hard to resist the conclusion that they and the Cnidians found themselves simultaneously in the same need to equip their new temples.

One other item of evidence points in the same direction. Eudoxus had an observatory at Cnidus, from which, although it was only a little above the level of the houses, he was able to observe the star Canopus. This observatory has not of course been identified on the ground, nor can the writer say how much

height would be needed to see Canopus; but it is obvious that much more height is available, and the houses must have extended much higher, in the new Cnidus than in the old, and if the observatory was in fact at Tekir, the change of site must date before 355.



FIG. 21 The Cnidian Aphrodite

The foundation of the new Cnidus marks virtually the end of the city's individual history. The new site must have brought commercial prosperity, at least for a time; down to the end of the Rhodian domination in 167 Cnidian coinage is abundant. After this, however, it becomes much rarer, and silver issues cease altogether; under the Empire it became very scarce indeed. If a city's prosperity may be measured by its coinage, the evidence is of a steady decline. Historically at least, Cnidus lived her best days on the old site at Datça. In early Imperial

times Cnidus is recorded as a 'free city', and was later the seat of a bishopric.

Hitherto little has been said of Triopium, which was at all times closely associated with Cnidus and formed part of her territory. The name is somewhat differently used in different contexts, and does not always mean quite the same thing. Herodotus, speaking of the Cnidians, says that 'their territory extends towards the open sea—Triopium, it is called—though it begins from the Bybassian peninsula'. His meaning is quite clear: Cnidian territory actually begins at the Bencik isthmus, but the eastern half, as far as the Datça isthmus, is a worthless mountain tract, and the only territory deserving of the name lies to the west of the city towards the open sea. This, he says, is called Triopium. How it got this name is uncertain; some said from the mythical hero Triopas, but more likely it was called 'facing three ways' by reason of its roughly triangular shape. Elsewhere Herodotus speaks of the 'Triopian headland', and Thucydides calls it 'a projecting headland of the Cnidian territory'; to others than the Cnidians themselves the important feature of Triopium was the Deveboynu promontory, an outstanding landmark and the difficult point in a journey up the coast. To a Cnidian, on the other hand, Triopium meant the western half of the peninsula, and in particular the fertile part of this around Betçe.

At the same time there is evidence also of a *town* of Triopium. Triopas is said to have 'founded' Triopium, which was named after him; and he can hardly have founded a peninsula or a headland. Still more significant is a passage of Arrian referring to the activities in 333 B.C. of Orontobates, the successor of the Hecatomnids. He was holding in the Persian interest Myndus, Caunus, Thera and Callipolis; 'and he had won over also Cos and Triopium'. If this means what it says, Triopium must at that time have had a government distinct from that of Cnidus, having broken away soon after the change of site. Such a state of affairs can only have been temporary. There is no tangible evidence, such as coins or city-decrees, of an independent Triopium, nor did anyone, so far as is known, ever call himself a Triopian.

Somewhere, then, in the western half of the peninsula was

the temple of Apollo, where was celebrated the festival of the six (later five) Dorian cities, at which the Halicarnassian Agasicles disgraced himself. Of the temple itself, as was said before, no trace has been found, but its general situation cannot, in the writer's opinion, be doubted. Only in the region of Betçe is the ground suitable for the celebration of games. The festival, we are told, included not only the normal athletic and musical contests, but also horse-races. So long as it was believed that Cnidus lay at all times at Tekir, the temple of Apollo was supposed to have stood on the headland of Deveboynu, and the absence of any visible remains was explained on the supposition that it had fallen into the sea; in fact there can never have been a stadium and hippodrome at Tekir.

At Betçe, on the other hand, there is abundant level ground with water, and even more to the point, here alone between old and new Cnidus are the ruins of a considerable town. On a steep hill above the village of Kumyer is an acropolis heavily fortified with walls of early date, with a copious spring on the south side; sherds from archaic to Roman times, and an inscription in the archaic Cnidian script, have been found on it, and another inscription reveals the presence of a precinct of Asclepius. This must surely be Triopium.

As is clear from Thucydides' narrative,¹ Triopium possessed a harbour distinct from that of Cnidus; Cimon in 468, with a fleet of 200 ships, had made Cnidus and Triopium his base. This harbour can hardly be other than Palamut Bay below Kumyer. This is an open roadstead with a small island, Baba Ada, lying half a mile offshore. The bay itself is somewhat exposed, though not to the prevailing north-wester, but there is evidence that the Cnidians converted it into a first-rate harbour by means of a sea-wall extending from the island to the mainland. All that can be seen of this today is a line of shallow water projecting from the south end of the island, and another projecting towards it from the mainland opposite; but the coastguard stationed on the shore in 1956 reported that there was in fact a submarine wall at this point, which he had seen with his schnorkel apparatus and on which he often caught his

¹ See above, p. 158.


fishing-line.¹ Such a wall—or perhaps rather two moles with an entrance in the middle—would make a roomy anchorage, sheltered from all sides, and if it really exists is conclusive proof that this is the harbour of Triopium. Even without a wall, an anchorage is marked here on the Admiralty Chart.

The festival of Triopian Apollo was probably of some importance in early times as a gathering-place for the Dorian states; later, however, it seems to have declined, and very little is heard of it. Ptolemy II showed some interest and may have attempted to revive it, but without much noticeable effect. Among the hundreds of inscriptions recording the victories of athletes all over the world in Hellenistic and Roman times only two make mention of the games at Cnidus; both the victors are local men, one from Cos and one from Cedraeae. An ancient commentator on Theocritus makes the surprising statement that these games were celebrated in honour of the Nymphs, Apollo and Poseidon; there is no mention elsewhere of any but Apollo, and this information is generally agreed to be unreliable.

Triopian Apollo, however, was not the principal deity of the Cnidians themselves; this was Aphrodite. From the seventh century down to Roman times nearly all the coins of Cnidus bear the goddess's head on the obverse or reverse. She had the special title of Euploia, 'of fair sailing', and after the move to Tekir this is symbolised on the coins by the prow of a ship. Her temple and statue at Tekir, as was said before, was a tourist attraction of the first order. The form of the statue is familiar from the numerous copies made in later times; the form of the temple was unusual, and seems to have been designed less for public worship than to show off Praxiteles' masterpiece. In the first place, it was not rectangular but round. Round temples were quite exceptional in Greek lands; on the other hand, they are often seen in Roman wall-paintings, and in some cases at least occur in association with Aphrodite (Venus).² On a monster show-boat constructed by Ptolemy IV of Egypt there is said to have been a circular

¹ This information was communicated to the writer by Dr Wilder Penfield of Montreal.

² They are found, for example, on the walls of bedrooms.



27 Lagina. Gate of the Temple Precinct.



28 Syangela (Aläzeytin), Lelegian houses.




29 Syangela, Chamber-tumulus.



30 Theangela, Door of cistern.



31 Myndus, 'Lelegian' Wall.



32 Theangela. Tomb (of the dynast Pigres?)


33 Loryma. The Fortress.



34 Cedrae. Wall and Tower.

35 Cedrae. The Theatre.





38 Caunus. Rock-tombs.

36 Cnidus. Round Temple, probably of Aphrodite, in 1969.


37 Amos. View from Acropolis.




39 Idyma. Rock-tomb.




40 Caunus. View over the Harbour; western acropolis on left.



41 Caamus, The Long Wall.



42 Caamus, Newly excavated building.






45 Alabanda. Aqueduct.

43 Alabanda. The Theatre.

44 Alabanda. Council-House.



46 Alabanda. Temple of Apollo Isotimus in 1939.

47 Alinda. Market-hall and Agora.




48 Alinda. The Theatre.

49 Alinda. Half-buried Stage of the Theatre.



50 Alinda. Interior of the Market-hall.



51 Alinda. Aqueduct.



52 Alinda. Tomb in use as a house.



53 Alinda. Tower in the City Wall.

temple of Aphrodite containing a marble statue of the goddess; and in Hadrian's Villa at Tivoli there is a round building with an open Doric Colonnade in which was recently found a copy of the Cnidian Aphrodite. This building is likely to be a replica of the temple at Cnidus, for it was Hadrian's whim to fill the grounds of his villa with reproductions, more or less fanciful, of famous features of the Greek world.

In the second place, the temple had at least two doors, perhaps more. Pliny says that 'the whole temple is opened, so that the statue may be seen from all sides'; he appears to mean that it may be opened, that is, there are doors, on all sides. A work entitled *Love Affairs*, passing under the name of Lucian in the second century A.D., gives an account of a visit to Cnidus. After admiring the gardens which filled the precinct the party entered the temple and stood amazed before the beauty of the statue in the middle; then, wishing to see the back as well (for the statue was noted as being equally lovely in all aspects) they went round to the rear of the temple, where the door was opened for them by the old woman who held the key. The back of the statue proved indeed to be in no way inferior to the front; they noticed, however, a dark patch like a stain on the inner side of the thigh. At first they supposed this to be a flaw in the marble, and admired the skill of the sculptor in contriving that it should come in so inconspicuous a place; but the old woman explained that this was not so. There had been, she said, a young man who fell in love with the goddess and dreamed of marrying her. All his days he spent in the temple from morning to evening; and to estimate his chances he cast knucklebones (the ancient dice) in the hope of making the throw named after the goddess herself, when all four dice showed different faces. Finally, driven to desperation by his desire, he concealed himself in the temple one day and contrived to remain hidden when the doors were closed for the night. In the morning the mark of his passionate embraces was clear on the marble, and there it remained ever since.

From these accounts it is supposed that the temple had no cella wall, but that the spaces between the columns were closed with barriers, two or more of which contained doors. These barriers reached only halfway to the roof, leaving an open

space above. It need hardly be emphasised how utterly unlike a normal temple this would be; but a representation of just such a building does in fact exist. In the Villa of Julia Felix at Pompeii a wall-painting shows a round temple with panels between the columns up to half their height; and above one of the panels rises the upper part of a female statue. In the temple at Cnidus the interior arrangements are uncertain, but evidently there must have been barriers there also, since Lucian's party could not simply walk round the statue but needed the back door to be opened for them.

In 1969 the American excavators discovered a round building at Cnidus which seems to have every chance of being the famous temple of Aphrodite;¹ their next hope is to find the statue itself, declared by Pliny to be the finest not only of Praxiteles' works but in all the world. Nicomedes, king of Bithynia, is said to have offered to pay the whole of the city's debts in exchange for it, but the offer was not accepted. These debts must have been considerable, and to some extent confirm the decline in the city's fortunes. An ancient writer says that the statue was later taken to Constantinople and there destroyed by fire, but this report is now generally disbelieved.

Among the human denizens of Cnidus the most distinguished is certainly Eudoxus. He is best known as an astronomer. In the early fourth century astronomy had barely begun to make the scientific advances which culminated in the brilliance of the Alexandrine era; Eudoxus, however, felt himself able to declare that the diameter of the sun is nine times greater than that of the moon, and three times greater than that of the earth. Cnidians also were the architect Sostratus, builder of the lighthouse at Alexandria which was reckoned among the Seven Wonders of the World, and the historian Ctesias, who wrote of India and Persia; he was also a member of a family of hereditary physicians, for Cnidus was a famous seat of medicine. Ctesias is said to have served as court physician in Persia and to have cured the Great King Artaxerxes II of a wound suffered in battle.

One or two Cnidian products are mentioned as deserving the

¹ See below, pp. 150-1.

gastronomer's praise, in particular the wine. This is said to be nourishing, enriching the blood and promoting easy movement of the bowels, but relaxing the stomach if drunk in excess. Cnidian vinegar is bracketed with the Egyptian as the best to be had. Mention is also made of a special kind of cabbage, curiously called 'briny'; what this may have been like is not known, but the best was grown at Cnidus.

The site of Old Cnidus lies immediately to the north of the Iskele of Datça, where is the present administrative centre of the *kaza*. The acropolis is on a blunt headland about a mile from the Iskele, a little to the south of the point where the Datça Çayı reaches the sea. The summit is defended by a fortification-wall enclosing an area about a quarter of a mile long; the masonry is a mixture of ashlar and polygonal. On the seaward side it stands not on the cliff but at its foot at sea-level; but the sea has risen since antiquity. This is the best preserved part, standing up to six courses; it is of a type which dates generally around 400 B.C. Whether this wall was standing at the time of the Athenian attack in 412 B.C.¹ is uncertain. Thucydides calls the city 'unfortified', but during the night the defenders 'improved their defences', so perhaps he means that the walls were in disrepair or had been partially dismantled, in which case the present wall may be a replacement of the defective fortification. Nothing is standing inside the wall, but the ground is thickly strewn with pottery ranging in date from the seventh century down to Hellenistic times. The spot is now called Dalacak. On its south side remains of a small harbour may be seen in the water.

This was not of course the whole city; there are indications of an outer defence line enclosing a very considerable area. To the north of the acropolis great quantities of large squared blocks are lying in the water, and belong evidently to a collapsed sea-wall extending to the mouth of the Datça Çayı; and on the south bank of the stream a clearly defined shelf, over a mile long, runs inland west and then south. This shelf appears to mark the line of a wall, of which only a few loose square blocks and some of the rubble filling may now be seen. This

¹ See above, p. 138.

outer wall no doubt ended at or near the Iskele, and would enclose an area not far short of two square miles.


Within this area, to the south and especially to the north of Dalacak, important finds have been made in the past, though little is visible today. In particular, early in the present century, a Greek of Syme carried out excavations at a spot near the mouth of the Datça Çayı and found an archaic sanctuary 'very rich in offerings of the greatest importance', and also another archaic building; neither of these is now to be seen. On the shore, however, close to the rivermouth, are the solid foundations of a large building which appears, from the olive-press lying in it, to have been an oil-factory.

Just to the south of the Iskele is a platform some 70 feet long, supported by terrace walls of heavy polygonal masonry; here was perhaps a small sanctuary. Masonry of this type occurs in numerous places on Cnidian territory and seems to be of Hellenistic date. Most of the finds at Old Cnidus have been made at a considerable depth, and there is no doubt that the archaic and classical remains are deeply buried.

It is clear from the sherds and other remnants that the site of the old city was not abandoned after the move to Tekir; this is after all the most fertile part of the peninsula. Pliny gives Stadia as an alternative name for Cnidus; this name appears later in the lists of bishoprics, and survives in the modern Datça. It may safely be accepted as the name of the old city after the change of site.

To the north-west of Dalacak, on the north side of the peninsula, is a second harbour known at present as Körmən Limanı; built into a mosque half a mile from the shore is an archaic capital subsequently reused as a boundary-stone and inscribed in letters of the fourth century 'Boundary of the Harbour'. Körmən Limanı is little used nowadays, but must have been popular in antiquity for vessels coming from the north as far as Old Cnidus, to avoid the difficult return journey round the cape.

From Old Cnidus at Datça to Triopium at Kumyer there must always have been a road, and in fact its course may be traced; it follows closely the line of the present track, and seems to have been of a width to take two lines of traffic. After



- | | |
|--------------------------|-------------------------|
| A - Acropolis | G - Odeum |
| B - Trireme Harbour | H - Temple of Aphrodite |
| C - Southern Harbour | J - Corinthian Temple |
| D - Upper Theatre | K - Roman Tomb |
| E - Sanctuary of Demeter | L - Lighthouse |
| F - Lower Theatre | M - Agora |

FIG. 22 Plan of New Cnidus

the foundation of the new city the road was extended to Tekir. Just beyond Kumyer it crossed a stream by a bridge, of which the greater part is still standing; it is among the more notable specimens of ancient Greek bridges. On either side a long abutment leads to the actual bridge, which spanned the stream in the form of a triangular or trapezoidal arch (the top is missing). The style of the masonry suggests a date around 300 B.C. As the road approaches the new city it is lined on both sides with tombs, forming a very extensive necropolis.

New Cnidus at Tekir must have been a most attractive city.

Strabo describes it as 'a kind of double city', for much of it occupied the off-lying island, which the Cnidians joined to the mainland by a causeway. He reckons the perimeter of the 'island' at seven stades, a slight underestimate. The main part, however, was on the mainland, and was laid out on the 'Hippodamian' plan, with streets crossing at right-angles. The steep gradient, as much as 1 in 3 in places, made it necessary for some of the north-south streets to be stepped. The fortifications enclose about two-thirds of the 'island' and an area on the mainland rather less than a mile long and a half a mile broad; the new city was thus smaller than the old, but more concentrated. The wall is best preserved on the north side, where it runs up to an acropolis on the east; the masonry is a regular ashlar. There are three gates, two on the north and one on the east. The towers are rectangular except for one at the mouth of the northern harbour which is still in excellent preservation.

This northern harbour is called by Strabo the 'Trireme Harbour', and is said to provide anchorage for twenty warships; it was closed with a chain in the usual manner. The commercial harbour on the south is much larger, with an entrance partially closed by a mole on either side; remains of the moles are visible under water and constitute a hazard to vessels entering. This harbour must have been constantly filled with wind-bound ships coming from the south.

High up on the north side is a large theatre, but it is poorly preserved and the eastern half has entirely collapsed. To the east of this, at the foot of a steep scarp, is the precinct of Demeter which was excavated by Newton and produced the splendid seated statue of the goddess which is now in the British Museum.

The American excavations have already done much in the way of clearing the buildings previously known but subsequently buried, and have added fresh discoveries to them. Among the latter the most exciting is certainly the round building which is in all probability the temple of Aphrodite. It stands on the slope overlooking the isthmus on the north; the site is a good one, but the rock-wall behind, and the rocky slope in front, seem to leave little room for the splendid gar-

dens which aroused the admiration of Lucian's party. The temple stood on a round podium about 5 feet high, with two steps above. At the time of writing it is only partially cleared, but the statue-base has been found; it is a block of dark grey stone with a surface 51 by 44 inches, most of which is occupied by a D-shaped sinking 2 inches deep which held the base of the statue itself. Pl. 36 shows the condition of the building at the end of the season of 1969.

The lower theatre has been cleared and proves to be in good condition. There are some thirty-five rows of seats, with two diazomata and an arched entrance on either side. Of the stage-building, however, little or nothing is to be seen. The theatre is estimated to hold about 8,000 people. The odeum G was also a handsome little building, but not very much of it is left.

The necropolis outside the city wall on the east is extensive and contains a great variety of tombs. In the north-east area are two rock-cut tombs approached by a *dromos* or walled passage; the entrance to the tomb is in one case triangular, in the other trapezoidal. In some cases the tombs are grouped at the rear of an open enclosure forming a family burial-ground. On the peninsula (K on the plan) is a fine built tomb of Roman date; in front is a vestibule paved with black and white mosaic, and behind this a chamber with apse at the rear and niches in the side walls. It contained originally three sarcophagi, of which only fragments are preserved.

The excavations have produced a number of sherds of the fifth century B.C., so that Tekir was evidently not unoccupied before the city moved there in the fourth century. We may hope that future discoveries will show what was there in the classical period.

As on other ancient sites in Turkey, the excavations have resulted in an accession of civilisation at Tekir. In 1950 the place was utterly deserted except for the lighthouse-keeper and a party of gendarmes; in 1970 the writer was surprised to find three restaurants on the spot, and visitors are now frequent. The site is reached by boat from Bodrum (the crossing taking up to six hours if the sea is at all rough) or from Marmaris; the motor-road goes as far as Datça, and the track from there onwards is suitable only for a jeep.

Supplementary Note. The identification of the newly-found circular temple as that of Aphrodite was confirmed in 1970 by the discovery close by of a large marble block with a fragmentary inscription containing the beginnings of the names Prax(iteles) and Aph(rodite). The purport of this inscription is not clear; perhaps it was a sort of advertisement for the statue, unusual though this would be, for Praxiteles' masterpiece, as was said above, seems to have been treated by the Cnidians more as a showpiece for visitors than as a normal cult-statue.

More controversial is another claim recently put forward by the excavator, Miss Iris Love. Exploring 'under the dust of ages' in the British Museum basement among the stones sent back from Cnidus by Sir Charles Newton in 1859, she found a marble head which she at once declared to be that of Praxiteles' Aphrodite, unrecognised in the museum vaults for more than a hundred years. It seems, however, improbable that this claim will be substantiated; the museum authorities point out that the head was found by Newton, not on the site of the Aphrodite temple (which was not dug by him) but on that of the sanctuary of Demeter and Persephone at the other end of the city, over half a mile away. The head itself is too much damaged to be immediately recognisable, but is thought at the museum to belong in all probability to a statue of Persephone, companion to the well-known figure of Demeter found close by in the same sanctuary. The controversy seems likely to raise a good deal of dust before it is settled.



The Rhodian Peraea

IN THE Dorian migration to Asia the principal settlement was on the island of Rhodes. Her three cities, Lindus, Ialysus and Camirus, which were known to Homer, made up half of the Dorian hexapolis. These cities remained separate and independent until 408 B.C., when they united to form a single Rhodian state; a new capital city of Rhodes was founded on the site which she has occupied ever since. The old cities were not abandoned but continued to maintain their own individuality within the new state.

Before this time the history of Rhodes is an almost total blank, but it is clear that from an early period the individual cities had possessed territory on the mainland of Asia opposite the island; this territory now became part of the Rhodian state, and its inhabitants had full status as citizens of Rhodes. The area in question comprised the peninsula south-west of Marmaris, commonly called the Loryma peninsula, and somewhat later the land to the north and north-west as far as the Ceramic gulf.

But as time went on Rhodes acquired, permanently or temporarily, much other territory on the mainland, which she held in the capacity of suzerain; this country was governed by Rhodian officials, but its people were not Rhodian citizens. The land around and to the north of the east end of the Ceramic gulf was probably annexed in the early third century, and the acquisition of Stratoniceia followed soon afterwards. About 190 B.C. the Rhodians bought Caunus from Ptolemy of Egypt for 200 talents. And in the following year they received as a gift from the Romans the whole of Lycia and Caria south of the Maeander. This gift was rescinded in 167, and Stratoniceia was never again Rhodian, but the country between there and the

Ceramic gulf continued to be controlled by Rhodes at least until the second century A.D. The Lycians had refused to acknowledge Rhodian dominion and had never been effectively annexed, nor did Rhodes ever regain central Caria. Lycia always excepted, the whole of this region, so long as it was under Rhodes, made up the Rhodian Peraea. Its heart was always the rocky and mountainous Loryma peninsula.

Following the main road south from Aydın by Çine the traveller reaches Rhodian territory at Muğla. Now the capital of a large *vilâyet*, this was only a small place in antiquity. Its name was Mobolla, which survives with little change; the intermediate form Mogola is recorded. A handful of inscriptions has been found here, attesting Rhodian domination, and there are some insignificant ancient remains on the flat-topped hill behind the town; otherwise nothing survives.

South-west of Mobolla lay the towns of Pisye and Thera. The former has kept its old name as Pisiköy. It is mentioned occasionally in literature and in inscriptions, but was never important. The acropolis hill is a mile or so south of the village, and there are some ancient stones at a spot about the same distance to the north-east. Thera is in very similar case. It makes one appearance in history, when it was held as a strong-point by Orontobates, the successor of the Hecatomnids, in 333 B.C., before it had become a Rhodian possession. The site is proved by inscriptions to be at Yerkesik, but has little or nothing to show today.

More interesting to the traveller are the ruins of Idyma. As the road from Muğla to Marmaris comes in sight of the Ceramic gulf, at the top of the Sakarkaya, a view opens up which is quite superb. To the west is the sea; to the south are the hills which conceal Marmaris, topped by the pointed peak of Altınsivrisi; to the south-east in the distance is the lake of Köyceğiz. And directly below, some 2,000 feet down, is the little plain which nourished the men of Idyma. Descending the road obliquely down the mountain-face the traveller will perceive at one point, below him on the left, a line of ancient wall forming an elongated oval, and looking rather like a giant ship wrecked on the mountainside. This is the acropolis of Idyma. It is most easily reached from the road above; the climb from

the plain is arduous to a degree. The masonry is roughly coursed, with ashlar work here and there; in the middle is a solid building with a number of rooms. The wall is best preserved on the north side. Extending down the hill is an outer enclosure, but its wall is largely destroyed.

Much lower down the hillside the road passes another and larger fortress of mediaeval date. As it reaches the plain it runs eastward beside a short but abundant stream, probably the ancient Idymus; before turning right to cross the plain it passes a group of rock-cut tombs. Three of these are plain, but two are of temple-tomb type with Ionic architectural façade; one had two columns, of which one is now destroyed, the other had rather surprisingly a single column in the middle. The former is cut clear of the rock, affording a passage all round it (Pl. 39). These tombs date in all probability to the fourth century B.C. Of similar type and similar date is another tomb, among a group of plain chamber-tombs, well up the hillside above the village of Kozlukuyu and below the acropolis. Numerous inscriptions found in the village leave no doubt of the identity of the site. Idyma was one of the comparatively few cities in the Rhodian Peraea which had formerly been members of the Delian Confederacy; she was at that time ruled by a dynast Pactyes, who struck coins in the name of the Idymians. The city belonged to Rhodes before 200 B.C., but was subsequently lost, then recaptured by the Rhodian general Nicagoras.

A close neighbour of Idyma was Callipolis. This name is evidently preserved in the village of Gelibolu on the coast some six miles to the south-west, where there are several forts, ancient and mediaeval, and other evidence of occupation, including two or three amphora-factories and an inscription of Rhodian type. Nevertheless it is clear that this cannot be the site of the Hellenistic and Roman Callipolis; the remains are not such as to suggest a city, and it is sure that none can ever have stood here. The true site is indicated by an inscription found at a spot about six miles inland called Duran Çiftlik; it is a dedication to the Empress Domitia by the people of Callipolis. The remains at Duran Çiftlik show that a sanctuary stood here, succeeded in later times by a church; the city itself

was on the hill, some 800 feet high, above the village of Kızılyaka a mile or so to the east. Little is now standing on the site, but the slopes are thickly strewn with pottery and loose building-stones; on the summit is a tower of poor-quality masonry. The ring-wall has disappeared above ground, but its line is marked by a clearly defined shelf running most of the way round the hill. On the east side is a group of simple graves formed of thin stones set on edge and covered with stone slabs. From this site the name of Callipolis must have been transferred to the coast at Gelibolu at some date during the middle ages; the occasion for this move can only be conjectured.

One hour's walk over the hill from Gelibolu to the west is the tiny village of Taşbükü. Lying rather more than a cable off-shore is a small island called variously Şehir Ada, Şehiroğlu or Sedir Ada; a boat of some kind is generally available either at Taşbükü or at Gelibolu. The island carries the ruins of Cedraea, one of the most considerable demes of the Rhodian Peraea. Close to half a mile in length, the island is divided into two parts by an isthmus in the middle; the ruins lie exclusively on the eastern half. Here a powerful wall in regular ashlar, with numerous towers, runs round close above the shore (Pl. 34). Near the central point are the foundations of the temple of Apollo, in the Doric order, on a platform supported by a solid wall well preserved; here again the temple was succeeded by a Christian church. Close by, on the north slope, is a good-sized theatre in excellent preservation, though buried in jungle; this is one of the three theatres known in the Peraea (Pl. 35). The lower parts, including the stage and orchestra, are buried, but fifteen or sixteen rows of seats are still to be seen. The cavea is divided by stairways into nine wedge-shaped sections (*cunei*); there is no sign of any diazoma. Terrace walls adjoin the theatre on either side; that on the west is especially well preserved, with handsome bossed masonry. To the east of the theatre many ruined buildings are discernible among the thick vegetation.

The agora seems to have lain towards the west, supported by a fine wall of regular ashlar whose courses are distinguished by horizontal cuttings along the edges of the blocks. Numerous inscriptions have been found here of the types that normally

adorned the market-place. The inscriptions contain references to at least three athletic festivals celebrated at Cedrae, so that the city must presumably have possessed a stadium, but none has been discovered.

On the mainland opposite the island is an extensive necropolis; the tombs are mainly large sarcophagi and built tombs with vaulted roof and containing sometimes more than one chamber.

Although the name Cedrae is apparently Greek, derived from the name of the cedar-tree, the city was in origin purely Carian. In the Delian Confederacy it paid a tribute of half a talent or rather less. Towards the end of the Peloponnesian War, in 405 B.C., while Cedrae was still an ally of Athens, the Spartan general Lysander attacked her, and taking her by force at the second attempt, sold the inhabitants into slavery. Xenophon, who records this event, describes the Cedreates as 'half-barbarian'. At some uncertain date after this, Cedrae was taken over by the Rhodians and fully Hellenised as a deme of the Rhodian state. No coins of the independent city are known, and after the incorporation into Rhodes there could of course be no question of striking money.

The country west of a line drawn from Cedrae to Marmaris is today very thinly populated. In antiquity it formed that part of the Peraea which was called Apeiros (the Mainland), and contained, so far as is known, two Rhodian demes. The more considerable of these is on the high and steep peak of Altınsivrisi (Golden Pike), the highest point in this region. There is a citadel on the summit, hardly less than 2,000 feet above sea-level, and substantial remains of the town on the slopes. This is almost certainly Euthena, one of the larger Peraean demes. The other is on a headland close to the village of Söğüt. Here is a fortified site with a handsome wall up to 18 feet in height, with a gate on the north; on the shore of the bay below is a short stretch of ancient quay-wall in good ashlar masonry with bossed faces. This is likely to be the deme of Amnistus.

There is no such uncertainty with regard to Marmaris, whose ancient name is abundantly proved by the inscriptions found there. This is the site of Physcus, the most important of

all the demes in the Peraea, and the only one to be named separately in the governor's command. As a deme it was attached to the city of Lindus, and was incorporated in the Rhodian state at least by the time of Alexander the Great (as an inscription shows), and no doubt a good deal earlier. Strabo makes the extraordinary statement that Physcus was the port of Mylasa; the error is the more surprising as more than once elsewhere he gives it its true position. At the south end of the present town is a low hill carrying a mediaeval castle picturesquely mingled with modern houses; this, however, is not the acropolis of Physcus, which was on a much higher hill called Asar Tepe a mile or more to the north. On this hill are some remains of walls dating to classical and Hellenistic times, but nothing is standing inside them. Nor does Marmaris itself contain any remnants of antiquity apart from the inscribed and sculptured stones which are collected at the school; these include a marble lion lacking the head, a slab with relief of a man and a horse, and a fine marble head of a young Roman lady from the beginning of the Empire.

As was said before, the heart of the Rhodian Peraea was the Loryma peninsula. This is mountainous, rocky and steep, wooded in the northern part but bare in the south. There is a passable road from Marmaris to Bozburun, and boats may be hired at Marmaris for a tour of the peninsula; otherwise all exploration must be done on foot.

Sailing south across the fine bay of Marmaris and passing through the narrow entrance, the traveller comes shortly in sight of a small headland known as Hisarburnu. There is a landing-place on the shore, and close above are the ruins of Amos, another of the important Rhodian demes. The spot is called Asarcık. The top of the hill is encircled by a wall 6 feet thick, standing up to 10 or 12 feet in height; the masonry is of the type called 'coursed polygonal'. This style is characteristic of the early Hellenistic period, and all the visible remains at Amos seem to be of this or similar date. The wall is provided with towers and a gate on the north side. At the west end of the acropolis are the scanty remains of a small temple about 45 feet long, and several uninscribed statue-bases. The plan is with difficulty recognisable as that of a temple *in antis*. On the

north-east slope is a small theatre, the second of the three known in the Peraea. It is in fair preservation; the rows of seats remain in part, and the analemmata stand up to 17 feet in height. The stage-building was divided into three rooms, still distinguishable; and in the orchestra, lying broken in two pieces, is the altar on which sacrifice to Dionysus was made before each performance. On the north slope of the hill, on a small terrace, the writer found in 1948 four inscribed fragments containing the terms of three land-leases issued about 200 B.C. These leases are very detailed, with precise instructions for the payment of rent, provision of guarantors and development of the property; the tenant must build a minimum number of sheds, plant a minimum number of vines and figs, with minimum space for corn between, and dig a drainage-trench. Penalties are fixed for failure to observe these conditions, and also for cutting wood on the property, burying a corpse in it, or encroaching on the public roads. It is evident that the leases were first leases of the estates, and we have evidence of a scheme of agricultural development initiated in the early second century, apparently by the Rhodian government. The visitor to Amos may well wonder where, in this rough hill-country, these estates may have been; it is probable that they lay on the flat plain by the present village of Gölenye, which no doubt belonged to Amos—one of the few pieces of flat land on the peninsula. The principal deity of Amos was Apollo, with the otherwise unknown epithet Samnaios; a temple-inventory and a dedication by one of his priests were found on the same terrace with the land-leases, and it is likely that the land in question belonged to his temple. Whether the small temple on the acropolis was his there is no evidence to show.

Further down the coast, at a spot called Gerbekilise or Gerbekse, are the ruins of a small Byzantine trading-station with several small churches; from here a path leads up in an hour and a half to the village of Bayır. This is identified by an inscription with the town of Syrna, not a Rhodian deme but distinguished by its sanctuary of Asclepius. Tradition said that Podaleirius, son of Asclepius and physician to the Greek troops at Troy, married Syrna, daughter of a king of Caria, and was given the Chersonese (that is, the Loryma peninsula) as a gift;

in it he founded two cities and named one of them after his bride. In the floor of the porch of the mosque at Bayır is a large marble block inscribed with a list of contributions made about 200 B.C. to certain construction-work in the sanctuary.




FIG. 23 Loryma. Plan of the Castle

At the southern extremity of the peninsula is the sheltered bay of Bozuk, with a few houses on the shore. It was formerly known as Oplosika Bükü, 'Arsenal Bay', and the arsenal (*hoplotheke*) is recorded by Constantine Porphyrogenitus in the tenth century. Here was the town of Loryma; like Syrna, it was not a Rhodian deme but belonged to the deme of Casara a little to the north-east. A few ancient stones may be seen near the coastguard-station by the shore; but the chief feature of the site is the impressive and well-preserved fortification on the narrow headland overlooking the entrance to the bay (Pl. 33).

It forms an elongated enclosure some 350 yards in length by 30 in width, with a fine wall 8 feet thick, of fairly regular ashlar slightly bossed, undoubtedly of Rhodian construction; some of the blocks are as much as 17 feet long. There are nine (ruined) towers on the sides and a round tower at each end, that on the east now destroyed. Five small gates lead through the wall, four of them towards the east end. No sign of buildings is to be seen in the interior, the whole structure being purely military; there is, however, a partly rock-cut cistern near each round tower, and at C, C on the plan the wall is pierced by an outlet for water. Outside the gate in the south wall at the east end inscriptions on the rocks show that the place was sacred to Zeus Atabyrius, a deity peculiar to Rhodes.

The acropolis hill is just to the east of the landing-stage, and carries some remains of its fortification, partly in squared masonry, partly in polygonal. By the edge of the sea at the foot of this hill is a small cave with an inscription on its wall forbidding the removal of offerings from the sanctuary, so that the cave was evidently sacred. On a high hill two hours' climb to the north is another fortress comprising an inner and an outer enclosure; these also are well preserved.

The harbour of Loryma is exceptionally well protected in all weathers. It was used as a refuge for the Athenian ships during the Peloponnesian War, and in 395 B.C. the Athenian commander Conon used it as a rendezvous shortly before the battle of Cnidus. And again in 305 Demetrius, son of Antigonos, assembled his fleet there in preparation for his unsuccessful attack on Rhodes.

A remarkable feature of this region is the large number of three- and four-sided bases graded in three stages like stepped pyramids (Fig. 24). These seem to occur only in the southernmost part of the Loryma peninsula; they are generally supposed to be bases for offerings, but none of them carries any inscription which might help to determine their purpose.

Rounding the mountainous and often boisterous promontory of Kızılburun the traveller enters the pleasant and comparatively well-populated bay of Syme; the island itself is in full view a few miles to the west. In the eastern recess of the bay, above the village of Saranda, is the acropolis of the deme of

Thyssanus, with a polygonal wall; and at the northern end is the admirable harbour of Bozburun. Here was the deme of Tymnus, but very little remains of it beyond a considerable quantity of inscriptions. One of these refers to a cult of Zeus and Hera, and assigns a stoa to the priests for the disposal of the victims after sacrifice, with a prohibition upon the burning



FIG. 24 Loryma. Pyramidal Block

of wood in the stoa for any other purpose, and on nailing up any object to the roof or epistyle; penalty 100 drachmae.

To the north of the Bozburun peninsula is the bay of Selimiye, called in antiquity Sinus Schoenus (Reedy Bay). Selimiye itself corresponds to the ancient Hyda or Hyla. Further north again, at the head of the gulf, is the town and bay of Bybassus, an important Rhodian deme. Between the shore and the village of Hisarönü is the acropolis, a steep rocky hill bearing remnants of fortification. Hisarönü was formerly known as Erine or Rina, and was supposed to represent the Rhodian deme of Erine, known from inscriptions. The identity of name appeared convincing, but in fact Erine derives almost certainly from a church of St. Irene. The true identification of the site is due to the perspicacity of Professor J. M. Cook, and deserves to be set forth in some detail.

On the mountain of Eren Dağı above Hisarönü on the south, at a spot called Pazarlık, a temple-site has long been known. Spratt in 1886 suggested it might be a temple of Leto, but his reasons were far from strong; he relied on the mention by Strabo of a grove of Leto at or near Physcus, and on a female

statue that he saw on the site. Professor Cook reasoned otherwise. The historian Diodorus observes that there is at Castabus in the Chersonese a sanctuary of Hemithea, then tells the story of the sisters Molpadia and Parthenus, who were saved by Apollo and brought to the Chersonese;

and the one called Parthenus he caused to be honoured with a precinct in Bubastus of the Chersonese [Bybassus], while Molpadia came to Castabus and by reason of a divine epiphany received the name Hemithea [demi-goddess] and was honoured in all the Chersonese; and in course of time her sanctuary so increased in renown that not only was it greatly revered by the neighbours, but even from afar men visited it and graced it with splendid sacrifices and notable offerings. And in consequence the precinct, though unguarded and unprotected by any strong wall, is crowded with votive gifts.

An inscription found by the writer near the village of Gölenye shows that the sanctuary was in the hands of the men of Bybassus. The whereabouts of Castabus in the Chersonese was quite unknown, but Bybassus at least was certainly in the region about the head of the gulf; might not the ruins on Eren Dağı be those of the sanctuary of Hemithea? This would explain the curious name Pazarlık (market) applied to this remote and deserted spot high up in the hills, if the festival of Castabus was succeeded by a great annual fair. Professor Cook accordingly carried out an excavation on the spot, and was rewarded with two inscriptions naming Hemithea and proving his theory to the hilt. Pazarlık is Castabus, and it follows that Hisarönü is Bybassus.

The sanctuary stands on a ridge of the Eren Dağı some 900 feet above the plain by Hisarönü, from which it is about an hour's climb. The temple of Hemithea stood on a platform built to accommodate it; it was in the Ionic order, but with minor Doric features, and dates from the latter part of the fourth century B.C. It replaced an earlier shrine of which some remnants were found. The plan is simple, a deep pronaos and a cella, with no opisthodomus, and a colonnade of eleven columns on the long sides and six at the ends. A curious feature

is a round altar-like structure, decorated with reliefs, which stood in the pronaos directly in front of the door to the cella; its purpose and its date are alike uncertain. A further unusual feature is the ornamental screen-wall which ran round three sides of the platform, with small rectangular buildings at unequal intervals and of unequal size; the function of these is also unknown. On the whole platform, however, very little is now standing above the foundations. The supporting walls of the platform itself, on the other hand, are of handsome masonry in very fair condition. The only other identifiable building on the site is a theatre, very poorly preserved, a little way down the slope to the south. This is the third and last of the theatres hitherto discovered in the Peraea.

Hemithea was a healing deity, and the method of cure practised in her sanctuary was incubation. According to Diodorus the goddess in person stood over the sick and treated them in their sleep; she was especially helpful to women in childbirth, and had restored to health many desperate cases. We know of a festival called the Castabeia which was held periodically on the site, and it is probable that the incubation was practised mostly, if not exclusively, at those times. Nothing more is known of the character of the festival; it can hardly have included athletics, for there is no level ground for a stadium nearer than the plain below, but the theatre was available for dramatic and musical contests. It was certainly popular; the inscription found at Gölenye strikingly confirms Diodorus' account, recording that the crowds were so great that they could not be accommodated in the existing buildings, and revenue was being lost. This created a difficulty, since there was no land adjacent to the sanctuary suitable for an extension; unfortunately the inscription is so mutilated that we do not know what steps were taken to remedy the situation. This was in the second century B.C., and it appears from the excavation that the sanctuary at Pazarlık declined very soon after this time both in splendour and in importance, and from the Roman period there is very little evidence to suggest that it even continued to function. This decline would be partly explained if it was found necessary to remove the festival to more spacious ground elsewhere; but in fact it coincides in time with

a general decline in the fortunes of the Rhodians. The establishment of the sanctuary in the fourth century was the work of the Rhodian state as a whole, not only of the deme of Bybassus; in the Gölenye inscription the decree is issued by the people of Rhodes, the proposer is a Bybassian, the man honoured is from Amos, and, as we learn from another inscription, the temple was dedicated by a man of the deme of Hygassus. For two hundred years the sanctuary flourished, then sank into oblivion, until Professor Cook's inspiration brought its battered remains to light once more.

*Caunus*

ALTHOUGH THE SITE of Caunus has been known since 1842, when Hoskyn found there a decree of the Council and People and Elders of the Caunians, this fascinating city was until recently surprisingly neglected. From then until the last war only two scholars, in 1877 and 1920, gave it their attention. The present writer paid it repeated visits from 1946 to 1952, and in 1967 the Turks began an excavation which is still in progress at the time of writing.

Stratoniceus the harpist, who lived in the fourth century B.C., and whose quips were famous in antiquity, once paid a visit to Caunus; observing the greenish complexion of the malaria-ridden inhabitants, he remarked that he now understood what Homer meant when he said, 'As are the generations of leaves, so are the generations of men'. The Caunians protested that it was unkind of him to stigmatise their city as unhealthy. 'What!' said Stratoniceus, 'how could I dare to call a city unhealthy where even dead men walk the streets?'

In fact, Caunus was a notoriously unhealthy city. Strabo, in a disputed passage, remarks that while the territory is rich, the city is universally agreed to be unhealthy 'even in the autumn' owing to the heat and the abundance of fruit. This surprising statement has sometimes been explained by supposing that the Caunians were tempted to over-indulgence in fruit; others, noting the apparently meaningless 'even', have supposed a defect in the text. It is, however, a fact that fruit was regarded by the doctors as dangerous to health; Galen, the greatest physician of antiquity after Hippocrates himself, considered it liable to cause fever, and observes that his own father lived to the age of a hundred by abstaining from it. And this idea con-

tinued in vogue even down to the sixteenth century; it was indeed one cause for the prevalence of scurvy.¹

The role of the mosquito in producing fever was not, of course, understood in ancient times. Caunus is at present some two miles from the sea, but the intervening area is not firm land but rather an expanse of reeds holding together a little soil. There can be no doubt that all this area was in antiquity sea, but it is likely that a similar marshy region existed near the city and afforded a rich breeding-ground for mosquitoes. When the present writer first visited Dalyan in 1946-47, the room in which he slept was singing with mosquitoes, and the least flaw in the mosquito-net meant a sleepless night; in 1948 the Turks began a serious campaign to exterminate malaria, and that year not a single mosquito was in evidence. Such perfection has naturally not been maintained, and the insects have to some extent found their way back; but the visitor need no longer be deterred by this menace.

Among the fruits which may or may not have been thus fatal to the Caunians the fig held the chief place. Caunian figs were indeed famous. The story goes that in 55 B.C., when the Roman general Crassus was about to embark on a campaign against the Parthians, a vendor of figs happened to come by, calling his wares. His cry of *Cauneas* sounded to superstitious ears like *cave ne eas*; but Crassus disregarded the warning and proceeded on the journey which led him to defeat and death. Figs are not today a notable product at Dalyan; but in other respects the fertility noted by Strabo is as great as ever. Fruit and vegetables, and especially sesame, are abundant; maize is also much grown, but this was of course unknown to the ancients.

Strabo says that Caunus has dockyards and a closed harbour; above it on a height is a fort called Imbrus; the river Calbis, deep with a navigable channel, flows nearby. These features are still to a large extent identifiable. The harbour is now a small lake, known as Sülüklü Gölü, below the acropolis hill on the west; by 'closed' is meant, not a sheltered anchorage, but

¹ On this interesting belief see J. C. Drummond and Anne Wilbraham, *The Englishman's Food* (London, 1939), pp. 68-9.

one closed at the entrance with a chain. As was said above, the sea came in antiquity right up to the city, and must have completely surrounded the acropolis hill except for the ridge joining it to the higher ground to the north. Where the dockyards stood cannot now be determined; possibly in the bay below this ridge on the east, but this is quite uncertain. Imbrus may, in the writer's opinion, be confidently identified with a large fort on the summit of the mountain now called Ölemez Dağ, over 3,000 feet high, just to the north of the city. Before the existence of this fort became known in 1947 other identifications were put forward, either with the acropolis hill itself, or even with the mighty Sandras Dağı, twenty miles away to the north-east; but these are clearly less satisfactory.

The river Calbis must evidently correspond to the Dalyan Çayı, which affords the outlet from the lake of Köyceğiz to the sea. It has a good strong current and is said to be as much as 30 feet deep in places. There is, however, a considerable tide from the sea, and the direction of the current changes regularly twice a day; with a strong sea-wind the salt water sometimes reaches to the lake. The *dalyan*, or fishery, consisting of a barrage of posts and wire netting across the stream, stood formerly opposite the village of Dalyan; but this is now removed, and a more up-to-date installation has been erected lower down, under the acropolis hill. The fish are mostly *kefal* and *levrek* (the ancient *kephalos* and *labrax*, mullet and bass), both excellent eating; in their seasons these pass up from the sea to the lake to spawn, and on their return some two months later are caught in vast quantities. A fragmentary inscription containing certain regulations concerning catches of fish suggests that in ancient times also the Caunians had their *dalyan*.

The actual course of the river, however, was almost certainly different when Strabo wrote. Caunus stood on the coast, and the Calbis flowed 'near by'. Just how far up towards the lake the sea came is hardly possible to determine, but if the line of the river was the same as it is now, the city must have been actually at its mouth. More likely it flowed further to the east, and it is not improbable that its ancient course is marked by a sluggish and marshy stream called Sariöz which at present trickles southwards into a kind of lagoon by the name of

Solungur Gölü. If this is right, the navigable channel mentioned by Strabo led from the sea, at a point over a mile east of Caunus, to the lake of Köyceğiz. But the silting process has so transformed the region that it is no longer possible, short of a thorough geological examination, to be sure of the details.

The acropolis hill is in two parts, the eastern high and steep, the western much lower. The city-centre lay near the east and north shores of the harbour; here have been found the majority of the inscriptions. Except along the ridge north of the theatre the buildings themselves have become buried and overgrown, though the Turkish excavators have begun to bring them to light. But a much larger area than this was walled in. Over the hill to the north-east runs a fine wall, two miles long and quite well preserved; the east and south faces of this hill are precipitous and unfortified. On the vast expanse of hillside thus enclosed nothing whatever has been found, and the wall winds its way over the mountain in complete solitude.

In classical times Caunus was reckoned a Carian city; she is expressly so called in the fourth century by the geographer who passes under the name of Scylax, and no tradition existed that she was ever colonised by Greeks. As so often happened in the case of cities with non-Greek names, an 'eponymous' founder was invented by the name of Caunus, made to be the son of Miletus; and a cult of this fictitious hero-king was maintained in the city down to Roman times. He is said to have had a sister Byblis, who fell in love with him and when he left her hanged herself; from this sad story came the proverbial expression 'a Caunian love'. According to Herodotus, the Caunians themselves reckoned to have come from Crete, though the historian does not believe this, but judges them to be indigenous. He distinguishes them both from the Carians and from the Lycians, particularly in respect of their peculiar customs, and adds that their language had become assimilated to the Carian—or the Carian to it. This last statement is interestingly confirmed by an inscription found by the present writer among the ruins in the centre of the city; this is written in the Carian script, and is as yet undeciphered, but it contains a number of characters which are not found in any of the Carian inscriptions known on other sites. It is likely therefore that the Caunian

language was, as Herodotus says, similar to, but not identical with, the Carian.

In the sixth century B.C., following the capture of Sardis by the Persians and the reduction of the Greek cities of Ionia, the Persian general Harpagus came south with an army to Caria and Lycia. He met with resistance at several places, and Herodotus tells of the desperate defiance of the Xanthians in Lycia; overwhelmed by numbers, they collected their families and possessions on the acropolis and set the place on fire, then sallied forth and died fighting to the last man. The historian adds that Caunus was captured in similar fashion; 'for the Caunians imitated the Lycians for the most part'.

Some forty years later, when the Ionian cities organised their revolt against the Persian King, the Caunians, remembering this disaster, refrained at first from taking any part; encouraged, however, by the Ionians' success in taking and burning Sardis, they were persuaded to join in. The revolt soon collapsed (494 B.C.), but Persian control of the coast was shortly afterwards brought to an end following the failure of Xerxes' invasion of Greece; in the Delian Confederacy which replaced it Caunus was included and assessed for tribute at half a talent. This figure is surprisingly low—considerably less than was paid by several of the Lelegian townships of the Myndus peninsula—but in 425 B.C. it was raised at a blow to ten talents, equal to Miletus, and far in advance of Ephesus or Cnidus. How or why the Caunians should have become suddenly so much richer is not known; the present writer has suggested that they may about this time have developed a profitable business in salted fish; there were salt-pans at Caunus, and certainly no lack of fish, and dried and salted fish was a staple article of diet in the ancient world. Others have supposed a project for developing the resources of the plain around the head of the lake of Köyceğiz; but in any case it is likely enough that the assessment of 425 was unrealistic, and there is no evidence that the money was ever actually paid. Towards the end of the Peloponnesian War not only the Athenians, but also the Spartans were able to make use of the port of Caunus.

With the King's Peace in 387 B.C. Caunus reverted with the rest of the coast to Persian control, and it was due to the

Hellenising policy of the satrap Mausolus that the city first began to acquire a Greek character. Statue-bases of him and his father Hecatomnos have been found in the ruins, and it is virtually certain that Mausolus was responsible for the fortification of the city with the long wall. In Alexander's campaign of 334 B.C. no actual mention is made of Caunus, but it was presumably given by him to Ada together with the rest of Caria.

In the disturbed times that followed Alexander's death Caunus passed from one to another of his Successors. Taken in 313 by Antigonos, she was captured from him by Ptolemy four years later. Of this latter event the historian Diodorus records that the king sailed to Caunus and occupied the city; of the two acropoleis, which were defended by troops, he took the Herakleion by force and the Persikon was surrendered to him by its garrison. The reference is evidently to the two parts of the acropolis hill; after occupying the lower city Ptolemy no doubt attacked the higher eastern portion, and when this fell, the garrison of the minor western hill, the Persikon, might well feel their position untenable and submit of their own accord.

After the utter defeat of Ptolemy at Salamis in Cyprus in 306 B.C. Caunus came back into the possession of Antigonos and his son Demetrius, and was held by the latter until 286; on his surrender in the following year to Seleucus, king of Syria, she passed to the hands of Lysimachus. At an uncertain date not long afterwards she was recaptured for Ptolemy by his general Philocles by means of a trick. Encamping outside the city, Philocles is said to have bribed the Caunian corn-inspectors to announce that the soldiers' rations would be issued, not at their stations but in the city; the defenders accordingly left the walls unmanned while they drew their allowances, and Philocles was able to capture the city. The wall in question must be the long wall over the hill to the north; Philocles came by land and cannot have been attacking the sea-girt acropolis.

Caunus was still Ptolemaic in 197-96 B.C., when she is mentioned among the 'allies' of Ptolemy V whose 'freedom' was protected by the Rhodians against Antiochus III of Syria. A few years later she became a Rhodian possession. Polybius records that in 166 B.C. a Rhodian envoy to the Roman Senate

declared that his city had purchased Caunus for 200 talents¹ from the generals of Ptolemy. The date of this unusual transaction must have been about 190 B.C., but the Rhodians might have saved their money, for in 189, after the defeat of Antiochus at Magnesia, the Romans gave them the whole of Caria and Lycia.

Rhodian rule lasted from 189 to 167, and during this period Caunus was under the command of a *hagemon*, a military and administrative official of unusually high rank for a dependent city. But Rhodes' new subjects were far from content, and in 167 the Caunians joined in the general revolt against her. The revolt was a failure, but immediately afterwards the Romans rescinded their gift and required the Rhodians to evacuate Lycia and Caria, including specifically Caunus. The Rhodians pleaded strongly to be allowed to retain Caunus, pointing out that she was not acquired by the favour of Rome, but that they had spent good money on her, and mentioning incidentally that from Caunus and Stratoniceia combined they drew an annual revenue of 120 talents. Caunus at 200 talents was evidently a bargain. But their plea was overruled and Caunus became a free city.

When the province of Asia was established in 129 B.C. Caunus was included in it, forming a border city on the south; not until much later was she assigned to Lycia. In 88 B.C. the province was overrun by Mithridates, and Caunus chose to take the king's part; she is mentioned among the places where the slaughter of the Roman residents was carried out with especial ferocity. Accordingly, when peace was made in 85, the city was given back to the Rhodians. No more content with Rhodian rule than they had been before, the Caunians made an application some time about 65 B.C. to be allowed to pay tribute to Rome rather than to Rhodes. Whether this appeal was successful or not is not known, but by the end of the century we find Caunus once more a free city. Even this, however, was not the last of her vicissitudes; the sophist Dio Chrysostom, writing soon after A.D. 70, describes the Caunians as undergoing a double servitude to Rome and Rhodes, from which it

¹ Perhaps something like a quarter of a million sterling; but such equations of ancient money with modern are hardly realistic.

appears that the Rhodians had yet again obtained control of the city.

These changes of fortune that Caunus underwent are no doubt exceptionally numerous, but they give a good idea of the unsettled state of the world in Hellenistic times. Throughout this period Caunus was a fully Hellenised city, anxious to forget her Carian origin. Her institutions are thoroughly Hellenic, and the names of her citizens are exclusively Greek. Not a single Caunian is yet known to have borne a Carian name. At the same time it is likely that she was not really popular. Dio Chrysostom in particular is almost vitriolic in his condemnation: 'These stupid Caunians', he says,

when did they ever produce a worthwhile citizen? Who ever did them a good turn? Their misfortunes are due to their extreme folly and rascality, and if they are all but wiped out by fever it is no more than they deserve.

He may no doubt have been prejudiced, but it is noticeable that even in earlier times in the inscriptions citizens of other cities are conspicuously few. A reputation for unhealthiness is of course no recommendation, and it is understandable that foreigners should be reluctant to take up residence; it is probable that this disability was never really overcome.

Caunus suffered also from another trouble, which she shared with Ephesus, Miletus and other places. The silting process which has now separated the city by two miles from the sea must have been an ever-present menace to her commerce. On a building by the shore of the harbour, in the first century A.D., was written a long inscription relating to the payment of customs dues. Unusually, it is concerned almost exclusively with remissions of tax. It appears that certain public-spirited citizens had presented a sum of 60,000 denarii for this purpose, so that foreign merchants might be encouraged to use the port and the city treasury should not suffer. Although no special motive need be sought for so useful a benefaction, it is likely enough that by this date the silting may have begun to be troublesome; the harbour was beginning to be difficult of access, and merchant-captains were showing signs of avoiding it.

This same inscription gives us some information about the principal articles of commerce at Caunus. They are in fact such as we should have expected, notably slaves and salt. The importance of these is shown by the fact that, whereas in all other cases tax is remitted, the export of slaves and import of salt continue to be dutiable. Caunian salt was known to Pliny as being especially recommended for addition to eye-salves and plasters; and Caunian slaves, male and female, were familiar in antiquity. Mention is also made of resin and pitch—that is, a form of burnt resin, not mineral pitch; these would be imported by land from the pine-forests which are still so notable a feature of the Carian landscape, and would be essential for the shipbuilding and repair work in the Caunian dockyards. If the trade in salted fish be added, we have a picture of considerable commercial prosperity in the Roman period.

The ruins at Dalyan are now most easily reached by land; a road turns off the main Köyceğiz-Fethiye highway a little south of Adaköy. This road is quite respectable, and there is even a petrol-station in Dalyan village. Alternatively, a boat may be hired at Köyceğiz; if time is no object, this is highly recommendable, for the lake scenery is superb. The approach by the river from the sea may be difficult for anything more than a rowing- or motor-boat, owing to a sand-bar at the mouth.¹ To reach the site from the village the river has to be crossed. It is not normally possible to do this at the new fishery, and the crossing is made by a ferry from the village; the ferryman will usually act also as guide to the ruins, which lie about a mile beyond.

Even before crossing the river the visitor's eye is caught by the very fine series of tombs cut in the cliff on the far side. These are undoubtedly the most striking feature of the site. They are disposed in two uneven rows, an upper row of columned temple-tombs and a lower row of simple chambers with square doors (Pl. 38). Some of the upper row are quite easily reached, others are inaccessible without tackle. The temple-tombs, and a few of the others, have a passage cut all


¹ As Freya Stark found (*The Lycian Shore* (London, 1956), p. 107); but it seems that the bar is variable.

round them in the rock. The term 'temple-tomb' refers only to the form of the façade, and does not imply that any kind of worship was carried out there; the interior bears no resemblance to a temple, but consists of a comparatively small chamber having usually three stone benches for the disposal of the dead. From the pottery found in them these tombs appear to date to the fourth century B.C. Only three or four of them carry inscriptions; of these one contains two words of Carian, while the others are not original, but relate to a reuse of the tombs in Roman times. Curiously, two of the inscriptions on neighbouring tombs are identically worded, claiming the tomb for the same three persons. The façades, which are entirely rock-cut, consist generally of two Ionic columns between antae, surmounted by a dentil frieze and a pediment with acroteria at the three corners. In many cases the columns have wholly or partly broken away. The pediment is normally undecorated, but in one case shows a pair of lions face to face.

The largest tomb of all, however, in the group nearest to the village, has four columns—or rather, it was intended to have four columns, but the work is unfinished. It shows in an interesting way how the tombs were made: the roof, the pediment and the frieze are practically complete; the capitals and the tops of the column-shafts have been merely blocked out square; below this nothing has been done beyond smoothing the rock-face.

At the western end of the series is a group of tombs of the type called Carian; the grave-pit is sunk into the solid rock and covered with a separate lid. In the rock-wall below this group is a cluster of niches for votive offerings to the dead.

The acropolis hill is an impressive crag, conspicuous from afar, perhaps 500 feet in height; it is steep on all sides and quite precipitous on the south. The wall and towers on its north slope are mediaeval, but on the summit is a fort of good ashlar masonry some 130 feet in length and half as wide, now in a very ruined state; this is apparently the Herakleion captured by Ptolemy in 309 B.C. The wall which runs up the western extension of the acropolis is also of classical Greek date; its thickness varies surprisingly from 10 feet to five. Of the Persikon nothing appears to remain.



- | | |
|--|---------------------------------------|
| A - Acropolis Hill | G, G - Rock-cut Tombs |
| B - Western Extension
of Acropolis Hill | H, J, K - Long Wall |
| C - Ancient Harbour | L - New Fishery |
| D - Theatre | M - Old Fishery |
| E - Area of new excavation | N, N - Dalyan Çayı,
ancient Calbis |
| F - 'Carian' Tombs | |

FIG. 25 Plan of Caunus

The long wall runs uninterruptedly from the north side of the harbour to a precipice high above the river beyond the village of Dalyan; it is reminiscent in some ways of the land-wall at Iasus. Its masonry varies remarkably, and the wall has evidently been repaired more than once. The upper part from J to K is the oldest, and the original parts date in all probability to the time of Mausolus; between H and J the style is a very handsome ashlar of Hellenistic date (Pl. 41). Below this the masonry is polygonal, the blocks prominently bossed and

occasionally drafted at the edges; polygonal masonry of this type dates generally to the post-classical period. As was said above, this long wall encloses for the most part nothing but bare hillside; it would have been possible to defend the city adequately with a much shorter wall much more easily manned. But Mausolus' ideas were always on a generous scale, and it may be that he intended Caunus to be a much larger city than in fact she ever became. We have seen that Myndus and Theangela were in similar case.

Near the foot of the acropolis hill is the theatre, the most attractive of the buildings which are still standing. It faces west, the northern half supported by walls of masonry, the southern half cut out of the hillside. It is of average size, with a single diazoma and thirty-four rows of seats, eighteen below the diazoma, sixteen above it. The theatre is of predominantly Greek type, the cavea being considerably more than a semicircle; the two arched entrances on the north side seem to be original. Corresponding entrances on the south side were of course not possible. The number of stairways, originally ten, is not doubled above the diazoma in the usual way. The lower part of the stage-building still exists and would repay excavation; at present it is buried and overgrown. It is separated from the cavea in the Greek fashion by *parodoi*, of which the northern is partially obstructed by a curious semicircular projection from the *analemma* whose purpose is not obvious. A part of the northern retaining wall has collapsed within the last few years, and a large carob-tree growing through the northern *analemma* must before long throw that down also.

On the ridge to the north of the theatre is a row of three buildings. The first is a church of basilica type, with apse and three aisles; it is of excellent squared masonry with elegant decoration. North of this is a large and massive baths, and to the north again a smaller building which has been thought to be a temple, but this is certainly a mistake. Neither the two doors in adjoining sides nor the arrangement of the interior walls conforms to the plan of a temple, and a library might be a more plausible suggestion. The northern door is flanked by engaged fluted columns, with a square buttress beyond on either side. The platform on which this building stands is

supported on the west by a line of column-stumps, some upright, some horizontal. All these three buildings are of comparatively late date; they would (and no doubt will) benefit from excavation.

In fact the excavations have already added a good deal to the amenities of Caunus. When the present writer in 1946 discovered the long customs-inscription referred to above, he supposed that the ruined building on which it was carved was likely to be the customs-house. In reality it has turned out to be a fountain-house, and has been completely restored by the excavators from its own blocks. The inscription stands on the outer side of the west face. In front is lying a dedication to Vespasian, but whether this is the actual dedication of the building appears doubtful.

Not far from this a stoa has been cleared, but the masonry is rather poor and many of its stones are reused. In it is a large moulded block carrying an inscription in which the People of Caunus honour the People of Rome for benefits received.

Between the ridge and the harbour the excavators in 1969 unearthed an interesting and in some respects mysterious building. Two concentric rings form about three-quarters of a circle; the inner ring consists of a thin wall of poor masonry about 15 inches high, with plastered face and unfluted columns at intervals; the outer ring is a narrow stylobate of white marble with slender flat-fluted columns spaced along it; these columns have small slots as if for fixing some kind of grille. At the back is a semicircular podium raised on three steps, with a row of unfluted columns behind it, rather irregularly spaced. Lying in the middle is a round flat-topped slab of purple stone, now broken in two. The purpose of this unusual building is not immediately apparent. The excavators have suggested that the inner ring contained a shallow bathing-pool surrounded by a colonnade. The plaster on the inner face supports this idea, and the bathers might step down from the podium into the water; indeed, the grille in the outer ring would presumably allow the pool to be entered only from this side. But the object of the round flat-topped stone (unless it was merely for sitting on) remains obscure, and an outdoor bathing-pool such as this is in the writer's experience most exceptional (Pl. 42).

Beside this building a deep pit has produced sherds going back to the ninth century B.C., and gives some hope that the excavations may throw new light on the early history of the site.

The inscriptions of Caunus mention a number of smaller places in the neighbourhood of the city, one of which, Pasanda, has lately been located with good probability. In the fifth century Pasanda paid in the Delian Confederacy a tribute equal to that of Caunus (down to 425 B.C.), but later sank to the status of a deme. An ancient authority places it thirty stades (between three and four miles) to the south of Caunus, and in this position, above the south end of Solungur Lake, a small town-site has recently been discovered. It has a wall, but nothing else is standing. In at least eight places a socket has been sunk into the rock to receive a stele, and one of the stelae has been found; it contains a list of names, and dates apparently to the second century B.C.



Alabanda

THE RIVER MARSYAS, now the Çine Çayı, which for much of its course runs in a deep gorge, towards its northern end, before joining the Maeander, traverses a broad and fertile plain. This is now controlled by the *kaza* of Çine; in antiquity it was the territory of Alabanda. Until the present century the town of Çine stood some five or six miles further to the south, where is now the village of Old Çine; the present Çine was then called Kiroba. For those who are not too particular about the quality of their hotels, Çine makes a convenient centre for visiting Alabanda, Alinda and several subsidiary sites.

Alabanda, the third of Strabo's three noteworthy cities of the interior, was a place of some importance throughout antiquity. Its foundation-legend is told by Stephanus of Byzantium;¹ in Carian, he says, *ala* means 'horse' and *banda* means 'victory'; the mythical king Kar, having won a cavalry victory, gave the name Alabandus to his son, and named the city after him. Cicero, in his book on the Nature of the Gods, mentions the god Alabandus, from which it appears that a cult of this 'eponymous' personage was maintained in the city down to Roman times; and his image has been, somewhat dubiously, recognised on certain coins of Alabanda.

The earliest historical mention of the city is in connexion with an incident during Xerxes' invasion of Greece in 480 B.C. The Greek and Persian fleets were anchored not far apart at the north end of Euboea; a Persian squadron of fifteen ships, which had lagged behind, came up, and mistaking the Greek fleet for their own, sailed right into the enemy's hands. On board one of these ships was Aridolis, tyrant of Alabanda, who was thus taken prisoner. Herodotus does not say that he was

¹ See below, p. 191, note 1.

captain of the ship, and it would be surprising if a city so far inland as Alabanda had any connexion with the sea. We should have expected Aridolis to serve in Xerxes' army rather than his navy.

In this passage Herodotus describes Alabanda as in Caria; in the following year 479, however, he tells us that 'Alabanda, a large city of Phrygia' had been given by the Persian King to a certain Amyntas. Stephanus, on the other hand, records a second city of Alabanda in Caria. What are we to make of this? No other hint of a second Alabanda, either in Caria or in Phrygia, is to be found, and it is obviously unlikely that a large city in Phrygia should completely disappear without any record. There can be little doubt that Herodotus is speaking inaccurately, and that in fact Amyntas succeeded to the tyranny left vacant by the loss of Aridolis in the previous year. What lies behind Stephanus' assertion is uncertain, but we may safely accept that there was never more than one city of Alabanda.

No mention is made of Alabanda in connexion with the passage of Alexander, and the city is next heard of at the end of the third century. At this time she bore the name of Antiocheia of the Chrysaorians, taken in honour of Antiochus III, king of Syria. A decree of the Amphictyonic Council at Delphi, dated to the last years of the century, records that an ambassador from Antiocheia, guided by an oracle, came to Delphi praising Antiochus for preserving 'the democracy and the peace' of the city, and requesting that the Council, in accordance evidently with the king's wish, should recognise the inviolability of the city's territory. The Council therefore decided that the city and territory should be regarded as inviolable and sacred to Zeus Chrysaoreus and Apollo Isotimus, and voted to erect in the sanctuary of Apollo at Delphi eight-cubit statues representing the city and the king. The city is described in the preamble as 'Antiocheia of the nation of Chrysaorians, kindred of the Greeks'. This is not intended to imply any genuine ethnological relationship, but is merely a recognition of the Hellenisation of a Carian community. Alabanda had in fact recently been colonised by the Seleucid kings, and her population was predominantly Greek.

Of the two deities here mentioned, Zeus Chrysaoreus is

already familiar,¹ but Apollo Isotimus is peculiar to Alabanda. Isotimus means 'equal in honour'; since Apollo was the special god of the Seleucids, it has been suggested that he was adopted at Alabanda as a compliment to them, and at once raised to an equality with the native Zeus. At the same time it is possible that he was originally an indigenous deity later identified with the Greek god.

A decree of inviolability, generally recognised among the Greeks, was a great thing for a city, as it should preserve her from pillage during the unsettled Hellenistic age. But it did not save Alabanda; hardly a year had passed before Philip V, king of Macedonia, in the course of overrunning Caria,² sacked her territory as that of an enemy. In defence of this sacrilegious act he said, simply and frankly, that it was essential that his soldiers should have something to eat.

The battle of Magnesia in 190 B.C. put an end to Seleucid power in Caria, and Antiocheia became again Alabanda. In the settlement of Apamea after the battle, when Lycia and Caria south of the Maeander were given to Rhodes, Alabanda would naturally be included. But Rhodian control can hardly have been more than nominal, and in fact the only indication of it is the existence, under the early Roman Empire, of a priest of Helios in the city; for Helios was almost exclusively a Rhodian deity. On the other hand, in 167 B.C., when Mylasa, which was excluded from the settlement, became embroiled with Rhodes, Alabanda went to her aid, acting virtually as a free city. And indeed, as we learn from Livy, in 170 B.C. envoys from Alabanda had come to Rome bringing a present of three hundred shields and a golden crown weighing fifty pounds to be dedicated to Jupiter, and reminding the Senate that they had already built a temple of the City of Rome and instituted games in her honour. What they asked in return Livy does not say, but an inscription of about this period tells us that Alabandian envoys had asked for an alliance with Rome. The Senate's response was on both occasions favourable. Whether the two embassies are the same or not, these are the actions of a free city, and we may with some confidence accept that Alabanda was never actually subject to Rhodes.

¹ See above, pp. 26, 89.

² See above, pp. 25-6.

The earliest coins of Alabanda seem to have been struck just before the city's name was changed; these were followed by a handsome issue in silver with the name of Antiocheia. Under the nominal rule of Rhodes the coinage appears to have ceased, but was recommenced after the grant of freedom in 167; this latter series bears dates ranging from 1 to 33, and lasted evidently till the Roman inheritance in 133 B.C. and the formation of the province of Asia. The commonest type on the early coins is the winged horse Pegasus; whether this, the victorious horse, may echo the supposed etymology of the city's name it would be rash to say, but there is no denying the excellence of her territory for the use of cavalry. After the establishment of the province no more coins were apparently struck until the early Empire.

How Alabanda fared during the invasion of Mithridates is not recorded; but the generally unsatisfactory government of the province under the Roman Republic affected her like the rest; in 51 B.C. she is named by Cicero as one of five cities in debt to the Roman banker Cluvius. The situation was not improved when eleven years later the renegade Labienus arrived with his Parthian allies.¹ Like Mylasa, Alabanda accepted a garrison from him, but later rebelled and slaughtered the occupying soldiers. For this she was punished by Labienus by the exaction of a heavy fine and the spoliation of her sanctuaries.

Better times came, here as elsewhere, with the establishment of the Empire. Alabanda's relations with Rome seem to have been universally good; we hear of cults in the city of Caesar, of Rome and Augustus, and of the Health and Safety of the Emperor—this last a curious and unique phenomenon. Alabanda had the rank of a *conventus*, which meant that the provincial governor held regular assizes in the city. Coinage under the Empire is abundant, and a general air of prosperity is revealed by the citizens' reputation for luxury and debauchery; Strabo notes the great number of female harpists, indispensable accompaniment to a rich banquet. Coins of the third century record the privilege of *ateleia*, or immunity from taxation. Two other privileges, however, are rather surprisingly absent. In

¹ See above, p. 28.


A.D. 22 Tiberius held an investigation into the various cities' claims to inviolability; whether Alabanda made a claim for her temples of Zeus and Apollo, relying on the decree of the Amphictyonic Council two hundred years earlier, we do not hear, but these were not in the list of those accepted, and the title of 'inviolable' does not appear on the city's coins. And despite the number of temples devoted to the Imperial cult, the title of *neocorus*, Temple-Warden, is equally lacking. The coinage continues down to the middle of the third century, and later we find Alabanda a bishopric under the metropolitan of Aphrodisias.

Several special products are mentioned. We hear of Alabandian hemp, considered especially good for making hunting-nets, and of a special kind of gem, like a garnet, but darker in colour and rough. There was also in the hills around the city a peculiar very dark marble, almost purple, which was soluble in heat and used in the manufacture of glass. Alabandian roses and crystal, on the other hand, though worthy of mention, were less highly esteemed and comparatively cheap.

One other little piece of information is recorded. The Alabandians were addicted to a particular misuse of negatives in speaking Greek; though known as the 'Alabandian solecism', this fault is in fact one which became increasingly common in post-classical Greek in all parts of the world.

Strabo says that the city of Alabanda lies under two adjacent hills in such a way as to present the appearance of a pack-ass loaded with its panniers—to which a certain Apollonius added 'panniers of scorpions, for these creatures are abundant both here and at Mylasa and in the country between.' It was in fact in the neighbourhood of Araphisar that the present writer first saw a scorpion in the flesh; but the resemblance to a loaded donkey has never been apparent to him.

The city walls follow the ridge of these hills, and enclosed originally a considerable area of the flat ground at their northern foot; of this space the present village of Araphisar occupies only a small corner. The greater part of the city being on level ground, its ruins have been and are exposed both to plundering of the stones and to inundation from the small stream which flows down in winter and loses itself in the plain. The ancient



- | | |
|----------------------|-----------------|
| A - Theatre | E - Agora ? |
| B - Council-House | F - Baths |
| C - Doric Temple | G - Aqueduct |
| D - Temple of Apollo | H,H - City Wall |

FIG. 26 Plan of Alabanda

foundations are in consequence some 10 or 12 feet under the present surface.

The ring-wall, with numerous towers, survives on the high ground and is quite well preserved in places, but on the plain it is mostly destroyed. It is built in the classical style, with two facings of slightly bossed ashlar masonry with a rubble filling between. Some six or seven gates are recognisable, but only by gaps in the wall.

The theatre is large but poorly preserved, only the ends of the retaining wall surviving. These are of fine bossed masonry (Pl. 43, Fig. 27), and contain each a vaulted passage for the

entrance and exit of spectators, now blocked up. They led no doubt, as usual, to the diazoma, but of this, and of the rows of seats, nothing whatever remains, and the stage-building also has totally disappeared. From the size of the cavea it is likely that there was a second diazoma higher up. The cavea, facing north-west, is more than a semicircle, implying that the



FIG. 27 Alabanda. Theatre

original building dates to pre-Roman times. The façade is over 270 feet in length. The excavations carried out at Alabanda by Etem Bey in 1905-06 left the theatre untouched.

Much better preserved, and the most conspicuous building on the site, is the rectangular structure, B on the plan, identified with much probability as a council-house (Pl. 44, Fig. 28). Like the theatre it is unexcavated. The walls are of handsome brown stone, with two broader courses alternating with one narrower. In the front (south) wall, which still stands over 30 feet high in part, are four doors now almost entirely buried; above them is a strongly projecting cornice, and above this again a row of windows of which only the east end remains. The blocks of this wall carry numerous masons' marks in the form of one or two Greek letters (sometimes upside down); these would be expected to indicate the positions in which the blocks were to be laid, but in fact they display no intelligible order. The interior is badly ruined, but was evidently occupied by seats; the ground rises towards the back, and the shallow curve

of the rows of seating can be distinguished. In each side wall is an entrance to a staircase leading up to the back rows; that on the east is nearly buried. A conspicuous and remarkable feature of the building is the horizontal row of square holes let into all four walls and especially noticeable on the south front.




FIG. 28 Alabanda. Council-House

Though quite carefully cut, these are clearly not a part of the original design, and their purpose has never, to the writer's knowledge, been explained. In the north wall, in addition to a few of these square holes, is a row of larger holes beneath each of which a cornice-block is let into the wall, projecting only a few inches; these are equally clearly original, and served for some kind of decoration whose nature is uncertain.

Just outside the city on the south the stream, called Kemerderesi, is spanned by the arch of an aqueduct (Pl. 45). This is, as usual, of Roman type, but the upper part with the actual water-channel is destroyed, and the arch is now higher than the adjoining wall. It is said locally that this arch and the bridge over the Marsyas at İncekemer on the Muğla road some twelve miles to the south-west belong to one and the same aqueduct; it is in fact true that the arches of the bridge, though much larger, are of similar construction to that at Alabanda.

The temple marked C on the plan was brought to light by

the excavations in 1905. It stands on an artificial terrace in the hillside, but little more than the foundations survives. It was of the Doric order, with eleven unfluted columns on the long sides and six at the ends; when first excavated, one stump of all these columns was found in place, but most of these have been removed or overthrown. The columns stand on square slabs which could easily be mistaken for bases; in fact they belong to the stylobate, which is not preserved. The temple comprises a pronaos, unusually deep, and a cella, but no opisthodomos; the front is, contrary to normal practice, on the west. For the identity of the deity to whom the temple belonged the evidence is scanty in the extreme. The excavators found in it fifty-six coins, all of the same early type with the head of Apollo, but this is obviously far from cogent; they also found on the terrace a figurine representing Artemis-Hecate, and the building is now generally called Temple of Artemis. For the entrance on the west the temple of Artemis at Magnesia would afford a parallel; but this identification too must be considered uncertain. As appears from the coins, the temple can hardly have been built much before 200 B.C., but for a more precise date evidence is lacking.

At F on the plan is a large building which seems to have been a baths. It has not been excavated, and the ruins lie in a jumbled heap distinguished by a conspicuous shallow arch. The plan, which appears unusual, has not been completely determined.

Between this and the council-house, at E, is an open level space about 360 by 240 feet, originally surrounded by a colonnaded stoa with an entrance at the south-west corner. The excavators were at first inclined to recognise a gymnasium, but most scholars now prefer to place the agora here. At present nothing but the open space is to be seen.

By far the most notable building in the ancient city was the temple of Apollo Isotimus. This was formerly supposed to have been built by the distinguished architect Hermogenes, himself an Alabandian, who was active in the early second century B.C.¹ The evidence for this is a passage in Vitruvius concerning the 'pseudodipteral' style; 'there is', he says, 'no example of

¹ This is stated, for example, in Hachette's *World Guide*.

this at Rome, but at Magnesia there is the temple of Diana by Hermogenes of Alabanda, and of Apollo by Menesthes.' It is now believed, however, that this text is faulty, and that Vitruvius really said (or meant to say) 'and at Alabanda of Apollo by Menesthes'. In any case, Vitruvius does not say that the temple of Apollo was by Hermogenes; and other evidence suggests that Hermogenes was a citizen of Priene. No other work by Menesthes appears to be known.

The temple had in the course of time become completely buried; the foundations, and numerous architectural members, were discovered in 1905 at a depth of 14 feet below the surface. It was orientated NE-SW, with the entrance on the north-east, and was, as stated, pseudodipteral—that is, the surrounding colonnade was set at twice the usual distance from the cella walls. The order was Ionic, with white marble columns 33 inches in diameter, thirteen on the sides and eight at front and back. Several blocks of the frieze were found, depicting a battle between Greeks and Amazons. As an inscription shows, the temple was dedicated in Roman times to Apollo Isotimus and the Divine Emperors. The ruins have suffered severely since the excavation. Pl. 46 shows what was visible when the writer first saw them in 1939; today there is hardly one stone upon another. The plan is just discernible at the west end, and a few marble blocks are lying around.

Outside the city on the west is an extensive necropolis; hundreds of sarcophagi line the street leading to the town. They are all of the same type, a rectangular coffer with a plain granite block for lid. The inscriptions on them, mostly very worn, have the peculiarity that they commonly name the trade or profession of the deceased—banker, architect, schoolmaster, doctor, fuller, dyer, gardener, tanner, and more interestingly a dealer in pheasants and (apparently) a lamplighter.



Alinda and Amyzon

AS COMPARED WITH Alabanda, her neighbour Alinda is historically obscure; but the ruins at Karpuzlu (formerly Demircideresi) are much superior—indeed they are among the finest in Caria. Surprisingly enough they have never been excavated. The site was visited by Chandler in 1765, but his brief and unenthusiastic account gave no idea of the excellent preservation of the buildings. He took the city to be Alabanda; the true identification was made later on the strength of the coins found there by Sir Charles Fellows and others. This still remains the chief ground for placing Alinda at Karpuzlu, for no inscription has ever been found to confirm it; the identification is nevertheless quite certain.

Save that she was a purely Carian foundation, nothing whatever is known of the origins of Alinda. The city's first, and virtually her only, appearance in history was in connexion with Queen Ada, sister of Mausolus.¹ Dethroned and expelled by her brother Pixodarus about 340 B.C., Ada withdrew to Alinda, where she continued to maintain herself in semi-royal state, ready to take any opportunity of regaining her throne. She had not, as it turned out, very long to wait. When Alexander the Great advanced into Caria in 334 B.C. Ada went to meet him, offering to surrender Alinda and to help him against the usurpers, pointing out that they were her own kinsmen. She proposed also, with a truly regal self-confidence, to adopt him as her son. In return she asked that he would restore her to her lost throne. Alexander's response was characteristically gracious; he declined to take Alinda from her, and did not disdain to be called her son; and later, when Halicarnassus was taken all but the two headlands, he left to her the task of cap-

¹ See above, p. 24.

turing these, and when this was done he appointed her queen of the whole of Caria.

Ada's dealings with Alexander may have had another consequence for Alinda. The grammarian Stephanus of Byzantium in his *Ethnica*¹ records, among eighteen cities of the name of Alexandria, one in Caria called Alexandria-by-Latmus; it possessed, he says, a sanctuary of Adonis containing an Aphrodite by Praxiteles. This Alexandria is not otherwise mentioned, and the name is evidently one of the many dynastic names which were taken temporarily in the Hellenistic age by cities of non-Greek origin; we have already seen the case of Alabanda. Some have supposed the city in question to be Heracleia-under-Latmus; others, with greater probability, have identified it with Alinda. Nothing is more likely than that the city should be renamed after the conqueror who had had such friendly relations with the queen. Of the cities which could be called 'by Latmus' Alinda is surely the most probable.

It is possible that we get a further glimpse of Alinda in Hellenistic history. In an inscription found at Karpuzlu two subordinates of the dynast Olympichus² are honoured for their services. Possibly then Olympichus had his headquarters in or near Alinda. But this conclusion is far from certain; we cannot really infer more than that the two men in question were in all probability citizens of Alinda. It has even been suspected that the inscription does not belong to Alinda at all, but has been brought to Karpuzlu from elsewhere.

However this may be, there is no doubt that in the period following Alexander's campaign Alinda was rapidly Hellenised. The inscription just mentioned refers to a tribe (that is, a subdivision of the citizen-body) called Erechtheis; this name is taken direct from Athens, which also had a tribe Erechtheis, named after the mythical king Erechtheus. If the inscription

¹ This curious work is a kind of geographical lexicon. Its professed purpose is to study the principles of formation of adjectives from place-names; it takes the form of a list of city-names with the 'ethnics' belonging to them, with occasional notes on the places. Though not written before the fifth century A.D. the work is derived from much earlier sources, and while almost useless for the purpose for which it was written, it gives us quite a lot of incidental information not available elsewhere.

² See above, p. 25.

really belongs to Alinda, this is a striking and significant fact; and if Alinda also possessed in the third century a statue by Praxiteles, it is evident that the city quickly lost its purely Carian character. It is true that neither of these things is proved; but the extant remains are sufficient proof in themselves. Both the theatre and the superb market-building were erected in the Hellenistic period; and a silver coinage begins about 200 B.C., with Heracles as its commonest type. The city wall may be earlier, perhaps due to Mausolus, for Arrian describes Alinda as 'a place among the strongest', implying surely that she was fortified when Alexander arrived. At the same time Alinda, like all towns of Carian origin, was a member of the Chrysaoric League.

In the province of Asia and under the Roman Empire nothing whatever is heard of Alinda. The city continued to coin down to the third century A.D., and is later recorded as a bishopric under the metropolitan of Staurupolis (Aphrodisias).

No visitor to Alinda is likely to come away dissatisfied. The site is a fine one, fully justifying Arrian's description; the hill, some 500 or 600 feet in height, is steep on all sides except the south-west, where it is joined by a saddle to a somewhat higher hill, which, however, also formed part of the city. The ring-wall, of good ashlar masonry, is quite well preserved for much of its course; it encloses the summit and south-east slope of the hill, but the north slope was excluded.

Climbing from the modern town the visitor comes first to the market-building, which is undoubtedly the gem of the site (Pl. 47). Similar buildings are found elsewhere, for example at Assos in the Troad, Aegae in Aeolis and Seleuceia in Pamphylia, but none is so admirably preserved as this. It stands to its full length of 325 feet and to most of its original height of over 50 feet. Of its three storeys the topmost was on a level with, and accessible from, the agora which adjoins it on the north; the bottom storey opens onto a narrow terrace on the south. This terrace is partly cut from the rock of the hillside, partly supported by masonry set between the rocks and strengthened with buttresses. The bottom storey is divided lengthwise from end to end by a continuous wall, and crosswise by walls from

front to back forming a series of pairs of chambers one behind the other. The front row of chambers, evidently shops, is entered by twelve doors in the front wall, two arched and ten rectangular, and from them other doors give access to the back row. The front chambers are not all of the same size, nor has




FIG. 29 Plan of Alinda

each its own front door; some of the doors lead to two or more adjoining chambers. The back row is almost entirely filled with rubbish. Owing to the ground rising towards the east, the last four doors at that end are set higher than the rest; since all four are at the same height, there must originally have been two levels. There is also an arched door in the short wall at this end. Light came to the front row of chambers principally through the front doors, though there are also V-slit windows; the back row had only such light as came through from the front, and must have been nearly dark. In some, but not all, cases there are sockets in the door-jambs for barring the door.

The middle storey, lower in height than the bottom storey, is divided longitudinally down the middle by a row of double

half-columns—that is, square pillars with a half-column on each side. These stand on the long middle wall of the lower storey, but not—except by accident—at the points where the short walls cross it; they are spaced consistently 15 feet apart, whereas the rooms below vary in size. Lighting came from small windows in the form of slits in the front wall; these are sloped away on the inside so as to spread the light. There is also a large window in the short end-wall on the west. No indication appears of any division into rooms on this storey; wooden partitions would no doubt be possible, but the large window just mentioned, unnecessarily large for a single room, looks as if it were intended to light the whole gallery. How this middle storey was reached, whether from above or below, is not clear, and its purpose is equally uncertain; possibly it served as a kind of warehouse or storeroom for the shops below (Pl. 50).

Of the top storey, which bordered the south side of the agora, comparatively little remains. Like the middle storey, it was divided lengthwise by a row of columns; some stumps of these are still in place, set directly above the double half-columns of the middle storey. These columns are unfluted and have merely a narrow rounded moulding at the base. It is likely that there was another row of columns on the north, fronting the agora, but nothing of this survives. Of the walls on the other three sides only a part of that on the west is preserved. The corner pillar stands 10 feet high; adjoining it is a row of five moulded blocks like bases, divided by plain blocks, forming a wall quite unlike either of the lower storeys. There were no doubt windows in this wall, and also apparently in the south wall, for the bottom block of the corner pillar is moulded on its east side. For the rest the arrangement of this storey is quite uncertain; its floor, and that of the middle storey, were evidently of wood.

The agora is a level area running the whole length of the market-building and something over 100 feet wide, bordered at the back by a retaining wall erected against the gentle slope of the hillside. It was surrounded in the usual way by a stoa, of which a few stumps of columns are, or were, visible. No bases have been found to suggest that the agora was adorned with

statues; indeed, no statue-base, let alone a statue, has ever been seen on any part of the site.

The theatre is almost as well preserved as the market-building, and no less interesting. It is of average size, with about thirty-five rows of seats, largely preserved but a good deal displaced by the vegetation which has grown up through them. There is a single diazoma, of which part of the back wall survives; and the ambulatorium, or open gallery, at the top is also preserved for most of the way round. The cavea faces south-west, contrary to the rule laid down by the Roman architect Vitruvius—a rule which is as often disregarded as observed. The retaining wall of the cavea, and the analemmata, still stand to most of their height; the masonry is a regular ashlar of the Hellenistic period. Two arched entrances, one on each side, lead to the diazoma; the one on the north-west side is now 9 or 10 feet above the ground outside, showing that the ground-level has changed, as indeed might be expected on so steep a hillside.

But the most interesting part of the theatre is the stage-building. Its lower parts are buried, but excavation would surely reveal an almost complete stage. The stage-building itself has collapsed, but its front wall is visible, together with certain piles of masonry projecting 4 feet from it. In front is the stage, supported on plain pilasters and paved with stone slabs 7 feet long and about 3 feet wide. Much of this paving is still in place, though some of the slabs have cracked in the middle. This stage projects about 17 feet from the stage-building, and practically closes the parodoi on either side; from this it appears that it belongs to a rearrangement in Roman times. At this period the stage was increased in depth, to accommodate the more numerous performers who then acted upon it, by extending it towards the cavea; in the more elaborate Graeco-Roman theatres, as at Ephesus and elsewhere, the parodoi were covered over and new arched entrances made to replace them, but at Alinda this has not been done. In consequence the stage still preserves very much the same appearance that it previously had in the original Hellenistic theatre, except that the parodoi are practically blocked. The height of the stage cannot now be determined, as its lower part is buried (Pl. 49).

Just below the summit of the hill is the fine tower shown on Pl. 53. It is in two storeys, built in excellent ashlar masonry. The lower storey has two doors in adjoining sides; that on the south has a lintel-block nearly 10 feet long, the other has a triangular relieving space over the lintel. The upper storey has one very large window and several smaller.

Close by this tower is the mouth of a tunnel which is said to run down the hill to the theatre, though no one has been through it; its lower exit is pointed out just above the theatre. That such an apparently useless construction really exists he who will may believe.

On the summit is a circular foundation, over 50 feet in diameter, whose purpose is unknown; and just to the west of it are the foundations of a small building which appears to be a temple. It has two chambers, a pronaos and a cella; if it ever had columns, none are visible now.

Across the saddle to the north-west, on a summit perhaps 100 feet higher, is a second acropolis which seems to have been residential only. It is entirely surrounded by walls of good ashlar masonry 6 to 7 feet thick, enclosing an elongated area some 250 yards in length, sloping gently down towards the west, and divided by a cross-wall (H on the plan) at its narrowest point. There must presumably have been a gate in this wall, but only dubious traces remain. On the south, at a much lower level, is a kind of annexe (E), defended like the main enclosure by a wall with towers. At J a gate gives access to this lower level; the gate itself, about 8 feet 6 inches wide, is standing on one side to six courses, of which the topmost curves inwards to form the beginning of an arch. This gate is protected by an adjoining tower.

Over the whole area are remains of private houses. These are comparatively few at the highest point B, but on C, E and F, and especially G, they are abundant; outlines of walls may be made out, together with door-posts, threshold-blocks and great quantities of loose uncut building-stones. At K is a row of six good-sized cisterns just inside the wall; they are sunk at least 17 feet into the ground, and are lined with poor-quality masonry heavily coated with plaster 2 or 3 inches thick and still showing traces of red colour.

This second acropolis is joined to the first by a good strong wall, with towers, crossing the broad ravine which runs southward from the saddle. There was also a wall across the saddle itself, but of this only scanty traces survive.




FIG. 30 Alinda. The Second Acropolis

Beyond the second acropolis, across the dip which separates it from the next hill, runs an aqueduct still in good preservation. It is well and strongly built, though without much pretence to elegant finish. There remain four arches and a stretch of solid wall pierced by a gate, no doubt for the passage of a road—or rather path, for it is only 6 feet wide. It is at present possible to walk also through the arches, but the ground-level was originally lower. Above the arches runs the water-channel,

consisting of two parallel rows of blocks set on edge and covered with other blocks, five of which are still in position.

Tombs are very numerous on all sides of the city, even on the far side of the hill beyond the aqueduct. Most common are graves of the 'Carian' type, cut in a boulder of rock (sometimes two side by side) and covered with a separate lid; most of these are full-length graves, but a few are mere rectangular holes about 18 inches square with a raised rim. There are also many sarcophagi, quite plain apart from a boss or other projection on the short end of the lid; and in the town are several handsome built tombs, now converted to modern uses. Not a single one of these many tombs carries an inscription, though on one sarcophagus close by the aqueduct there is a sinking with three holes as if for a bronze name-plate. Inscriptions of any kind are indeed exceedingly rare at Alinda; the writer has seen only a fragment built into a window of the mosque, though one or two others have been known. Elegant or artistic carving is equally rare; statues, altars, reliefs, and marble work of any sort, are almost totally absent. If the Alindians had really enough appreciation of art to purchase a statue by Praxiteles, this scarcity is surprising. Mention may, however, be made of a white marble frieze-block built into a wall of a house in the town; it depicts eight persons engaged in battle, and might well come from a temple, but if so the building to which it belonged has disappeared.

AMYZON

High up in the wild country to the north of Alinda lay the old Carian city of Amyzon. It is remote and inaccessible, though jeeps do in fact go up from Karpuzlu in something under two hours by the worst road in the present writer's experience which professed to be passable for motor transport.

Very little is heard of Amyzon in the ancient writers. Strabo groups it disdainfully with Heracleia, Euromus and Chalcedon as 'outposts' of the larger cities; 'these then', he observes, 'are of less account', and makes no further reference to Amyzon. Other authors merely mention her existence. Our knowledge of her history is accordingly confined to what may be gathered from the inscriptions. From these we learn that the city was in

the third century in alliance with the Ptolemies, but towards the end of the century changed its allegiance to support the Seleucid cause. A letter of Antiochus III of Syria, written in 203 B.C., confirms the city's privileges, among which was the right of asylum for the temple of Apollo and Artemis. In the latter part of the second century we find Amyzon concluding a treaty with Heracleia-under-Latmus, but its terms are lost with the damage to the inscription. In the second century A.D. the city restored 'the road allotted to it'. This was somewhat unusual, as road repairs were normally undertaken by the Imperial government. Nothing more is known of the road in question, but it was presumably superior to the one from which the writer suffered. Later Amyzon was the seat of a bishopric.

The site, now called Mazın Kalesi, is a mile or so above the village of Gaffarlar, on the highest point in the neighbourhood. Gaffarlar is a fair-sized village, with a moderate extent of cultivation around it, but for the most part the country is a wilderness of rocky scrub-covered hills. Rather half-hearted excavations have been carried out more than once, but the place is now deserted and overgrown.

Yet the ruins are not negligible. Of the city wall a right-angled stretch some 150 yards long is still standing up to 20 feet in height and 5 feet 6 inches in thickness; the masonry is a very handsome isodomic ashlar dating perhaps around 300 B.C. (Pl. 78). In the interior are the ruins of a temple, possibly that of Apollo and Artemis mentioned in the inscriptions; built into it upside down is a list of officials, among whom the god's name occurs on three occasions. This means that no citizen sufficiently wealthy could be found to serve in those years, and the expenses of the office were undertaken by the temple treasury. The building is so ruined that no idea can be obtained of its exact form.

Close to the road is another building, equally ruined; in it are lying several broken columns fluted only in the upper part, but the masonry is very poor.

Inside the southern stretch of the city wall, and parallel to it, is a series of at least eleven vaulted underground chambers; they are about 80 feet long, 14 feet wide and more than 9 feet high. They are well and strongly built of small stones, and the

lower part of the walls is plastered. The entrance is in each case in the end facing the city wall; they are therefore not cisterns, but presumably store-rooms.

What provision was made for water is not clear. There is no sign of an aqueduct, nor did the writer notice any cisterns on the hill; there are said to be three or four springs within tolerable distance of the site, but in general water is scarce. Today on the way up from Karpuzlu there are at frequent intervals stone huts by the roadside in which are kept one or more jars of drinking-water. The supply is renewed daily by the villagers, an unpaid service which in summer at least deserves the traveller's gratitude.




Gerga

THE THIRD SITE for which Çine serves as a base is of very different character from the other two. It is indeed no more than a village, but the remains are so striking and unusual that the present writer at least knows no place more fascinating. It is somewhat remote, and an adequate visit calls for a full day, mostly on foot. The site lies in the wild mountain country about four miles east-south-east of Eski Çine, and may be approached from there by way of the village of Ovacık; but it is easier now to drive along the new main road from Çine as far as the fine old bridge at İncekemer (Pl. 54), and to walk up from there. A guide is of course necessary. The Çine river may be crossed either by the bridge itself or, to save a little distance, by jumping from rock to rock across the stream at a point nearer to Çine.

In either case it is an hour's gradual climb northwards to the first signs of the ancient village. On either side of a stream-bed, dry in summer but in winter running southwards into the Çine Çayı, is a good-sized rock bearing the name *Gerga* in Greek letters nearly 3 feet high. On the western rock the name is divided between the east and north faces. Such an ancient equivalent to the modern road-sign is unexampled in the writer's experience. But at *Gerga* the visitor is amazed to find the same thing repeated again and again; in at least nineteen places (there are certainly more) the name is written on the rocks in the same huge letters 2 to 3 feet high. Not always in the same form, however; sometimes it is *Gergas* and sometimes *Gergakome* (the village of *Gerga*).

Just to the west of the spot mentioned above is a steep hill-side, and near the top of this is the next surprise, a colossal statue fallen on its back. It has toppled from its base, which

stands nearby, breaking close above the ankles. It represents a male figure standing stiffly with very square shoulders, the arms by the sides and the feet a little apart. The face and head



- | | |
|-----------------------------------|----------------------------------|
| A - Base with large fallen statue | F, G - Oil-mills |
| B - Temple | H - Terrace-wall with buttresses |
| C - Fountain-house (or tomb?) | J - Fallen Statue |
| D, E - Pyramidal Stelae | |

FIG. 31 Gerga. Plan of the Village Centre

are much damaged, and the features are no longer discernible. And across the breast, in letters 8 inches high, is the name Gerga. This again is unparalleled in the present writer's experience (Pl. 58).

Working gradually upwards from here to the north-west the visitor will pass several cases of the name Gerga or Gergakome written on the rocks (Pl. 55), in one case in Latin letters; he may then cross a saddle to the next hill to the east, which

carries the principal ruins. Here he will find a group of buildings, evidently private houses; they are badly ruined but several doorposts are still standing. Running down from here is a street lined with a wall on either side, in which again the name Gerga may be seen. Lower down the slope is another curious feature, a large flat-topped rock with sloping surface on which is inscribed in Greek letters 'Gerga Enbolo' (Pl. 56). The second word is obscure, but means most likely 'rostrum'—that is, the flat rock served as a speaker's platform at village meetings.

Higher up to the north-east is the village-centre (plan Fig. 31), which is full of interest. It is supported by a curved terrace wall with buttresses, of thoroughly Carian workmanship, and on the terrace above is a group of monuments which is quite unique. The eye is first caught by the handsome building B, still excellently preserved complete with roof (Pl. 59); this is undoubtedly a temple. Its plan is shown in Fig. 32; it is empty, and quite plain apart from two cupboard-like recesses on either side of the door. The roof is constructed with ridge-pole and rafters, in imitation of timber work. And in the pediment over the door is written the name Gergas.

This building is no doubt the gem of the whole site, but it is equalled in interest by the remarkable installation at the east end of the terrace. This consisted originally of two stone stelae 11 feet high, tapering to the top like two-dimensional pyramids, and between these a colossal statue on a base. The two stelae are still standing (Pl. 57), and each is inscribed with the name Gergas. The whole must have formed a most striking and unusual group, but the statue has now fallen over the edge of the terrace and is lying below. It is similar in size and appearance to the other described above, but lacks the head and feet. There is in this case no inscription on the breast; presumably it was sufficient that the name was written on the stelae.

At the south-east corner of the terrace are two blocks F and G, with hollowed surface and an outlet in the form of a hole or groove. These have been used for treading grapes or olives, though this may not have been their original purpose; they may once have supported statues or other objects. More common than this type is the oil- or wine-press in the shape of an

ashtray with central knob; with these a millstone was used in the manner still employed today.

Further to the west, at A on the plan, is another extraordinary monument. Here is a large rectangular base from which a huge statue has fallen and is now lying face downwards, so that little can be clearly seen; it is over 14 feet high. The French




FIG. 32 Gerga. Plan of the Temple

scholar G. Cousin in 1899 had a better view of it; it is a standing figure in a stiff posture, with the hands resting on two cylindrical staffs with swellings at the base. The body consists merely of a flat rounded surface, with four small holes in the breast, apparently for fixing a plaque of some kind (Fig. 33). The head, now missing, was seen by Cousin, who calls it 'absolutely monstrous, with its enormous mouth and small eyes widely spaced'; the head was perhaps covered with a veil. On

the bottom step of the base is a lion's head at the right end, and at the left end a semicircular projection; on the step above, in the middle, is a bull's head. A few paces to the east, projecting from the same platform on which the statue lies, is a kind of base adorned with five objects each formed of two contiguous




FIG. 33 Gerga. Statue

balls like a figure 8, arranged in a semicircle; the largest is 2 feet 4 inches long. These are puzzling; Cousin's explanation, that they are the toes of the statue's right foot, is startling rather than convincing (Fig. 34).

At various points on the site—the writer saw four of them—are small square buildings about a man's height, all closely similar to one another. They are open in front and roofed with a single large slab; the floor inside is hollowed out. They are all

inscribed with the name Gerga in its various forms; one of them (Pl. 60) has the name three times, on the edge of the roof-slab over the entrance, on the right-hand interior wall, and on the roof looking to the sky.

These buildings have been considered to be tombs, and the French scholar A. Laumonier, who has made an extensive




FIG. 34 Gerga. Base

study of the Carian cults, sees in the site of Gerga as a whole a kind of sanctuary, its central point the funerary temple B, that is the tomb of the local god or hero Gergas, with the tombs of priests or other notables closely grouped around it, in accordance with the familiar desire (not only in ancient times) to be buried as near as possible to some sacred spot. The habit of writing the name Gerga or Gergas on the tombs he ascribes to religious or magical motives, for example to invoke the protection of the deity. The present writer has to confess that this was not the impression that he received. The buildings described above seemed to him to be not tombs at all, but fountain-houses. Fountains would be very necessary, for the site is almost entirely dry in summer; there is one spring, but by the end of summer it is reduced to a miserable trickle. A number of considerations support this view. The front of the buildings is completely open, and there is no sign that it was ever closed. On the inner wall of one of them is carved a dolphin, the normal symbol of water. Another has a hole in the back wall which seems to be a pipe-hole. And round the interior walls of a third is written Gergakome. To write the name of a god on the inner wall of a tomb is one thing, but to write the name of the village is another; there seems no reasonable motive for such a proceeding. Nor does any of the buildings contain any visible provision for a burial. The writer indeed saw nothing on the site

which seemed to him to be a tomb, for there appears no cogent reason why even the 'funerary temple' should need to be really a tomb rather than a straightforward temple.

There is little sign of Hellenic culture on the site. The three surviving statues are crude in style and of archaic appearance, and the masonry in general is Carian rather than Greek. Nevertheless it would be a mistake to suppose that the monuments of Gerga must go back to a remote antiquity. On a small and secluded site like this there is a strong tendency to conservatism, and the criteria of classical Greek art do not apply. It is indeed doubtful if anything there is earlier than the Roman Empire; the inscriptions, both on the rocks and on the buildings, are unquestionably of that period. One or two fragments of inscriptions on stone have been seen, but have now disappeared; here again the style of writing is of the Roman age.

On the various problems provided by the site every visitor will form his own opinion, but of one thing there can be no doubt; no one who makes the effort to visit Gerga will feel that he has wasted his day.



Tralles and Nysa

IN THE GREAT migrations of Greeks into Asia Minor barbarians normally played no part. It is therefore surprising to read that in antiquity the city of Tralles was believed to have been founded by an oddly assorted company of Argives from the Peloponnese and Trallians from Thrace or Illyria. If this tradition has any basis of fact, it is further surprising that the city should have taken its name from the barbarian element rather than the Greek. It had also, we are told, at some time the names Charax and, from the abundance of flowers that grew there, Euantheia. How much of all this may be accepted is very dubious.

Tralles first appears in history in 400 B.C., when the Spartan general Thibron was attempting to recover the cities of Asia from the Persians; his attack on Tralles failed by reason of the strength of the position. Diodorus, who records this, calls her a city of Ionia; much more normally she is reckoned to Caria, though some prefer to regard her as Lydian. On Alexander's arrival in 334 Tralles submitted quietly, and was used by the conqueror as a base.

Antigonus in 313 was more successful than Thibron and was able to take the city by force. After his death in 301 it fell into the hands of the Seleucids, and while their power lasted assumed the name of Seleuceia. Pliny says that it was also called Antiocheia; no reason appears why the same city should be called after two kings, both Seleucid, and this statement of Pliny's, for which there is no other evidence, is generally disbelieved. When the Seleucid power was broken at the battle of Magnesia in 190, Tralles was given by the Romans to Eumenes of Pergamum. A later Pergamene king, Attalus, had a palace

in the city built of brick; this was afterwards used as a residence by the chief priest of Zeus.

When Aristonicus was disputing the Roman inheritance of the Pergamene kingdom, Tralles made the mistake of supporting him; as a punishment it appears that she was deprived of the privilege of minting coins. The city had nevertheless the rank of a *conventus* under the Roman Republic, though under the Empire this was transferred to Ephesus. In the Mithridatic War of 88–85 B.C. the slaughter of the Roman residents was apparently instigated at Tralles by the sons of a certain Cratippus, who for a short while held the position of tyrants there.

When Julius Caesar defeated Pompey in the crucial battle of Pharsalus in 48 B.C., many portents of this great victory were reported from many parts of the world. At Tralles, we read, there stood a statue of Caesar surrounded by a stone pavement laid on hard ground; yet from this pavement a palm-tree sprouted.

A year or two after the foundation of the Empire Tralles suffered from a severe earthquake. Augustus came to the rescue with financial help, and in gratitude the city took the name of Caesarea. The history of this name is characteristic: down to the time of Nero the coins are inscribed 'Caesarea' only; after this 'Caesarea Tralles'; and by the end of the first century 'Tralles' only as in the past.

Strabo refers to the great wealth and prosperity of the citizens, and notes that 'the leading men of the province, who are called Asiarchs' were frequently men of Tralles; yet when she and ten others competed for the privilege of erecting a temple to Tiberius, she was passed over, like Laodiceia, as lacking sufficient resources. We can only conclude that the expenses connected with a cult of the Emperor were formidable indeed.

The principal deity of Tralles was Zeus, with the title Larasius, that is, according to Strabo, Zeus of Larasa, a village three miles to the north on Mt. Messogis—though in fact he uses the forms Larisa and Larisius. The chief games celebrated in the city were the Olympia and Pythia, modelled on the great games of classical Greece.¹

As distinguished citizens Strabo mentions the family of

¹ See below, p. 227.

Pythodorus, who came originally from Nysa,¹ and among well-known orators a certain Damasus, who had the curious nickname Skombros, 'the Mackerel'. The cultivation of figs, which are the principal product of the Maeander valley today, is not noticed in antiquity, and Tralles was famous chiefly for her pottery.

The site of Tralles at Aydın (formerly called Güzelhisar) answers well to Strabo's description: the city, he says, is founded on a flat-topped hill with a steep acropolis, and is well defended all round. The ruins are seldom visited these days, for two good reasons: there is very little to see; and the site is occupied by the army, so that a permit from the municipality is needed. At the end of the last century a fair amount was to be seen, notably a gymnasium, a theatre and a stadium; the present writer in 1946 found hardly anything remaining. Long occupation by the military has had its usual effect of obliterating all that was there before.

The only thing actually standing is a row of three tall arches, called the Üç Göz, which formed part of the gymnasium. They are of poor-quality masonry of late Roman date, partly of large stone blocks with abundant mortar and partly of brickwork. The whole was coated with stucco, which still remains on the underside of the arches. Close by is a wall of similar construction, presumably belonging also to the gymnasium, and a row of five column-stumps resting on a mass of brickwork.

At the north end of the flat hilltop is the acropolis hill, with the theatre at its foot. This was excavated in 1888 and proved to be of considerable interest, if only because it was one of the very few that had an underground tunnel in the orchestra. This was 7 feet deep, and in the centre of the orchestra branched right and left at right-angles; its beginning and end, however, were not determined. These tunnels are supposed to have been used for the appearance of characters from the underworld. In 1946 nothing of this remained; a broad trench had been driven, for some obscure military purpose, right through the orchestra. A corner of the cavea was still visible on the east side, and also on the east side the arched entrance to the upper diazoma; nothing more.

¹ See below, p. 212.

Of the stadium too very little remains. The vaulted entrance is preserved at the east end; like the gymnasium it is partly of stone, partly of brick. At various points on the site later excavations revealed the foundations of temples, but these are no longer in evidence.

Travellers to whom time is of importance will therefore probably content themselves with the view of the Üç Göz from the road or railway.

NYSA AND ACHARACA

Eastward of Aydın the south face of Mt. Messogis is cut by innumerable stream-beds, torrents in winter but dry in summer. Set astride one of these, a mile above the village of Sultanhisar, are the ruins of Nysa.

Nysa is a frequent name on the map of the ancient world; Stephanus of Byzantium lists ten cities so called. It was also a not uncommon name among the ladies of the Hellenistic royal families, and according to the same writer the Carian Nysa was founded by Antiochus I of Syria and named after his wife.¹ Strabo, on the other hand, says that three brothers, Athymbrus, Athymbradus and Hydrelus, came from Sparta and founded three cities in their own names, and that these were afterwards united in a single city Nysa, of which Athymbrus was regarded as the founder. Strabo knew Nysa well, for he was educated there, and his account surely represents the belief of the citizens themselves. Moreover, Stephanus also, in another passage, says that the old name of Nysa was Athymbra, and in inscriptions down to the end of the third century B.C. the Nysaeans are called Athymbrians. Since Strabo makes no mention of the Seleucids, and since no wife of Antiochus I by the name of Nysa is otherwise known, it is likely that this part of Stephanus' testimony should be discredited. Equally or even more improbable is yet another statement of Stephanus', that Nysa was once called Pythopolis after a certain Pythes (otherwise unknown) who entertained Xerxes in 480 B.C. Nothing has been found on the site to suggest that a city existed there before the third century. It seems probable that the name

¹ For the story see below, p. 247.


Nysa was given at some time after 200 B.C. in honour of some female member of the Seleucid line, though the lady in question and the occasion are equally unknown. At the same time, and in spite of Strabo's silence, it is almost certain that Nysa was a Seleucid foundation, for as early as 281 B.C. we find Seleucus and Antiochus writing to the Athymbrians to confer or confirm certain privileges.

Nysa has little individual history. An inscription gives us a glimpse of events at the time of the Mithridatic War, when a rich Nysaeon by the name of Chaeremon furnished the Roman commander with 60,000 bushels of wheat as provender for his army. This conduct so enraged Mithridates that he put on Chaeremon's head a price of forty talents if taken alive, twenty if dead. Chaeremon took refuge in the sanctuary of Ephesian Artemis (whether in Ephesus itself or at Nysa, for her cult was very widespread), but it seems that the right of asylum may not have been respected by the king, and that Chaeremon was taken and put to death. His family was distinguished as well as rich; a relative of his named Pythodorus was among the closest friends of Pompey the Great and possessed a fortune of over 2,000 talents; he married a daughter of Mark Antony, and their daughter Pythodoris became in turn queen of Pontus and of Cappadocia. She was, says Strabo, a sensible woman and well able to manage affairs of state.

Nysa was not backward in the field of letters. Strabo mentions a number of distinguished orators and philosophers who were natives of the city; among them was his own teacher Aristodemus, who held classes twice daily at Nysa, rhetoric in the morning, grammar in the evening. At Rome he taught the children of Pompey, and he had also a school in Rhodes.

But the chief claim of Nysa to distinction lay in the existence on her territory of a healing sanctuary of Pluto, god of the underworld, close to which was a remarkable cave called the Charonium. The site was at the village of Acharaca, three miles on the road from Nysa to Tralles. More will be said of this below.

Strabo describes Nysa as lying on the slope of Mt. Messogis, close above the plain; it is, he says, a kind of double city, being split down the middle by a stream forming a ravine; of this,



- | | | |
|-------------------|------------------|------------------------|
| A - City Wall | F - Baths | K - Library |
| B - Theatre | G - Amphitheatre | L - Byzantine Building |
| C - Tunnel | H - Kâtip Ören | M - Water-depot |
| D - Council-House | J - Gymnasium | N - Bridge |
| E - Agora | | |

FIG. 35 Plan of Nysa

part is spanned by a bridge joining the two halves of the city, and part is adorned with an amphitheatre, under which the stream flows concealed. Below the theatre lie on one side the gymnasium of the young men, and on the other the agora and the Council-House of the Elders. This account may be verified on the ground today.

From Sultanhisar a newly-constructed motor-road leads directly to the theatre. This has now been almost completely excavated, by local effort financed by the Turkish government. It is a little above average size and forms rather more than a semicircle. The cavea is in good condition, with most of the seats remaining; it has one diazoma, with twenty-three rows below it and twenty-six above. There is an arched entrance (vomitorium) low down on each side. The nine stairways below the diazoma are increased, in the usual way, to seventeen above it; other steps lead up from the diazoma to the upper seats. The stage-building is of Roman type, with five doors leading onto the stage, but it has not been entirely cleared. The front wall of the stage, and a part of its decoration, is visible, with a fragmentary inscription referring to persons by the names of Justus and Stratonice; nothing is known of these, but they presumably contributed in some way to the construction or embellishment of the theatre (Pl. 61).

Just below the theatre the stream runs through an ancient tunnel, admirably constructed and about 100 yards long, lit at one point by a shaft in the roof. About the middle it makes an obtuse bend, and here, on the north wall, is cut an inscription: 'Work of ...lus up to this point'. The beginning of the man's name is now lost, nor is it clear why he did not finish the job; perhaps funds ran out.

The vast constructions in and over the ravine, referred to by Strabo, are unfortunately in very poor condition. The 'bridge' of which he speaks was in reality a great platform spanning the northern part of the gully from the west end of the tunnel to the north end of the amphitheatre, but only a few rather shapeless pieces of its masonry remain. The amphitheatre itself is in no better case, though a few of its seats are, with some difficulty, discoverable. The idea of making use of the sides of a stream-bed to build an amphitheatre is not confined to Nysa;

the same may be seen, for example, at Pergamum, at Cyzicus, and at Tripolis in Phrygia. The plan had the further advantage that the water of the stream was readily available (at least till May) to flood the arena for mimic sea-fights and other water-spectacles.

Of the gymnasium, on the west side of the ravine, hardly a trace is now visible; the site is chiefly recognisable as a level area some 180 yards in length. Close to the south end is a better preserved building known today as Kâtip Ören. The original plan is obscured by a church which was later built over it, but it is likely to have been a baths; water-pipes are much in evidence, and ancient gymnasia were normally accompanied by baths. The chief features are the arches in the walls; but the masonry is very late, and it is certain that this building did not exist in Strabo's day.

On the other side of the ravine are the agora and Council-House of the Elders. Of the agora only a small part of one side has been excavated; a few column-stumps are standing, and others are lying around, but nothing more. The council-house (*Geronticum*) on the other hand is perhaps the most attractive building on the site. It is excellently preserved and completely excavated, with twelve rows of seats and five stairways. The building forms a semicircle within a rectangle, of which the back is supported by large double half-columns. Behind the speakers' platform four large solid piers make three entrances. Outside this are the bases of a row of eight columns, the middle six on high pedestals, and behind this again is a long narrow bathing-pool; close by is a marble bath with a plug-hole. Two inscriptions have come to light; one refers to the two Empresses, the elder and younger Faustina, the other is an epigram in verse, for some reason left unfinished.

Of the buildings not mentioned by Strabo, the library is no doubt the most interesting. It may indeed not have existed in his time, for in its present form at least it can hardly date before the second century A.D. It had originally two, or more likely three, storeys, but of these the uppermost is almost entirely destroyed, and the ground floor is buried to most of its height. The adjoining sketch shows the plan of the first floor. The niches in the walls, rectangular and vaulted, which held

the books must be imagined as veneered with marble or stucco which is now gone. The entrance must have been on the south side, but the south wall is completely destroyed. It is noticeable that the bookshelves, on either side of the central reading-room, were not in the outer wall of the building, but separated from it by a gallery; the same feature is to be seen in the library




FIG. 36 Nysa. Plan of First Floor of the Library

of Celsus at Ephesus, its purpose being to protect the books from damp. It is to be hoped that this building will one day be excavated, for the ground floor is probably in quite good preservation. In its present condition it hardly gives a fair idea of what must have been a very handsome building.

There are many other structures on the site, all of late date, indifferent masonry and uncertain purpose. Even the city wall is not earlier than Byzantine; for the ordinary visitor its scanty remnants barely justify the effort of tracking them down. There must presumably have been a wall in Hellenistic times, but no vestige of it survives.

In the village school in Sultanhisar there is a small collec-

tion of antiquities, including the remarkable piece of sculpture shown in Fig. 37.

From Nysa a road lined with tombs led westward towards Tralles, passing through the village of Acharaca. It is scarcely



FIG. 37 Nysa. Dolphin and Boy at the School in Sultanhisar

possible now to follow this road, which crosses a number of steep ravines, and the ancient bridges are no more. A visit to Acharaca is most easily paid from Çiftekahveler on the modern highroad, from which a tarmac road leads up to the village of Salavathı. The site is just outside the village.

Strabo's account is as follows. On the road from Tralles to Nysa there is a village of the Nysaeans called Acharaca, in

which are the Plutonium, with a rich precinct and a temple of Pluto and Persephone, and the Charonium, a remarkable cave lying above the precinct. Here, it is said, sick persons go to be cured by these deities, and dwell in the village near the cave with the more experienced of the priests; these incubate on behalf of the patients and prescribe treatment in accordance with their dreams, though sometimes the patients do the dreaming themselves. Often the sick are taken into the cave and installed there, like animals in their lair, for several days without food. For all others the place is forbidden ground, and indeed deadly rather than curative. A festival is celebrated there, at which a bull is taken up into the cave by the young men of Nysa; when released, the animal goes forward a little, then collapses and dies.

The Plutonium has been identified and partially excavated; it lies close to the east side of the ravine in which the stream flows past the village. The ruins are hardly impressive, but enough survives (or survived early in this century) to enable a provisional restoration of the plan (Fig. 38). The form of the temple, if rightly reconstructed, is highly exceptional; the colonnade had six columns at the ends and the unusual number of twelve on the long sides. Ten of these have been identified in their original positions. Unusual also is the north-south orientation, with the entrance apparently on the north. Most remarkable of all is the interior arrangement, with two parallel walls running the whole length of the temple. It should, however, be borne in mind that the restoration is largely conjectural, the surviving fragments (shaded on the plan) being so very scanty.

At present even less than this is visible. In the excavation hollow is a row of six unfluted column-drums, 3 feet 6 inches in diameter, in their original positions, a large column-base with torus moulding, and two or three large blocks lying loose; and beside the path between the village and the stream are two blocks of a Doric triglyph-and-metope frieze.

By Strabo's account the cave called Charonium should be somewhere above the temple, but it seems clear that none answering the description exists today. A little to the west, however, is the source of the stream in a deep and narrow gully;




FIG. 38 Acharaca. Plan of the Temple (conjectural)

the stream is heavily charged with sulphur and has a bright yellow colour which gives it its name of Sarisu. The smell of sulphur is said to be often very strong in winter. In the high and steep rock-walls of the gully are a number of ancient buildings of the arched type so characteristic of Nysa. Although no proper cave is to be found, it may well be that this place, which is quite impressive, does in fact represent the Charonium; it is the sort of place which had religious associations in antiquity. Caves can fall in and disappear; and it is easy to imagine the patients installed in the arched buildings in question. In any case it is hardly doubtful that the healing properties of Acharaca derived from the presence of the sulphur-bearing stream (Pl. 63).



Aphrodisias

'FOR SOLOMON went after Ashtoreth the goddess of the Zidonians . . . and Solomon did evil in the sight of the Lord'.¹ Ashtoreth of Sidon, Ishtar of Babylon and Nineveh, Astarte, Aphrodite or Venus, the worship of the laughter-loving Goddess of Love was virtually ubiquitous. Even for the wisest of the kings of Israel her power was too strong. Cities named after her were common; Stephanus of Byzantium lists a dozen places, towns or islands, by the name of Aphrodisias, of which the best known, at least in Roman times, was the city on the eastern border of Caria.

According to Stephanus the city was founded by Pelasgian-Lelegians and called Lelegonpolis, then Megalepolis, then Ninoe after Ninus, king of Assyria. The first two of these names may safely be disregarded; this is not Lelegian country, and there was certainly no 'great city' on the site in early times. The third name Ninoe, however, may well be historical. It is likely enough that Assyrians from Nineveh may have established a cult of Ishtar in this rather remote region, before or after the destruction of Nineveh by the Medes and Babylonians. We seem indeed to have a trace of such a tradition in the cult of Zeus Nineudius which is recorded in the later inscriptions of the city.

That the site was occupied very early is beyond doubt. The recent excavations have revealed pottery going back to the Early Bronze Age in the third millennium, and even to the Chalcolithic period before 3000. But the evidence for a city of Aphrodisias is surprisingly late. The name at least seems established by the third century B.C., when the historian Apollonius came here from Egypt to settle, and wrote a book on Caria; he is called Apollonius of Aphrodisias. Yet the first

¹ I Kings 11.5-6.

mention of a *city* is not earlier than the first century. In 82 B.C. the Roman general Sulla, in response to a Delphic oracle, sent an axe and a golden crown to Aphrodite; the oracle speaks of 'a very great city of Caria named after Aphrodite'. But oracular language is often exaggerated.

Before this we must imagine a sanctuary of Ishtar-Aphrodite, with no doubt a considerable settlement around it, quite highly civilised; apart from pottery and figurines of the sixth and fifth centuries, coins of Alexander and a fragmentary Lydian inscription have been found on the site. By the second century this settlement had developed into a city.

The modest beginnings of the city of Aphrodisias are clearly shown by her relations with the neighbouring city of Plarasa.¹ Between 39 and 35 B.C. Mark Antony sent to Aphrodisias a copy of a decree of the Senate conferring freedom and immunity from taxation on 'the city of the Plarasans and Aphrodisians', and on the temple of Aphrodite a right of asylum equal to that of Artemis of Ephesus. Similarly, on the coins down to the time of Augustus both names occur, and Plarasa is placed first. Under the Empire Aphrodisias alone is named, and Plarasa fades from view. It seems that the sanctuary of Aphrodite was on the territory of Plarasa, and as it developed the two places united into a single city; in the course of time the newer member gained the dominance and Plarasa sank to the status of a deme of Aphrodisias.

New glimpses into the city's history are afforded by the inscriptions recently discovered in the course of excavating the theatre.² These are not yet formally published, but include a whole series of letters from the Emperors, ranging from Augustus to Gordian III in the third century. Another records a treaty with the neighbouring cities of Tabae and Cibyra in the second century B.C. From another it appears that the city suffered from looting at the time of the war with Labienus in 40 B.C., losing among other things a golden statue of Eros dedicated by Julius Caesar, but later recovered.³ A third is a

¹ The Carian city of Plarasa has been located with fair probability at Bing , nine miles to the south-west of Aphrodisias.

² See below, p. 229.

³ It seems that the thief had had the effrontery to dedicate it in his own name to Artemis of Ephesus.

letter from Hadrian exempting the city from the Nail Tax (whatever that may have been).


In Imperial times Aphrodisias was very rich and prosperous. As a measure of the wealth of her citizens, a certain priest of Heracles, Attalus Adrastus, gave 122,000 denarii for a hall of sacrifice and a banqueting-hall, and in his will left over a quarter of a million for gymnastic purposes. Aphrodisias was famous as a seat of medicine and philosophy, and above all for her school of sculptors. This last has been abundantly confirmed by the quantity of statues and reliefs found by the excavators, and a sculptor's workshop has been located on the site.¹ At one of the festivals celebrated in the city a contest in statuary was included—a form of competition which seems to be unparalleled elsewhere.

The principal deity was naturally Aphrodite. After her, the most frequently represented on the coins is Dionysus, and other members of the Greek pantheon are mentioned in the inscriptions. A non-Greek deity is the Phrygian Men Ascaenus, and Zeus bears the two curious titles of Nineudius, mentioned above, and Spaloxus. The meaning of the latter is unknown.

The site of Aphrodisias at Geyre has never been in doubt. Somewhat superficial excavations have been carried out several times since the beginning of the present century, and in 1961 a thoroughgoing investigation was begun under the auspices of New York University; this is still in progress at the time of writing, and has already transformed the site.

The temple of Aphrodite has always been conspicuous, though little of it survives apart from the colonnade. It was in the Ionic order, with thirteen columns on the long sides and eight at the ends; the style was 'pseudodipteral', that is the columns were placed at twice the usual distance from the side walls, as if to give the effect of a double row without the expense of the inner row. The temple itself comprised a pronaos and a cella, but no opisthodomus. It was formerly thought to date from the time of Hadrian, but is now shown to have been begun in the late second or early first century B.C. At the same time the excavation has produced sherds of archaic date, and there is in fact some slight evidence for an earlier temple on the

¹ See below, p. 228.



- A - 'Acropolis Hill'
- B - West Gate
- C - North Gate
- D - East Gate
- E - Stadium

- F - Temple of Aphrodite
- G - Theatre
- H - Odeum
- J - 'Bishop's Palace'
- K - Propylon


- L - Baths of Hadrian
- M - Agora
- N - Portico of Tiberius
- P - Sculptor's Workshop
- Q - Museum Depot

FIG. 39 Plan of Aphrodisias


spot: there are traces of an early Hellenistic mosaic which was cut through in building the pronaos. In early Byzantine times the temple, except for the colonnade, was destroyed to make way for a church, of which the apse is standing at the east end. At this time it appears that the columns on the short ends were removed and added to the side rows; this accounts for the curious fact that the end column but one on the north side, as




54 Bridge at İncekemer.



55 Gerga, Inscribed rock.





56 Gerga, Speaker's Platform (?)




57 Gerga. Pyramidid Stele.



58 Gerga. Colossal statue on western hill.





61 Nysa. The Theatre.

59 Gerga. Temple.

60 Gerga. Fountain-house (or tomb?)



62 Nysa. The Library.

63 Acharaca. The Charonium (?)



64 Aphrodisias. The Stadium.

65 Aphrodisias. Sarcophagus.



66 Aphrodisias. Temple of Aphrodite.



67 Aphrodisias. Columns of the Agora,



68 Aphrodisias. Baths of Hadrian.

69 Aphrodisias. Bull's Head.

70 Aphrodisias. Sarcophagus.





71 Hierapolis. Petrified Cascades.

72 Hierapolis. The Sacred Pool.




73 Hierapolis. Sculpture in the Theatre.




74 Hierapolis. Triumphal Arch and Main Street.




75 Hierapolis. The Plutonium.



76 Laodiceia. Water-tower, showing remains of pipes. 77 Laodiceia. The Aqueduct.





78 Amyzon. The City Wall.

is shown by the form of its capital, was a corner column in the original temple. At present fourteen columns are still erect and almost complete, in several isolated groups; two groups have the architrave still in place. Some of the columns bear inscriptions recording their presentation by individual citizens to Aphrodite and the People.

The form of the cult-statue is known from a number of copies. The goddess stood in 'hieratic' form, stiffly erect with forearms extended, like the Ephesian Artemis, and wearing a long robe decorated with bands of relief. The usual arrangement of the reliefs is: at the top, the sun-god and moon-goddess, sometimes with Aphrodite between them; below this, the three Graces, sometimes between two deities; next, Aphrodite seated on a goat with fish's tail; and finally three Cupids. This last is often omitted, and there are other variations also. A statue of this form was found in 1962 just outside the temple precinct. From the inscriptions it appears that Aphrodite was served by male priests.

A hundred yards or so to the east of the temple stand the spiral-fluted columns of a monumental gateway. This is not quite aligned with the temple and is not the entrance to the temple precinct; the boundary of the precinct seems in fact to be marked by a handsome wall with maeander frieze immediately behind the temple on the east.

The city wall is late, not earlier than the fourth century A.D., and contains a great number of reused stones, many of them inscribed. It is best preserved on the north side. No sign of an earlier wall is to be seen, and it may well be that the city relied for protection on its sanctity. A block built into the wall on the north-east carries the following inscription: 'Whoever throws rubbish here shall incur the curse of the 318 Fathers'—that is the bishops assembled at the Council of Nicaea in 325.

Three gates are preserved, on the west, north and east. That on the west is called in an inscription the Antiocheian Gate; Antiocheia on the Maeander was in fact the nearest city on that side. It is dedicated by its inscription, on the outer side, to the 'health and safety and fortune and victory and eternal survival' of the Emperor Constantius II (323-61).

The North Gate lies a short distance to the east of the

stadium. Its inscription, on the inner side, is interesting. It is in two parts; the upper records the building of the wall, probably in the fourth century; the lower refers to a later restoration of the gate 'for the good fortune of the brilliant Metropolis of the Staurupolitans'. The name of Aphrodisias was in fact changed in the seventh century to Staurupolis; the old name offended Christian susceptibilities and the City of Aphrodite became the City of the Cross. The restoration in question is

ΤΗΣ ΑΜΠΡΑΚΤΑΥΡΟΥ ΠΟΛΙΤΩΝ ΜΗΤΡΟΠ
 ΠΕΛΙΟΥ ΤΟΥ ΕΛΛΟΓΙΜΕΣ ΧΚ ΠΑΤΡΟ

FIG. 40 Aphrodisias. Part of the Inscription over the North Gate

actually earlier than this, for the inscription originally read 'Metropolis of the Aphrodisians'; this name was erased and the other substituted. By a curious exercise in economy the letters *πο*, which happen to be common to both names, were left un-erased in making the alteration, as also were the last two letters. In actual fact, as the inscription stands it reads 'Metropolis of the Taurupolitans'; the previous word chances to end in *s*, and this letter was made to do double duty. Altogether a remarkable piece of epigraphical cheese-paring.¹

The East Gate also is in very fair condition, a triple arch of which the middle has collapsed. The south wing is a handsome wall, decorated with reliefs showing a human head, floral and other designs. The date is equally late, as is shown by the inscriptions, of about the second century, which are built into the arches.

The stadium, dating from the early Empire, is one of the best preserved anywhere in the ancient world. It is rounded at both ends, each with a tunnel entrance; that on the west is now blocked by a solid wall at its outer end. As at Priene and else-

¹ It was thought at one time, on the strength of this inscription, that Aphrodisias did for a while have the name Taurupolis, 'city of the bull'. Stephanus in fact records a city of Tauropolis in Caria, and even mentions an alliance with Plarasa; but this was in the third century B.C. and a different city must be meant. The name Staurupolis is regularly given to Aphrodisias in the Byzantine lists (though even here Taurupolis also occurs, no doubt by error).

where, the rows of seats are slightly curved to afford a better view of the whole length. In the middle of the north side is a Royal Box. No starting-sill for the foot-races is preserved, but among the blocks lying in the arena at the west end are a slender unfluted column-drum, a dentil frieze and other blocks which might possibly belong to a structure such as that at Priene.¹ At the east end, as at Ephesus, a curved wall has been built across at a late date to form a nearly circular area for entertainments of the Roman type; gladiatorial shows are mentioned in the inscriptions. The blocks along the top of this wall are pierced, mostly two to a block, with holes going through from the upper surface to the front face, as if to hold ropes. The writer has seen no explanation of these, nor any parallel elsewhere.

The stadium was the scene of all the athletic and most of the other contests in the various festivals held in the city. These festivals were very numerous in Roman times and naturally varied greatly in reputation. Some were modelled on the great games of classical Greece, especially the Olympic and Pythian games, and had the same name, organisation and prizes; thus we find 'Olympic' games celebrated all over Asia Minor. But this could only be done with permission from Rome, and was considered a great privilege. At Aphrodisias we have Pythian but not Olympic games. Others were instituted in honour of, and with the consent of, the Emperor, like the Gordianeia at Aphrodisias. Others again were endowed by a private citizen, and commonly bore his name; these carried less glory and were often restricted to men of the city itself, or of a limited region. The others were normally open. The prizes in the first class consisted merely of a wreath of leaves; but just as a victory at Wimbledon is worth far more to the winner than the actual prize-money, so an Olympic victor might expect to be handsomely treated in his own city. In the smaller games the prizes were in cash. Apart from the normal athletic contests—foot-races, wrestling, boxing, pancration (a kind of unarmed combat) and the pentathlon—a great variety of other events were included. At Aphrodisias we hear of competitions in tragedy, comedy, satyric drama, flute- and harp-playing, oratory and

¹ See *Aegean Turkey*, pp. 208–9.

the war-dance; there were prizes also for heralds, trumpeters and, as mentioned above, sculptors. Second and third prizes were normally given only for the non-athletic events; in athletics victory was the thing that mattered. Horse- and chariot-racing took place separately in the hippodrome; such races are mentioned at Aphrodisias, but the hippodrome has not been located.

Just to the south of the temple is the newly-discovered odeum; its state of preservation is almost perfect. Built in the second century A.D., it was later damaged, perhaps by an earthquake, and repaired. In plan it closely resembles the council-house at Nysa, and may well have been used on occasion as an assembly-room.¹ The floor of the 'orchestra' is elegantly decorated, but is now permanently under water. On the front of the platform is an incomplete inscription referring surprisingly to a palaestra; the significance of this is obscure.

Adjoining the outer wall of the odeum on the west is an interesting heroum, that is the tomb of a distinguished citizen accorded the privilege of burial within the city. It is circular, with three steps leading up to a platform which supported an octagonal arrangement of seats surrounding a large sarcophagus and an altar decorated with Cupids carrying flowers and fruit. The heroum is evidently older than the odeum, since the wall of the latter slightly overlaps it. To the north of the odeum the great quantities of unfinished statues and marble chips found by the excavators show that the building here was a sculptor's workshop; the building itself is, however, poorly preserved.

Beside the odeum on the west is a complicated group of ruins including a peristyle court with blue marble columns, dubbed by the excavators 'the Bishop's Palace'. From a lead seal found in it with an inscription referring to the Metropolis (or Metropolitan) of Caria, and from its convenient proximity to the church which succeeded the temple, it seems not improbable that this may have been the residence of the bishop of Aphrodisias-Staurupolis.

The acropolis, the only elevated ground on the site, is so called merely for convenience. It is not a natural hill, but

¹ See below, p. 255, n. 1.

simply the accumulation of the earliest levels of occupation, for this was evidently one of the first areas of settlement in prehistoric times. Trenches sunk on the western slope brought to light material dating from the Middle Bronze Age about 2000-1600 B.C., including storage vessels containing charred seeds. At a spot further to the east, called the 'Pekmez Area', even earlier sherds were found.

On the east slope of the 'acropolis' is the great theatre, at present in process of excavation. It proves to be in excellent condition, with most of the seats still in place, and will eventually be one of the finest in Asia Minor. It is unusually large and had apparently the exceptional number of three diazomata; at least, an inscription refers to 'the third diazoma', though the excavations have revealed no sign of this, and it seems indeed difficult to find room for it. The stage and stage-building also are well preserved, at least in the lower parts, but are not yet fully cleared at the time of writing. The arrangement at the north end is peculiar. The north return wall of the stage-building is standing to a height of 16 or 17 feet and flanks a passage or corridor, on the other side of which is a large vaulted room. Such a room is not a normal part of a theatre, and in this case it is evidently a later addition to the original plan. Its purpose is not known; a green-room or property-room is a possibility. But it was the wall of the stage-building that caused the excavators the greatest surprise and delight; it proved to be covered with the long series of Imperial letters which was mentioned above. When their contents are published these cannot fail to improve our scanty knowledge of the city's history under the Empire.

Between the theatre and the temple lay the agora. This has not been excavated, and is at present occupied by a grove of poplar-trees. Of the colonnade which surrounded it a group of seven columns is standing (Pl. 67), and the bases of many more are still in place.

Further to the west is the Baths of Hadrian. This is not yet completely cleared, and the identity of all the rooms is not certain. In front (1 on the plan) is a courtyard handsomely paved with black and white squares. Adjoining this on the south (Room 2) is the frigidarium; this is not heated and has a

shallow pool at its west end. Room 3 is the tepidarium, slightly heated by means of a hypocaust, and Room 4 is the hot room or caldarium, also with a hypocaust of which a good deal is preserved (Pl. 68). Room 10 is the praefurnium or furnace-room, with a laconicum or sudatorium (sweating-room) on




FIG. 41 Aphrodisias. Plan of the Baths (approximate only)

either side (9 and 11 on the plan). The open court 7 has a shallow square pool in the middle. Room 8 was in all probability the apodyterium or changing-room, from which the bather might pass first to the frigidarium 2, then to the successively warmer rooms 3, 4 and 9, finishing perhaps with a cold plunge in the pool 7. Rooms 5 and 6 have not yet been excavated; it is likely that they, together with Room 11, formed the women's baths, which are often separate from the men's rooms; this would explain the second laconicum 11.

Immediately to the east of the baths is the palaestra 12, for gymnastic exercise; baths and palaestra commonly went together. To the east again is the Portico of Tiberius; this is only partially excavated. It was decorated with a most striking frieze of heads and masks joined by garlands; many of these, discovered in 1937, are now in the museum in Smyrna, and others have been found during the recent excavations. The portico extended a long way to the east and united with the agora to form an impressive complex.

The tombs at Aphrodisias lay in the usual manner outside the walls. Many of the sarcophagi are very handsome, as may be seen from the specimens collected outside the museum depot. The inscriptions are mostly long, with detailed instructions as to who may be buried inside, and invoking fines and curses on anyone who may violate the tomb. The fines vary in amount up to 50,000 denarii. These epitaphs throw much interesting light on family life and social customs; one, for example, permits the owner's wife to be buried, but only if she remains his wife and produces a son.

The museum contains some excellent sculptures of the Aphrodisian school, in particular a number of first-rate portrait statues. Two full-length standing figures and two seated figures of philosophers or poets are especially admirable.

*Hierapolis*

NOWHERE, even at Ephesus, is the impact of developing tourism in Turkey more striking than at Hierapolis. When the present writer first went to Pamukkale in 1939 the white cliffs, the ancient buildings and the tombs stood deserted, and the sacred pool lay inviting the occasional visitor to a free and solitary bathe. The scene is very different now. The solitude is gone; the pool has become an adjunct of the Pamukkale Motel, surrounded by cabins and filled daily with bathers from Denizli and elsewhere; several other motels stand near the cliffs, full to capacity in the season; and the wall of the ancient baths is lined with the booths of the post-card and souvenir-sellers. And to increase the change excavations have lately begun and are continuing. Whether all this is an improvement or not is a matter of opinion, but Hierapolis can never lose her attraction, and the excavations at least have already added greatly to the interest of the site.

When the writer's party in 1939 proposed to pitch a tent for the night, an unexpected difficulty arose; it was almost impossible to drive the pegs into the ground. In fact the level plateau on which the city stands is not earth at all, nor even rock, but a solid calcareous mass deposited in the course of ages by the lime-charged springs and streams of the region. The process still continues, and in the last two thousand years has buried the lower parts of many ancient buildings to a depth of several feet in solid stone. The spring which feeds the sacred pool has not been located, but lay presumably somewhere up the slope towards the theatre. When the water emerges from the ground it has a temperature a little below blood-heat, making the pool comfortable for bathing; by the time it reaches the plain it has lost nearly all its heat and is freely used for drinking

and for watering the fields. From the pool it issues in numerous rills, mostly a foot or so wide; these as they go deposit their lime, which gradually forms a rim on either side, so that the water runs in a self-built limestone channel. Some are still flowing; many others, abandoned in the course of time, are now dry. When they reach and fall over the edge of the plateau the




FIG. 42 Map of the Environs of Denizli

lime deposit forms a shallow basin; trickling over the rim of this the water makes another basin below, then another and another, in many cases leaving clusters of stalactities, so that the whole cliff appears like a vast petrified cascade, slowly changing its appearance from year to year (Pl. 71). Assuming that the rate of deposit has been fairly consistent, it has been calculated that the whole mass of the plateau may have taken

something like 14,000 years to accumulate. The most striking of the self-built channels runs along the length of the main street, resembling a wall rising 6 or 7 feet above the level of the ancient road.

The sacred pool is so called, though its sacred character is really only an assumption, based on apparent probability and the number of ancient stones lying in it. These include a long foundation and numerous column-drums and other carved blocks. The foundation shows the ground-level in Roman times, for the pool has of course changed its shape and appearance since antiquity. The spring which feeds it seems to have borne the appropriate name of *Thermodon*.

Hierapolis means *Holy City*; *Stephanus of Byzantium* says she is so named from the many temples she possessed; and in fact, down to the time of *Augustus*, the name appears officially on the coins as *Hieropolis*, 'Templeville'. It has been ingeniously suggested that this was not the original meaning; since the city is a *Pergamene* foundation, and the kings of *Pergamum* (like all *Hellenistic* kings) normally gave to their new foundations names commemorating members of their families, it is more likely that *Hierapolis* was named after *Hiera*, or *Hiero*, wife of *Telephus*, the mythical ancestor of the *Pergamenes*. The name was not, however, generally so understood in later times, when we often find the two parts separately declined as adjective and noun. How many temples the city really possessed we cannot tell; certainly a great variety of deities was worshipped there, but these had not all temples. Actually, the only priests mentioned in the inscriptions are those of *Cybele* and the *Emperors*; and on the site one temple only has been identified, namely the temple of *Apollo* recently excavated.

The *Pergamene* foundation of *Hierapolis* is not in fact anywhere recorded, but may nevertheless be confidently accepted. In the third century B.C. the *Lycus* valley belonged to the *Seleucid* kings of *Syria*, who founded in it about the middle of the century the city of *Laodiceia*. It is plainly improbable that they would found a second city in such close proximity. After the battle of *Magnesia* in 190 B.C. this region passed to the kingdom of *Pergamum*, and the earliest inscription of *Hierapolis* is a decree in honour of *Apollonis*, mother of *Eumenes II*, passed

on her death some time after 183. In all probability therefore the city was founded by Eumenes in the first quarter of the second century.

Whether, and if so in what form, the site was previously occupied is not known, but it is evidently unlikely that so remarkable a place would be left neglected. Herodotus mentions a town of Cydrara in this neighbourhood, and later we find a city of Hydrela; the latter name, a synonym of Denizli, 'watery', suggests this region of many waters. Hydrela survived into Roman times; Cydrara, on the other hand, disappeared at an early date.

The city's subsequent history is almost a blank. It was included in the province of Asia in 129 B.C., after which time recorded events are practically confined to a succession of earthquakes. At least four of these occurred in the two centuries between Claudius and Alexander Severus; the worst was apparently that under Nero in A.D. 60, and it was probably after this that with help from the Emperor the city was rebuilt in its present form. It is thought that the city-centre, whether at that or some other time, was shifted a short distance southwards; the chief evidence for this is the scanty traces of an earlier theatre in a hollow in the hillside to the east of the northern city-entrance. There is, however, no reason why the theatre should not be situated outside the city wall, as it was, for example, at Mylasa and Perge in Pamphylia.

The highly prized title of Neocorus was awarded apparently by Caracalla. Otherwise nothing more stirring appears to have occurred than an occasional visit from the Emperor. Hadrian was probably there in A.D. 129, and Caracalla in 215, and a visit by Valens in 370 is actually recorded. There was a separate colony of Jews at Hierapolis, to some extent self-organising, and Christianity, as at Laodiceia and Colossae, was early introduced. The apostle Philip lived there with his daughter at the end of his life, and his tomb was shown to visitors; it is so again now, having been recently uncovered by the Italian excavators.¹ The bishop of Hierapolis was promoted to the rank of metropolitan by Justinian in the sixth century.

The names of the citizens, as they appear in the inscriptions,

¹ See below, pp. 243-5.

are almost exclusively Greek or Roman, and the city constitution was the normal Greek, though the tribes appear to have had Phrygian names. The religion, on the other hand, had a strong admixture of the Anatolian. Most of the familiar Greek deities were worshipped, but in numerous cases they were merged with earlier local gods. The patron deity was Apollo, identified with the Phrygian *Lairbenus*, a sun-god whose sanctuary lay some twenty miles to the north-east of Hierapolis. Similarly *Leto*, mother of Apollo, was assimilated to the Anatolian mother-goddess *Cybele*. Zeus also had at Hierapolis the non-Greek epithets *Bozius* and *Troijs*, and the strange Ephesian *Artemis* had her worshippers too. Coins show the moon-god *Men*, a wholly Anatolian deity. Of the purely Greek gods, the cults of *Poseidon* the Earth-Shaker and *Pluto*, lord of the underworld, are naturally explained by the physical features of the country.

It was indeed this last that gave Hierapolis its chief claim to fame in antiquity, namely the *Plutonium*. This remarkable phenomenon is described by several ancient authors. Strabo, writing as an eyewitness, says:

The *Plutonium* is an orifice under a slight ridge of the hill which rises above, large enough to admit a man, and very deep. In front of it is a fenced enclosure some 50 feet square, filled with a thick mist, so that the floor is barely visible. Outside the enclosure the air is free of the mist, so long as no wind is blowing, and a man may approach safely; but for any living creature which enters inside death is instantaneous. Bulls, for example, which are taken in collapse and are brought out dead; we ourselves sent in small birds which at once fell lifeless. The eunuchs of *Cybele*, however, are immune to the extent that they can approach the orifice and look in, and even penetrate for some distance, though not normally without holding their breath.

The historian *Dio Cassius* visited the spot in the second century, and observes similarly that the vapour destroys all living creatures except the eunuchs; 'I tested it', he says, 'by means of birds, and I bent over and saw the vapour; it is enclosed in a sort of cistern, and an auditorium had been built over it'.

Later, in the fifth century, a visit by the physician Asclepiodotus is reported; he took the precaution of wrapping his cloak two or three times round his face, so as to breathe the pure air he took in with him, and was able to follow the course of the hot water for most of the way in, but could not reach the end because the ground was cut away by a stream of water too deep for a man to pass. The orifice is described as lying under the temple of Apollo.

The rediscovery of this remarkable phenomenon is no doubt the most striking result of the Italian excavations. The temple of Apollo had become almost completely buried; on clearing its south side the Plutonium came to light, corresponding in all essentials to the ancient accounts. There is, as Strabo says, a small shelf in the hillside, on which the rear part of the temple rests; in this shelf, at the foot of the temple on the right, is a dark chamber some 9 feet square, with a paved floor; at the back a gap 3 feet wide shows the natural rock split by a deep cleft in which is a fast-flowing stream permeated with a strong-smelling gas. The chamber is entered by an arched doorway (Pl. 75) from which three steps lead down. The door has been partially blocked by the excavators for security reasons, and the visitor may hear but not see the rushing water. In front is a rectangular courtyard; in the floor of this, and in many other places, are cracks from which the gas emerges; it has a very strong sharp smell, which catches the throat and brings tears to the eyes. A single good sniff incapacitates for some minutes, though it does not kill; however, whether by coincidence or otherwise, the writer remembers on a recent visit seeing a dead sparrow lying in the courtyard.¹

From the ancient accounts related above it appears that the Plutonium underwent a number of changes. Strabo makes no mention of a temple, and it seems clear from his words that none existed in his time, only the opening in the hillside with

¹ On a further visit in 1970 the writer was shocked to find not only that a placard had been erected absurdly labelling the place the Pit of Evil Spirits, but much worse, that the court was strewn with the rotting and malodorous corpses of a dog, a cat and other small creatures, presumably placed there to illustrate the lethal properties of the place. The stench was horrible. Who was responsible for this repulsive idea the writer cannot say, but it can hardly be expected to be tolerated for long.

an enclosure in front. How this came to be filled with mist is not clear; no such effect is noticeable today, nor is this peculiarity mentioned in the later accounts. By the second century the place had evidently been converted into a regular tourist attraction, with provision for spectators. Finally, after the temple was built, the place was given the form which it has today.

As in all cities of any size, periodical festivals with athletic and musical contests were celebrated at Hierapolis. In Imperial times we find Olympic, Pythian and Actian games, modelled on and given nominal equality with the famous festivals in Greece; we hear also of another festival called by the unusual name of 'the games by the Chrysorrhoeas'. This stream, 'flowing with gold', is identified with the torrent on the north side of the city beyond the necropolis; that it ever really bore gold is uncertain, but is considered not impossible. The curious thing is that no sign of any stadium has ever been seen at Hierapolis, though there must evidently have been one; since there seems no place for it on the plateau, it presumably lay down below on the plain. Gladiatorial and wild-beast shows were given in the theatre, as is indicated by reliefs found there.

But Hierapolis was not merely a resort for tourists and theatregoers. Most of her prosperity came from her industries, which were unusually numerous and varied. Commercial companies recorded in inscriptions include not only guilds associated with the woollen industry, such as dyers, purple-dyers, wool-washers and carpet-weavers, but also nail-makers and coppersmiths. These were organised companies, and were often entrusted with the upkeep of their members' tombs. Exports included also a special kind of marble peculiar to Hierapolis; its nature and varied colouring were due, it was said, to the hot water entering the quarries and permeating the stone. Oddly enough, with one possible exception, this stone does not seem to have been used for the buildings of the city itself.

Among the distinguished citizens of Hierapolis the best known is the sophist Antipater, who was chosen by the Emperor Septimius Severus to educate his sons, the future Emperors Caracalla and Geta. His family tomb stands in the northern necropolis, though his own grave has not been identified.

The city as it stands today is wholly of the Roman period. It has been thought that it represents a more or less complete rebuilding after an earthquake, possibly that of A.D. 60, with financial help from the Emperor. However this may be, nothing remains of the original Hellenistic city. Even the city wall




FIG. 43 Plan of Hierapolis

is no exception; in respect of height, strength and quality of masonry it is unimpressive. Under the *pax Romana* powerful fortifications were not called for, and the Holy City was protected by its sanctity; it is suggested that the wall was built rather against marauders than against enemies.

The backbone of the city is formed by a street over a mile long running dead straight from end to end; only the northern part is at all well preserved. At either end, north and south, this street was prolonged outside the city wall for some 170 yards to a monumental gateway; that on the north is in good

condition. It consists of a triple arch flanked by two round towers (Pl. 74), and is shown by its inscription, of which fragments have been found, to have been dedicated to Domitian in A.D. 84-85. Just inside the gate on the east is a small Byzantine chapel with the base of the altar remaining in the apse; and close beside the gate on the west the excavators have cleared and restored the handsome tomb of a certain Flavius Zeuxis, a merchant who, as the inscription records, had made seventy-two voyages round Cape Malea to Italy. Between the gate and the city wall the street is flanked by private houses, some of which have been recently excavated. The corresponding monumental gateway at the south end of the street is now mostly destroyed.

The newly discovered temple of Apollo lies on the sloping ground between the sacred pool and the theatre. It faces south-west and is approached by a broad flight of steps. The front part stands on a podium 7 feet high, the rear part on the natural rock. The temple itself is unusually short in relation to its width, measuring some 60 by 45 feet; it comprises a *pronaos* and a *cella* which is actually broader than it is long. There was originally a row of unfluted columns in front, probably six in number. The excavation was much hindered by the exhalations of gas; this inconvenience was remedied in antiquity in an interesting way. The blocks of the substructure were so placed as to leave gaps two inches wide between them, thus allowing the gas to escape at the side of the temple. This arrangement is especially evident on the left flank of the podium.

Below the temple on the right is the grotto of the Plutonium described above. It is integrally connected with the temple by a pavement running over the grotto; on this pavement are lying four blocks forming part of a circular base whose purpose has not been explained. The back of the temple is divided by a narrow space from a flight of steps belonging to another building which at the time of writing has not been excavated.

As it stands the temple is not earlier than the third century A.D., and is largely constructed of reused material; much of this is likely to have come from an earlier building on the spot. When a temple was first erected here is uncertain; as was mentioned above, there seems to have been none in Strabo's day.

Among the reused blocks are several bearing inscriptions; these include a letter-oracle of the familiar type,¹ and at the north corner of the cella a long text recording an oracle rendered on the occasion of a pestilence affecting Hierapolis and many other cities. This was probably the appalling plague which afflicted the whole of the Empire during the reign of Marcus Aurelius in the second century. The god recommends, as usual, sacrifices to various deities, with especial attention to Apollo of Claros and Apollo Careius, and adds, rather surprisingly 'for you are sprung from me and from Mopsus the protector of your city'. Mopsus the seer was at home at Claros in the distant past after the Trojan War, and so remote an ancestry for a city founded in the middle Hellenistic age may savour of exaggeration; at the same time, Mopsus appears on coins of Hierapolis, where he is associated with another legendary figure, Torrhebus, son of Atys. Torrhebus was also, we are told, the name of a city in Lydia, and on her territory was a mountain with a sanctuary of Carius—clearly the same as Careius. The hero Torrhebus, wandering one day by a lake, heard the voices of the Muses and from them learnt music, which he afterwards taught to the Lydians. The lake is identified with the lake of Gölcük just below the main summit of Mt. Tmolus above Sardis, some seventy miles north-west of Hierapolis. Evidently then, the Hierapolitans had invented for themselves a legendary origin involving Mopsus and Apollo Clarius, Torrhebus and Apollo Careius. Since the coins in question are dated about the middle of the second century A.D., it is likely that they were issued in consequence of this same oracle. On the other hand, it is remarkable that among the hundreds of delegations to the oracle of Claros recorded from Imperial times not a single one is from Hierapolis.

A short distance to the north of the temple is the nymphaeum. This is a solid building with a back wall and two side walls enclosing a water-basin approached from the front by a flight of steps. A broad ledge runs all round the interior; below the ledge are five semicircular recesses in the wall, three at the back and one on each side, and above each recess is a rectangular niche originally crowned by a pediment. In the middle

¹ See *Turkey's Southern Shore*, pp. 172-5.

niche at the back is a pipe-hole by which the water was admitted. It is likely that the water came, not from the hot spring, but from a reservoir on the hill outside the city wall on the east. The whole building was richly decorated, and many handsome architectural pieces have been excavated.

Further up the hillside is the theatre, large and well preserved, with a frontage of over 300 feet. The cavea is in exceptionally good condition, with about fifty rows of seats and eight stairways dividing them into seven sections; there is a single diazoma, to which a vaulted passage, or vomitorium, leads on each side. The number of stairways is not doubled above the diazoma, as was often done. In the middle of the cavea is a semicircular 'Royal Box', and the orchestra is surrounded by a six-foot wall. The stage-building, long and narrow, is standing in large part, but the decoration of the stage-wall has collapsed into the orchestra; at the time of writing good progress has been made by the excavators in clearing the vast mass of material which had buried the lower parts of the building and the orchestra itself. The stage is about 12 feet high, with round niches in its front wall; in its back wall—that is the front wall of the stage-building—are the usual five doors, with arched windows high above them. This wall, the back of the stage, was originally adorned with three superposed rows of columns, the lowest row unfluted on octagonal bases, and further decorated by statues and by friezes representing mythological scenes. In these Dionysus is as usual prominent; one scene shows his birth, with his mother Semele reclining on a couch attended by servants, one of whom is washing the infant with water issuing from a rock-face; others show the god himself riding in his car and accompanied by Maenads; in one case (Pl. 73) the car is drawn by horses, but in another by the more usual leopards. Another block carries the interesting scene—not yet, to the writer's knowledge, explained—which is shown in Fig. 44.

Although the cavea is slightly more than a semicircle, the building is of Roman type, not a converted Greek theatre; the earlier theatre lay much farther to the north. Fragments have been found of a long inscription recording the dedication by a rich citizen of the stage-building (or a part of it) to Apollo and

the Emperors, 'with the help of his own farm-hands'. The date is apparently the latter half of the second century A.D. Another block lying in the orchestra refers to a gift by a lady of 600 feet of something unspecified. And in the wall of the diazoma, at the middle point, is a metrical inscription greeting the city of



FIG. 44 Hierapolis. Relief in the Theatre

Hierapolis as 'foremost land of broad Asia, mistress of nymphs, adorned with streams of water and all beauty'.

Somewhere in the southern part of the city the agora is presumed to have lain, but owing chiefly to the thick deposit of lime its exact position has not been determined.

One of the most striking of the Italian excavators' discoveries is that of the Martyrium of St. Philip, who, as was mentioned above, ended his life at Hierapolis. A simplified plan of the building is shown in Fig. 45. From the central octagonal chamber six rectangular rooms open off, and the whole is surrounded by a row of smaller rectangular chambers entered




FIG. 45 Hierapolis. Plan of the Martyrium of St. Philip

from outside. A broad stairway leads up from the south-east. In the middle of each side a door leads through to the central chamber, at the back of which is the semicircular synthronus.¹ No altar has been found, but in the floor of the synthronus is a round hole which is supposed to have held a lectern. The building is not a church, but was used for commemorative services and the recital of panegyrics on the saint's feast-day. The small outer chambers served no doubt to accommodate the pilgrims (or some of them) who assembled on the festal occasion. The

¹ Normally an apsidal recess with rows of seats for the bishop and presbyters.

martyrium would be expected to contain the saint's tomb, but this has not been discovered. Erected early in the fifth century, the building had a short life and was destroyed little more than a hundred years later.

The necropolis is one of the most extensive in Asia Minor. Not fewer than 1,200 tombs have been counted, and over 300 epitaphs have been read and published. The two principal groups are on the slope outside the wall on the east and lining the street beyond the city gates on the north. In the latter case especially the tombs are closely packed, jostling one another in the most picturesque confusion; a walk along this street on a moonlight night is an experience to be remembered. The epitaphs, however, recall a time when there was less congestion; many of them refer to a garden or other area around the tomb; one insists that the tomb shall not be overshadowed, another that the approach shall be kept clear even if the adjoining ground is occupied. A feature peculiar to Hierapolis is the so-called *stephanoticum*, a sum of money left in charge of some official body, often one of the guilds, the interest to be used for laying a wreath on the tomb each year on a specified day. In one case a Jew requires that this shall be done on the feasts of Unleavened Bread and Pentecost. The sum so bequeathed varies greatly, from 150 to 2,500 denarii. Most epitaphs provide for a heavy fine for violation of the prescribed conditions, and one adds a comprehensive curse:

may he who commits transgression, and he who incites thereto, have no joy of life or children, may he find no land to tread nor sea to sail, but childless and destitute, crippled by every form of affliction let him perish, and after death may he meet the wrath and vengeance of the gods below. And the same curses on those who fail to prosecute him.

Many of the tombs consist of a solid base or substructure on which were set one or more sarcophagi; others are larger and more impressive, but the most interesting are perhaps the tumulus-tombs, which have been recently cleared and restored by the excavators. These are among the earliest at Hierapolis, and may well be of Hellenistic date. Like the vastly larger tumuli at Sardis, they comprise a circular wall at the base,

with a cone of earth above, surmounted by a phallus-stone or other 'prophylactic emblem'. In the centre is the vaulted funeral chamber, equipped normally with stone benches for the dead body. Some of the tumuli are entered by a door in the circular wall and a short flight of steps down to the door of the inner chamber; others, however, have no entrance in the outer wall, so that either it was not envisaged that the tomb would be opened again after the original burial, or, if it were, access to the door of the chamber must have been gained by digging through the cone of earth.

*Laodiceia and Colossae*

BY COMPARISON with Hierapolis the ruins of her neighbour Laodiceia are somewhat unspectacular. Among the crowds of summer visitors to Pamukkale not one in a hundred makes his way to Laodiceia; yet the site is not without interest, though apart from a small excavation, restricted to the nymphaeum, it remains untouched.

Like Stratoniceia, Laodiceia was a foundation of a Hellenistic king, though there is some doubt as to which king. One tradition said that Antiochus I, king of Syria, saw in a dream three women, in whom he recognised his mother, wife and sister, each desiring him to found a city in Caria; he therefore founded three, one of which he named after his sister Laodice. The other two were Nysa and Antiocheia. This sister, however, is not otherwise known to have existed, and most scholars prefer the alternative account by which the foundation was made by Antiochus II in honour of his wife Laodice. He acted, it was said, in accordance with the command of Zeus transmitted by an oracle of Apollo. In this case the foundation must date between 261 B.C., when his reign began, and 253, when he divorced Laodice. It is further recorded, on somewhat dubious authority, that the site was previously occupied by a village called at first Diospolis, then Rhoas. The former name, City of Zeus, may in fact preserve the memory of an earlier sanctuary on the site, for Zeus was the principal deity of Laodiceia.

The site was well chosen, at the junction of the great route up the Maeander valley and the road to the south-east to Pisidia and the coast, in a region, moreover, exceptionally well watered; the Lycus, a considerable tributary of the Maeander, is little over a mile distant, and the two streams, the Asopus and the Caprus, which pass close on either side of the city,

maintain a flow of water throughout the year. Only in such a desirable neighbourhood could three cities, Hierapolis, Laodiceia and Colossae, support themselves so close together. There was, however, one ever-present disadvantage; this country lies in an earthquake belt, and disasters from this cause were frequent.

For the first two centuries of her existence Laodiceia has little individual history; not until the first century B.C. did she acquire any considerable importance. By the treaty of Apamea in 188 the whole of this region was attached to the kingdom of Pergamum, and in 129 was included in the province of Asia. In the first Mithridatic War (88-85) Laodiceia was among the comparatively few who resisted the king and was besieged; the defence was conducted by the Roman commander Quintus Oppius, who had retired thither with an assortment of troops, and the city was eventually relieved, though not without suffering serious damage.

In 50 B.C. Cicero, as governor of Asia, resided at Laodiceia for ten weeks conducting judicial business; for the city was at that time the capital of the *conventus* of Cibra. Ten years later Labienus arrived at the head of his Parthian troops. Most cities submitted quietly to him, but at Laodiceia an influential citizen by name Zeno persuaded his countrymen to resist. What happened is not known, but his courageous action was rewarded soon after by Mark Antony, who appointed his son Polemo to the kingship of an extensive area in the south, and later also of Pontus on the Black Sea coast. On other Laodiceans Antony conferred the great privilege of Roman citizenship; it was usual, when this was done, for the recipient to add to his own name the name of his benefactor, producing an awkward mixture of Greek (or Anatolian) and Roman; at Laodiceia names such as Marcus Antonius Zeno are frequent, for the privilege extended to the man's descendants in perpetuity.

It is no surprise to learn that there was in the city at this time a flourishing colony of Jews. Their freedom of worship was guaranteed by the city authorities, but even so they were not entirely free from victimisation. It was their habit to collect every year a sum in gold to be forwarded to Jerusalem; in

62 B.C. the Roman governor issued a veto and the money was confiscated to the public treasury.

In A.D. 26 Laodiceia was among the cities of Asia who competed for the honour of erecting a temple to the Emperor Tiberius, but was turned down as lacking sufficient resources; the privilege was awarded to Smyrna. This apparent poverty was only comparative; at least, when in A.D. 60 the city was badly damaged by an earthquake, it was able to recover without help from the Emperor.

But the time of greatest prosperity for Laodiceia came towards the end of the second century, and it was then, under the Emperor Commodus, that she at last received the coveted title of *neocorus*, 'Temple-Warden'. This was granted, no doubt, in respect of a temple of Commodus in the city. As is well known, when an emperor died he was, by decree of the Senate, either deified or condemned to oblivion; in the latter case his name was ordered to be erased from all public monuments throughout the Empire. This was Commodus' fate on his death in 192 (though the decision was reversed a few years later), and Laodiceia was deprived of her title of Temple-Warden; in a recently discovered inscription the word *neocorus* has been erased and the more banal epithet 'Emperor-loving' substituted. The precious title was, however, given back some time later by Caracalla, and Laodiceia became 'Temple-Warden of Commodus and Caracalla'.

Coins and inscriptions of Laodiceia reveal the existence of numerous cults of the familiar Greek gods. Among these Zeus holds the first place. He was worshipped under two titles, Laodicean Zeus and Zeus Aseis. This latter epithet is unique and its meaning uncertain; it has been compared with the Arabic *aziz* ('powerful', later used to translate 'saint') and supposed to indicate a Syrian element in the population introduced at the time of the city's foundation by a king of Syria. Another non-Greek deity was the Anatolian moon-god Men, whose cult was widespread in Asia Minor. Cults of the deified Rome and the Emperors were normal; less usual is the mention of a priest of the City, that is of the personified Laodiceia. Apollo occurs principally in connexion with the oracle at Claros in Ionia; the recent excavations on that site have revealed

hundreds of records of delegations sent year after year by a great variety of cities to consult the god and sing hymns in his honour, and Laodiceia is among the most faithful clients. Her delegation was regularly headed by the prophet of Pythian Apollo; he was, surprisingly, always a boy or youth, and was accompanied by his father (orphans were not eligible) who made the actual consultation of the oracle, while the son joined in the hymns. His title of prophet does not imply an oracle of Pythian Apollo at Laodiceia itself; his function was rather to report the oracles of Clarian Apollo.

Christianity was introduced in this region during the lifetime of St. Paul by his companion Epaphras of Colossae; in the Epistle to the Colossians more than one reference is made to Laodiceia, where no doubt the acceptance of the new faith was assisted by the presence of a Jewish colony. In Revelation Laodiceia is one of the Seven Cities of Asia; from the letter addressed to her it appears that the wealth of the citizens had led to a lukewarm attitude towards the new religion: 'I know thy ways, thou art neither hot nor cold; therefore will I spew thee from my mouth'. The city was nevertheless the seat of a bishopric, and in the fourth century was the scene of an important Ecumenical Council. Its prosperity continued into the fifth century, but was shattered by a devastating earthquake in 494; although the city existed until the Turkish conquest in the fifteenth century, it seems never to have really recovered from this disaster.


Among the products of Laodiceia one is outstanding—her wool. This was reckoned softer even than that of Miletus, and was remarkable for its raven-black colour, attributed by Vitruvius to the water which the sheep drank.

The ruins stand on and around a flat-topped hill between the villages of Eskihişar and Göncah, six miles south of Hierapolis and ten miles west-north-west of Colossae. They may be reached by a road turning off the road to Pamukkale just after it branches from the Uşak highway, close beside the Arı Tuğla-Kiremit factory, or from the other end of the same road at the village of Korucuk. A ring-wall, of which some traces remain on the east side, was carried round the rim of the plateau, enclosing an area of about a square kilometre; the hill was

accordingly not merely an acropolis, but contained the whole city. There were three gates in the wall, on the north-west, north and east. Of the northern gate little survives, but the eastern gate is better preserved. It was called the 'Syrian Gate'. The road leading out from it was lined in the usual fashion by tombs, among which was that of the sophist Polemo; it is said that he was buried in it, by his own wish, while still alive; as the door was being closed, 'Make fast, make fast', cried the dying man; 'let the sun never see me reduced to silence'. This was not the Polemo mentioned above, but a later member of the same family. He was a rich and proud man, who habitually travelled in a chariot with silver reins, and is said to have spoken to cities as a superior, to kings as by no means an inferior, and to gods as an equal. He had a house in Smyrna, and on one occasion Antoninus, then governor of Asia and afterwards Emperor, chose it as his residence while its owner was away. Polemo, unaware of this, returned late one night and was highly indignant at being excluded from his own home; without more ado he turned the governor out to find lodging elsewhere. Antoninus remembered this and later when as Emperor he received Polemo in Rome, he embraced him and said, 'Find Polemo a lodging—and see that nobody turns him out'. Antoninus Pius was of course one of the 'good Emperors'.

On the opposite side of the city is the Ephesian Gate—so called, though the name is not ancient. It had the familiar form of a triple arch flanked by towers and was dedicated to Domitian (A.D. 81–96). Fellows in 1838 saw remains of a paved road leading from the gate to a bridge of Roman construction crossing the Asopus; this bridge still survives in part. Here too the road is lined with sarcophagi.

At the southern end of the plateau is the stadium, running north-west and south-east. It was dedicated to Vespasian in A.D. 79 by a rich citizen, the ceremony of consecration being performed by the then proconsul of Asia, the father of the future Emperor Trajan. The building is remarkable for its exceptional length of some 380 yards, or twice the length of the stadium foot-race; as at Aphrodisias, both ends are curved. These features are explained by the name 'amphitheatral stadium' which is given to the building in the inscriptions; that



- A - 'Ephesus Gate'
 B - 'Hierapolis Gate'
 C - Syrian Gate
 D - Stadium
 E - Gymnasium?
 F - Aqueduct

- G - Odeum or
 Council-House
 H - Nymphaeum
 J - Large Theatre
 K - Smaller Theatre
 L - Ionic Temple

- M, N - Unidentified
 Buildings
 P - Bridge
 Q - Sarcophagi
 R - Clearing-Basin
 S - Water-Tower

FIG. 46 Plan of Laodiceia

is, it was intended not only for the athletic contests conducted in a normal stadium, but also for the gladiatorial shows for which amphitheatres were designed. Cicero in 50 B.C. refers to these performances at Laodiceia. The present state of preservation is not more than fair; several rows of seats are visible on either side.

Close against the eastern end of the stadium are the solid remains of a large building which has been variously supposed to be a gymnasium or baths. The fragmentary dedication to the Emperor Hadrian and his wife Sabina records that certain persons (probably the city authorities) consecrated the —, then tantalisingly breaks off. Since the building has not the normal form of a gymnasium, the alternative identification is probably to be preferred. This is to some extent confirmed by the presence of a water-tower at its southern corner, still standing some 16 feet high; its eastern side is now broken away, revealing a number of water-pipes running vertically up its core (Pl. 76). But this tower did not only supply the adjoining building; it furnished water to other parts of the city, notably the *nymphaeum*. The water came by an aqueduct from the south, of which more will be said below. At the west foot of the tower stands an unfluted column, which is all that remains of a fountain-house constructed about the same time as the stadium by a certain *Hedychrous*.

Some 100 yards to the north, at G on the plan, is a small theatre-like building with five or six rows of seats visible; this has been hesitantly identified as an odeum, but is perhaps more likely a council-chamber.¹ It has not been excavated, and in its present condition is unimpressive.

The city possessed two theatres, in the north-eastern slope of the plateau; both are above average size. The larger, J, faces north-east; most of its seats are preserved, though somewhat disarranged. The front wall of the Roman stage is visible, with a large shallow niche in the middle; this building would probably be interesting if it were excavated. The smaller theatre faces north-west. The upper part of the *cavea* is well preserved,

¹ It is often difficult to distinguish between an odeum and a council-house. The form of the building is equally appropriate for both purposes, and it is probable that in practice it served, like the theatre, for both.

with many rows of seats virtually complete; but the lower part is badly ruined and is now featureless.

Nearly in the centre of the plateau, at H, is the nymphaeum which was excavated in 1961-63 by a team of French archaeologists. It was built not before the early third century A.D.,




FIG. 47 Laodiceia. Plan of the Nymphaeum

and was reconstructed three or four times. Its original form is shown in the accompanying plan, Fig. 47; it is distinctive and unusual. The main feature is a square water-basin, A, with a colonnade on two sides; two semicircular fountains, B and C, adjoin it on the east and south. All these were fed from the chambers D and E, which in turn were supplied from the water-tower by the stadium. The whole was richly decorated and contained a number of statues; a full-size figure of Isis was found by the excavators and removed, and the inscribed base of the

statue of a consular benefactor Anicius Asper remains in the building. At a much later date the whole structure was radically altered. The basin A was abolished and converted into a closed chamber, with a raised floor approached by a flight of four steps from the road which passed the building on the north. This chamber was used for some Christian purpose. The smaller basins B and C continued in use as fountains, but the semicircular recesses were walled off and rectangular troughs installed in front of them. The chamber E was at this time attached to a house adjoining on the south. In consequence of these changes the present appearance of the ruins is rather confused.

Of the other public buildings on the plateau most have now quite disappeared. At L an Ionic temple has been identified, but of this and the neighbouring buildings M and N nothing is now to be made out. An inscription records a Strategium, or hall for the generals, in the third century B.C.; the commissioners responsible for its construction are praised for ensuring that the architect and artisans should not make a high profit. The work was evidently let out, in the usual ancient fashion, under a contract for the whole job.

Among the most interesting things at Laodiceia is certainly the aqueduct which carried water to the tower by the east end of the stadium. It was fed from the abundant spring, now called Başpınar, in the upper part of the present town of Denizli, one of the sources of the Başlı Çay (ancient Caprus). From the spring it descended to the neighbourhood of the railway station, then in the form of a covered channel, partly cut in the rock, over the intervening hills to a clearing-basin (R on the plan) on the hill opposite to the city. Up to this point the water flowed under the force of gravity: but from here it was carried, in a piped channel, under pressure across the hollow and up to the water-tower. The total length is thus about five miles, with a fall of some 350 feet.

Visitors who are not too pressed for time may find it of interest to follow the line of this aqueduct at least for some distance. To a spectator looking south from the water-tower a line of stones is clearly visible running up the hill opposite; this is the aqueduct, and makes a convenient mark to aim for. In

the dip below the tower, on either side of the railway, the course of the pipe-line is marked by a row of blocks, at first a single, then a double, row; the blocks are roughly cubical, with a side of 2 to 3 feet, and pierced through the middle. Many of them have also a funnel-shaped hole in the upper surface, reaching through to the pipe-hole in the middle; in the ordinary course of events these holes were plugged with round stones. But the water at Laodiceia, like that at Hierapolis, is heavily charged with lime; many of the blocks are quite thickly coated, and in a few cases the channel is completely blocked. When the flow was thus cut off, the funnel-shaped holes would enable the stoppage to be located; it was only necessary to remove the plug to discover whether the channel was dry at any point.

Some 200 yards to the south of the railway line, at the top of the conspicuous line of blocks at R, is a clearing-basin where the pressure begins. It is almost entirely destroyed, but apparently consisted of two chambers, a large and a small. This point is about 100 feet higher than the base of the water-tower and 160 feet above the floor of the intervening dip.

Between R and the next shoulder is a hollow; this was spanned by a built aqueduct some 450 feet long, some of whose arches are standing near the middle to a height of 10 feet or more. On the far (south) side of the next rise is a mass of fallen blocks belonging to another aqueduct which has completely collapsed. Round the next corner the channel is very clearly visible; in one place it is cut in the rock, with several of the covering-stones still in place. Over all this length, as far as R, there is a steady fall of approximately 1 in 170. The channel continues to be easily traceable all the way to the plain of Denizli.

The date of this interesting structure has not been determined. It has been urged that since a supply of water was essential at all times the aqueduct must have existed almost as soon as the city; but with so much river-water available this argument loses most of its force.¹ The small built aqueducts, to judge from the quality of the masonry, can hardly be earlier than the second century A.D. They may of course be part of a

¹ Strabo observes that the rivers here, though causing petrification, are perfectly drinkable, and the writer's experience confirms this.

later reconstruction, and the rest of the channel is really undatable; but as it stands the aqueduct appears as a work of the Roman Imperial period.

COLOSSAE

The third city of the Lycus valley, Colossae, had a very different history from the other two. She is first heard of in 480 B.C., when Xerxes passed through on his march across Asia Minor; Herodotus calls her 'a great city of Phrygia'. A similar judgment is given by Xenophon in relating the march of Cyrus in 401; he speaks of a large and flourishing population. But the foundation of Laodiceia in the third century was fatal to the prosperity of her neighbour; Strabo in the time of Augustus refers to Colossae as a minor city (*polisma*), and under the Empire, apart from her trade in wool, little or nothing is heard of her. Pliny's description of her as 'among the most famous towns of Phrygia' relates evidently to a much earlier period. The coinage is somewhat scanty and almost entirely of Imperial date. What the city was like in the fifth century B.C. we do not know, nor how it was governed; a king or tyrant is no doubt the most likely. In the later inscriptions, all of Roman date, it appears with a normal Greek constitution.

Christianity was early established in the city by St. Paul's companion Epaphras, himself a native of Colossae, and the Epistle to the Colossians gives abundant evidence of the apostle's interest in the newly-founded church. But by about 800 the city was in complete decay and was replaced by the new town of Chonae, the modern Honaz, a few miles higher up to the south. So completely was the old name forgotten that the idea arose that the Colossians addressed by St. Paul were the Rhodians, so called from their famous colossus. In the Byzantine lists the bishop is regularly recorded as of Chonae, not of Colossae.

Despite its resemblance to the Greek word *kolossos*, meaning an over-life-size statue, the name Colossae is unquestionably Anatolian. The word *kolossos* itself, as its termination indicates, was taken over by the Greeks from a pre-Greek language. At the same time, the city-name appears often in late sources in

the form Colassae, and it has been suggested that this may in fact be nearer to the original Phrygian name.

The site is fixed on the left (south) bank of the Lycus some three miles north of Honaz. Herodotus says that the river disappears underground at Colossae and reappears five stades (rather over half a mile) lower down before going on to join the Maeander. In reality the city stands at the head of a narrow gorge over two miles long, but there is no indication that the river ever flowed underground at this point. Strabo says that the Lycus runs underground for much of its course; and this is indeed true, but it does so above Colossae, not below it. Herodotus' statement is a characteristic example of his imperfect understanding of oral information imparted to him; he was told of the gorge and of the river's subterranean course, and combined the two to make the river run underground in the gorge.¹

The site itself is accessible from Honaz by a road just, but only just, passable for a car. The acropolis is on a hill some 150 or 200 feet high on the north and west, but lower on the other sides; the summit is now a ploughed field. It was surrounded by a ring-wall, of which some remnants, in very poor condition, stand on the east side; many other blocks lie strewn down the slopes. The Lycus flows a short distance to the north, and the view over the valley is very fine. Towards the west end of the flat summit is a square hole faced with masonry of small stones and said to be very deep; the writer's guide claimed to have descended it on a long rope till he could no longer breathe, without reaching the bottom.

Low down on the east side is the site of the theatre. No seats or stage-building are preserved, but the hollow is unmistakable, and a tiny piece of the cavea remains at the north corner.

¹ In just such a way Herodotus misunderstood what he was told of the Hittite figure in the Karabel pass near Smyrna; see *Aegean Turkey*, pp. 56-7. The historian knew little or nothing of the interior of Asia Minor from personal observation. Five stades is said to be a reasonable estimate of the length of the narrowest part of the gorge. Hamilton, who visited Colossae in 1856, conceived the idea that the underground channel of which Herodotus speaks was formed by the continual incrustation of the sides of the gorge by the lime-charged river till they met overhead, the tunnel thus created having later been destroyed by earthquakes. This ingenious conception has found no support from later investigators.

Other blocks are lying around. As it stands the theatre is very shallow, with room for only a dozen or fifteen rows, but the lower part is evidently buried.

On the other (north) side of the river was the necropolis. The tombs are sunk into the ground so close together that Hamilton at first mistook their lids for a pavement. Here also are (or were) visible the ruins of a large building which was perhaps the church of St. Michael, one of the most distinguished in Asia. For the rest the buildings of Colossae are, in Wheler's phrase, 'by the various and potent Engines of Time, and Fate, now no more to be seen'.

Short Bibliography

GENERAL

R. Chandler, *Travels in Asia Minor and Greece*, 3rd edition (London 1817).

Charles Fellows, *Asia Minor* (London 1839).

C. T. Newton, *A History of Discoveries at Halicarnassus, Cnidus and Branchidae* (London 1863); a shorter version, *Travels and Discoveries in the Levant* (London 1865).

D. Magie, *Roman Rule in Asia Minor* (Princeton 1950), invaluable to scholars.

Freya Stark, *The Lycian Shore* (London 1956), chapters 6–11.

A. Laumonier, *Les Cultes Indigènes en Carie* (Paris 1958), recommended especially to scholars.

Gwyn Williams, *Turkey* (London 1967), brief and deals with the coastal parts only.

E. Akurgal, *Ancient Civilisations and Ruins of Turkey* 2nd edition (Istanbul 1970), selective and deals briefly with Caria.

Hachette *World Guides*, *Turkey*.

CHAPTERS II–III. MYLASA

A. and T. Akarca, *Milâs* (Istanbul 1954), in Turkish.

CHAPTER IV. LABRAYNDA

Labraunda, Swedish Excavations and Researches (Lund 1969–).

CHAPTER V. IASUS

E. L. Hicks in *Journal of Hellenic Studies* vol. VIII; W. Judeich in *Athenische Mitteilungen* XV, 137; Italian Excavation Reports in *Annuario della Scuola in Atene* 1961 onwards.

CHAPTER VI. CINDYA AND BARGYLIA

G. E. Bean and J. M. Cook in *Annual of the British School in Athens* 52, 96–99.

CHAPTER IX. HALICARNASSUS

G. E. Bean and J. M. Cook in *Ann.Br.Sch.Ath.* 50, 85-108.

CHAPTER X. THE MYNDUS PENINSULA

W. R. Paton and J. L. Myres in *Journ.Hell.Stud.* XIV, 373-80 and XVI, 242-66; G. E. Bean and J. M. Cook in *Ann.Br.Sch.Ath.* 50, 108-65. W. Radt, *Siedlungen und Bauten auf der Halbinsel von Halikarnassos*, in *Istanbuler Mitteilungen*, Beiheft 3 (Tübingen 1970).

CHAPTER XI. SYANGELA

L. Robert, *Collection Froehner* I, 65-101; G. E. Bean and J. M. Cook in *Ann.Br.Sch.Ath.* 50, 112-15, 145-47, and 52, 89-96.

CHAPTER XII. CNIDUS

G. E. Bean and J. M. Cook in *Ann.Br.Sch.Ath.* 47, 171-212; new excavation reports in *American Journal of Archaeology* 1968 onwards.

CHAPTER XIII. THE RHODIAN PERAEA

P. M. Fraser and G. E. Bean, *The Rhodian Peraea* (Oxford 1954); J. M. Cook and W. H. Plommer, *The Sanctuary of Hemi-thea at Kastabos* (Cambridge 1966).

CHAPTER XIV. CAUNUS

M. Collignon in *Bulletin de Correspondance Hellénique* 1877, 338-46; A. Maiuri in *Annuario della Sc.Atene* III, 263ff.; G. E. Bean in *Journ.Hell.Stud.* 1953, 10-35 and 1954, 85-110; P. Roos in *Opuscula Atheninsia* VIII, 149-66 and IX, 60-68.

CHAPTER XV. ALABANDA

Etem Bey in *Comptes Rendus de l'Académie des Inscriptions* 1905-06.

CHAPTER XVI. ALINDA AND AMYZON

W. R. Paton and J. L. Myres in *Journ.Hell.Stud.* XVI, 238-42; E. Fabricius in *Altertümer von Aegae* (Berlin 1889),

27-30. (Amyzon) L. Robert in *Comptes Rendus de l'Acad. Inscr.* 1948, 431-2 and 1949, 304-6 and 1953, 403-15.

CHAPTER XVII. GERGA

G. Cousin in *Bull. Corr. Hell.* 1900, 28-31; A. Laumonier in *Bull. Corr. Hell.* 1934, 304-7 and 1936, 286-97; G. E. Bean in *Anatolian Studies* 1969, 179-82.

CHAPTER XVIII. TRALLES AND NYSA

K. Humann and W. Dörpfeld in *Athenische Mitteilungen* XVIII, 395ff.; W. von Diest, *Nysa ad Maeandrum* (Berlin 1913).

CHAPTER XIX. APHRODISIAS

Excavation Reports in *Amer. Journ. Arch.* 1963 onwards.

CHAPTER XX. HIERAPOLIS

Altertümer von Hierapolis (Berlin 1898); W. M. Ramsay, *Cities and Bishoprics of Phrygia* I, 84-121; Excavation Reports in *Annuario della Sc. Atene* 1961 onwards.

CHAPTER XXI. LAODICEIA AND COLOSSAE

W. M. Ramsay, *Cities and Bishoprics* I, 32-83; J. des Gagniers, *Laodicée du Lycos: Le Nymphée* (Paris 1969). (Colossae) W. M. Ramsay, *Cities and Bishoprics* I, 208-16.

TURKEY BEYOND
THE MAEANDER



- Ancient City and Town Sites
- ▲ Other Ancient Sites
- Modern Towns and Villages

- Good or tolerable roads
- Poor or bad roads
- + + + Railway

0 5 10 15 20 25 30 miles
0 10 20 30 40 kilometres
500 metre contours
Ancient names in capitals

Denizli 10 miles

Fethiye 13 miles



Index

- Acharaca, 217-20
 Actium, battle of, 28
 Ada, 24, 60, 108, 190
 Agasicles, 102
 Alabanda, 31, 34, 180-9
 Alabandus, 180
 Alinda, 190-8
 Alâzeytin (Syangela), 128-9
 Alexander, 24, 72; at Alinda, 190; at Halicarnassus, 107-8
 Alexandria, name of Alinda, 191
 Altinsivrisi, 154, 157
 Amnistus, 157
 Amorges, 71
 Amos, 158-9
 Amyntas, 181
 Amyzon, 198-200
 Antigonus III Doson, 25, 34, 59
 Antiocheia, name of Alabanda, 181
 Antiochus I, 88, 211, 247; II, 34, 59, 247; III, 26, 73, 108, 181
 Antipater, 238
 Antony, Mark, 27-8, 222, 248
 Apamea, treaty of, 26, 34
 Aphrodisias, 221-31
 Aphrodite, 221; of Aphrodisias, 223; of Cnidus, 140, 144-6, 150, 152
 Apollo: Careius, 241; Clarius, 241, 249-50; at Hierapolis, 234, 236; at Iasus, 74; Isotimus, 181-2; at Laodiceia, 255-7; Triopian, 20, 143-4
 Apollonius of Aphrodisias, 221
 Aqueduct: at Alabanda, 187; at Alinda, 197; at Laodiceia, 255-7
 Aridolis, 180-1
 Aristonicus, 27, 83, 88, 117
 Arlissis, 32
 Arselis, 31
 Artemis: Astias, 74; Cindyas, 82-3
 Artemisia: the elder, 24, 102; the younger, 105-7
 Athletics, 227
 Athymbrus, 211
 Attalus I, 25; III, 27
 Augustus, 29, 36, 95, 109
 Ayakh, site of Euromus, 45
 Baltalı Kapı, 39-41
 Bargylia, 26, 34, 82-7
 Bencik, 137
 Berber İni (B. Yatağı), 43-4
 Bridge, Greek, 149
 Brutus, 27-8
 Bybassus, 137, 162-3
 Byblis, 169
 Caesarea, name of Tralles, 209
 Calbis, R., 167-8
 Callipolis, 155-6
 Camping, 6
 Caria, Carians: boundaries, 18; customs, 20; federations, 21, 26; language, 18, 20; origin, 17, 18; 'thalassocracy', 17; tombs, 55; village-system, 20-1
 Caryanda, 126-7
 Cassius, 27-8, 109

- Castabus, 163-5
 Caunus, 23, 153, 166-79
 Cedraeae, 156-7
 Ceramus, 53-7
 Chaeremon, 212
 Chalctor, 35, 48-9
 Charonium at Acharaca, 218-20
 Chonae, 257
 Christianity, 30, 250, 257
 Chrysaoric League, 26, 34, 59-60, 89
 Chrysaoris, 89
 Cindya, 82-3
 Cleopatra, 28
 Cluvius, Roman banker, 35, 83, 183
 Cnidus, 23, 135-52; battle of, 71-2, 139
 Colossae, 257-9
 Cook, J. M., 51-2, 137, 162-5
 Corris, 59
 Crete, 17, 19, 169
 Ctesias, 146
 Cydrara, 235

 Damasus, 210
 Datça, 135-6
 Daurises, 22, 58
 Delian Confederacy, 22
 Delos, purification of, 17
 Diogenes, 116-17
 Dogs, 94
 Dolphin, 72-3, 206
 Dorian: hexapolis, 20, 102; migration, 20
 Dorion, musician, 39

 Egypt, Ptolemaic, 24
 Erine, 162
 Eskihişar, site of Stratoniceia, 90
 Eudoxus, 140, 146

 Eumenes, 25
 Eunuchs, 98, 236
 Eupolemus, 133
 Euromus, 35, 45-8
 Euthena, 157
 Euthydemus, 35-6

 Faustina, Empress, 215
 Figs, 167
 Fish, 65-6, 69, 168, 170
 Fruit, unhealthy, 166-7

 Gelibolu, 155-6
 Gerga, 201-7
 Gökçeler, site of Pedasa, 119
 Gordius, 122
 Gorgus, 72
 Goths, 29, 92
 Gümüşkesen, 43
 Gümüşlük, site of Myndus, 116

 Halicarnassus, 23, 24, 101-14, 133
 Harpagus, Persian general, 22, 137, 170
 Hecate, 94
 Hecatomnos: dynast, 23, 32, 44; priest, 59
 Helios, 182
 Hemithea, 163-5
 Hera, 99-100
 Heracleia, 23, 46
 Heraclides of Mylasa, 32
 Heraklion, 171, 175
 Hermogenes, 188-9
 Herodotus, 104
 Hierapolis, 232-46
 Homer (*Iliad*), 18
 Hybreas, 35-6
 Hyda (Hyla), 162
 Hydae, 35, 49-50
 Hyssaldomus, 23, 32, 44

- Iasus, 23, 69–81
 Idrias, 89
 Idrieus, 24, 58, 61–5
 Idyma, 154–5
 Imbrus, 167–8
 Incekemer, 201
 Ionian Revolt, 22
 Isotimus, epithet of Apollo,
 181–2

 Jews: at Hierapolis, 235; at
 Laodiceia, 248–9
 Julius Caesar, 209, 222

 Karakuyu, site of Chalcedon, 48
 King's Peace, 22–3
 Knights Hospitallers, 106; castle
 of, 113–14
 Kozlukuyu, site of Idyma, 155
 Kursunlu Yapı, 56

 Labienus, 28, 36, 89, 95, 183, 248
 Labraynda, 22, 33, 35, 58–68
 Lagina, 94–8
 Laodiceia, 247–57
 Latmus, 23
 Lelegians, 17, 18, 19, 105, 108,
 115, 221
 Library, at Nysa, 215–16
 Lide, Mt., 120
 Lipara Is., 136
 Loryma, 160–1
 Lycians, 19, 26, 31, 89, 170
 Lydians, 21
 Lygdamis I, 102; II, 103

 Macedonia, Kingdom, 24
 Madnasa, 124
 Magnesia, battle of, 26
 Manitas, 33
 Mark Antony, 27–8, 222, 248
 Marmaris, 157–8

 Marsyas, R., 89, 180
 Martyrium of St. Philip, 243–5
 Mausoleum, 105–8, 110; at
 Iasus, 81
 Mausolus, 23, 32, 52, 58, 61–4,
 72, 105–6, 116–18, 171, 176,
 192
 Memnon, 107–8
 Men, 223, 236
 Miletus, 18, 22, 70
 Minos, 17
 Mithridates VI, 27, 88, 95, 172
 Mobolla, 154
 Molpadia, 163
 Mopsus, 241
 Muğla, dialect, 18
 Mylasa, 23, 31–44
 Myndus, 23, 83, 109, 116–19
 Mysteries at Lagina, 96

 Naucratis, 138
 Newton, C. T., 101, 105, 135, 150
 Ninoe, name of Aphrodisias, 221
 Nysa, 211–20

 Octavian, 27–8 (*see also*
 Augustus)
 Oliatus, 31–2
 Olympichus, 25, 59, 61, 191
 Olymus, 35, 48
 Oracle, 38, 66
 Orontobates, 24, 107–8, 142
 Orthosia, battle of, 34
 'Oxhide' ingots, 113–14

 Pactyes, 155
 Pamukkale, site of Hierapolis,
 232
 Panamara, 98–100
 Pasanda, 179
 Pazarlık, 162–5
 Peçin Kale, 33, 50–3

- Pedasa, 19, 22, 119-22
 Pedasus, 19
 Pegasus, 83
 Pergamum, 25
 Persikon, fort, 171
 Petra, fort, 61
 Philip V, 25-6, 34, 60, 73, 83,
 120, 182
 Philippi, battle of, 27-8
 Philocles, 171
 Phocion, 33
 Phormio, boxer, 109
 Physcus, 157-8
 Pigres, dynast, 128
 Pisyre, 154
 Pixodarus, 24, 107
 Plague, 29
 Plarasa, 222
 Plutonium: at Acharaca, 218; at
 Hierapolis, 236-8
 Podaleirius, 159-60
 Polemo: the elder, 248; the
 younger, 251
 Polites, runner, 54
 Praxiteles, 140, 191
 Ptolemy I, 171; II, 108
 Pythodorus, 212
 Pythodorus, 210, 212
 Pythopolis, 211

 Quarry for Mausoleum, 118
 Quintus Cicero, 109

 Romans in Asia, 27, 29, 73
 Rhodians, 25, 54, 88, 106-7, 171-
 2; Rh. Peraea, 153-65

 St. Philip, 243-5
 Salamis, battle of, 102-3
 Salmacis, 103-4, 110-12
 Sarapis, 91
 Sarpedon, 19

 Seleuccia, name of Tralles, 208
 Seleucid Kingdom, 24
 Seleucus I, 88; II, 25, 34, 59
 Seven Wonders, 101, 146
 Side (Sibda), 124-6
 Sostratus, 146
 Spartans, 22, 71, 138
 Stadium: at Aphrodisias, 226-8;
 at Labraynda, 66; at
 Tralles, 211
 Strabo at Nysa, 211-12
 Stratoniceia, 31, 88-93, 153
 Stratoniceus, 33, 166
 Süleyman Kavağı, 43
 Sulla, 222
 Syangela, 23, 128-34
 Syrna, 159-60


 Taurupolis, 226
 Tekir, site of New Cnidus, 135,
 138
 Telmissus, 122-3, 125-6
 Temples:
 of Aphrodite, at Aphrodisias,
 223-5; at Cnidus, 144-6,
 150, 152
 of Apollo, at Alabanda, 188-9;
 at Amos, 159; at Cedraea,
 156; at Cnidus, 143; at
 Chalcetor, 49; at Hierapolis,
 234, 240-1; at Telmissus,
 122, 125-6
 of Apollo and Artemis, at
 Amyzon, 199; at Hydae,
 50; at Olymus, 48
 of Artemis, at Alabanda, 187-
 8; at Cindya, 82-3; at
 Iasus, 74
 of Hecate at Lagina, 94-8
 of Hemithea at Castabus,
 163-5
 of Rome and Augustus, 37, 42

- of Sarapis at Stratoniceia, 91-2
 of Zeus Carius, 37, 41, 51-2; of Z. Chrysaoreus, at Ceramus, 55; at Stratoniceia, 89; Z. at Iasus, 74; Z. Labrayndus, 61; Z. Lepsynus, 47; Z. Osogos, 38, 41-2; Z. Stratius, 58; Z. Zenoposeidon, 39, 42
 Termera, 123-4
 Termilae, 19
 Theangela, 128-34
 Theatres: at Alabanda, 185-6; at Alinda, 195; at Amos, 159; at Aphrodisias, 229; at Bargylia, 85; at Castabus, 164; at Caunus, 177; at Cedreae, 156; at Cnidus, 151; at Colossae, 258-9; at Euromus, 47; at Hierapolis, 235, 242-3; at Iasus, 79; at Laodiceia, 253-4; at Mylasa, 42; at Nysa, 214; at Stratoniceia, 92; at Tralles, 210
 Thera, 154
 Thyssanus, 161-2
 Tissaphernes, 71
 Torrhebus, 241
 Tralles, 208-11
 Triopium, 136, 138, 142-4
 Tymnus, 162
 Underwater finds, 113
 Uranium, 126
 Verres, 109
 Vitruvius, 104, 109-10
 White Pillars, 21
 Wine: of Cnidus, 147; of Myndus, 117
 Wonders of the World, 101, 146
 Wool, 250
 Xanthians, 170
 Xerxes, 22, 102-3, 257
 Yerkesik, site of Thera, 154
 Zeno, 248
 Zenoposeidon, 39
 Zeus: at Iasus, 74; at Panamara, 100; Z. Aseis, 249; Z. Bozius, 236; Z. Carius, 17, 21, 37, 41, 51-2; Z. Chrysaoreus, 89, 181; Z. Labrayndus, 37-8, 60; Z. Larasius, 209; Z. Lepsynus, 47; Z. Nineadius, 221, 223; Z. Osogos, 38-9; Z. Panamarus, 99; Z. Spaloxus, 223; Z. Stratius, 37, 58; Z. Troius, 236; Z. Zenoposeidon, 42

62701



*Printed in Great Britain by
W & J Mackay & Company Limited
Chatham, Kent*



~~cat~~
27/10/77

Caria - Archaeology
Archaeology - Caria

"A book that is shut is but a block"

CENTRAL ARCHAEOLOGICAL LIBRARY

GOVT. OF INDIA
Department of Archaeology
NEW DELHI.

Please help us to keep the book
clean and moving.
